

819 N. Cass Street, Milwaukee WI



East Side of the Building (Front of the Building ) – Work Phase 4 of 4



Remove and replace as needed, any rotten wood trim pieces with matching size and profile. Repaint all wood trim on top dormer in the existing paint color.

Infill cracks or voids in stucco and repaint to match existing color.



North Side of the Building, (Work Phase 1 of 4)



Remove all wood trim and replace with new wood matching profile and size, Repaint all trim to match existing color.

Remove all stucco that is damaged or cracked, replacing sections that are missing. Repaint all stucco on top dormer matching the existing color.

West Side of the Building, (Work Phase 2 of 4)



Patch cracked Stucco areas and repaint to match existing color.

Remove rotten wood trim and replace with wood trim pieces with matching size and profile. Repaint matching existing color.



South Side of the Building, (Work Phase 3 of 4).

No Pictures of the top dormer available right now, however the scope remains the same, to replace rotten wood trim and repairs any cracks or voids in the stucco.

