WR Construction

Wade Ritchie 7359 N Vine St. Lannon, WI 53046 (414) 748-0084

Estimate

Submitted on 05/28/2024

Estimate for

Bill Brauer and Isabella Jaegersbe Bill Brauer and Isabella Jaegersbe

 214 E Vine St
 Project

 Milwaukee, WI 53212
 Wood stairs and 4' concrete steps to front door

Estimate #

	Item	Description	Unit price	Total price
Wood de	eck/stairs	 1.)Demo and clean up and haul away of all current deck and stairs. Removal of current stone steps to be left on-site for home owners use. 2.)12"x48" Sonotubes installed and filled with concrete to form the base for deck and stairs 3.)Old ledger board removed and new installed to house rim joist 4.)Flashing installed to divert rain and snow melt away from house walls 5.)Pressure Treated CedarTone wood deck system including 4"x4" posts, 2"x8" framing, 2"x12" stair stringers, railings and spindles, as well as 5/4"x6" WeatherShield decking boards. 6.)Fasteners are galvenized or dipped to increase longevity during exposure to outdoor elements 7.)CAMO brand hidden fastener screws on surface boards for reduced splitting, cracking and easier maintenence 8.)36" tall Pressure Treated CedarTone Deck Hand Rail system installed 9.)Joist hangers and corner brackets galvenized for strength and longevity 	\$2,250.00	\$2,250.00
Labor		Demo, digging, deck and stair install, and clean up	\$1,600.00	\$1,600.00
Concrete steps		 Remove old stones and set aside for owners use nes built for concrete formation centered with new wood stairs led of current materials to suit 4" thick concrete walk and steps 4.)Concrete poured to a minimum thickness of 4" edged and seemed with a brushed finish for a non-slip surface 6.)Removal and disposal of forms and any concrete waste 	\$1,050.00	\$1,050.00
Labor		Grading, Form construction, Flat Work and Clean Up	\$1,200.00	\$1,200.00
Notes:	Thank you for considering WR Construction for your next home project. If you have any questions please don't hesitate to reach out. Estimate is valid for 90 days from the date of submission. 50% of project is due up front to order materials and schedule project dates		Subtotal Adjustments	\$6,100.00 \$0.00
			\$6	,100.00