




**14 DECEMBER 2011**



**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202

**striegel-agacki studio**

architecture | milwaukee - los angeles






**SITE PHOTOS**

**VIEW NORTH UP JACKSON**

**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles





**JACKSON STREET: WEST SIDE ADJACENT TO 1601**




**JACKSON STREET: EAST SIDE ACROSS FROM SITE**

**CONTEXT**

**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



BUILDING YOUR VISION

striegel-agacki studio

architecture | milwaukee - los angeles





**NW CORNER (1601 N JACKSON)**



**NE CORNER**



**SW CORNER**




**SE CORNER**

**JACKSON - PLEASANT INTERSECTION**


**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles






**BASEMENT LEVEL PLAN** (1" = 16')


**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles






**ENTRY LEVEL PLAN** (1" = 16')


**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles






**TYPICAL FLOOR 2 THROUGH 4** (1" = 16')

**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles





STEEL GUARDRAIL W/ GLASS PANEL IN-FILL

PAINTED STEEL CHANNEL, TYPICAL

BRICK 'MIDDLE'

CEMENTITIOUS PANEL 'TOP'


IN-FILL 'MIDDLE', TYPICAL

STEEL GUARDRAIL W/ STEEL MESH IN-FILL

CONCRETE 'BASE'

CONCRETE 'BASE'

BRICK 'BASE'



**JACKSON - PLEASANT STREET CORNER: 34 UNIT BUILDING**


**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202

striegel-agacki studio

architecture | milwaukee - los angeles






**BRICK**



**METAL PANEL (ALT)**




**RESIN PANEL (ALT)**




**METAL PANEL (ALT)**



**GLASS IN-FILL**



**POURED CONCRETE**



**BRICK**



**CEMENTITIOUS PANEL, PAINTED**



**CEMENTITIOUS PANEL**



**WIRE MESH IN-FILL**

**BASE:**

**MIDDLE:**

**IN-FILL MIDDLE:**


**TOP:**

**GUARDRAILS:**

**EXTERIOR MATERIAL PALETTE**

**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202




striegel-agacki studio  
architecture | milwaukee - los angeles





**SOUTH ELEVATION**




**EAST ELEVATION**

**EXTERIOR ELEVATIONS**

**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles





**NORTH ELEVATION**




**WEST ELEVATION**

**EXTERIOR ELEVATIONS**

**1601 JACKSON APARTMENTS**

1601 North Jackson Street Milwaukee, Wisconsin 53202



striegel-agacki studio  
architecture | milwaukee - los angeles







CONTRACTOR IS REQUIRED TO CONTACT DIGGERS HOTLINE TOLL FREE TO OBTAIN LOCATION OF UNDERGROUND UTILITIES PRIOR TO BEGINNING THE WORK. WISCONSIN STATUTE 182.0715 REQUIRES NOTICE TO THE PUBLIC OF THE LOCATION OF UNDERGROUND UTILITIES. CALL DIGGERS HOTLINE 1-800-942-8511

NOTE: EXISTING UNDERGROUND UTILITY INFORMATION WAS OBTAINED SURVEYING ASSOCIATES, INC. FROM AVAILABLE RECORDS. THE ENGINEER MAKES NO GUARANTEE AS TO THE ACCURACY OF THIS INFORMATION. VERIFICATION TO THE SATISFACTION OF THE CONTRACTOR OF ALL UNDERGROUND UTILITIES, WHETHER OR NOT SHOWN ON THE PLANS, SHALL BE ASSUMED AS A CONDITION OF THE CONTRACT. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN LOCATION OF UTILITIES IN THE FIELD AND LOCATIONS SHOWN ON THE PLANS.

LANDSCAPE PLANTING SCHEDULE					
QUANTITY	BOTANICAL NAME	COMMON NAME	PLANTED SIZE	ROOT	COMMENT
15	ROSA X PURPLE PAVEMENT	PURPLE PAVEMENT SHRUB ROSE	18"	3 GAL	#1 WASHED
1,933 S.F. OF GRASS TERRACE BETWEEN SIDEWALK AND BACK OF CURB					

# PROPOSED LANDSCAPE PLAN



**GARLAND ALLIANCE LANDSCAPE ARCHITECTS**  
 3707 N. RICHARDS ST., STE 200  
 MILWAUKEE, WI 53242  
 PHONE: (262) 796-4480  
 EMAIL: lin@garlandalliance.com



**TRIO CIVIL ENGINEERING**  
 17700 W. CAPITOL DRIVE  
 BROOKFIELD, WI 53045  
 PHONE: (262) 796-4480  
 FAX: (262) 796-4480  
 EMAIL: j.purdick@trioengineering.com

**PROJECT:**  
**1601 N. JACKSON STREET**  
 1601 N. JACKSON STREET  
 Milwaukee, Wisconsin  
**BY:**  
 Dermond Property Investments LLC  
 757 N. Water Street, Milwaukee, WI 53202

**PLAN DATE:**  
 DECEMBER 22, 2011

**JOB NUMBER:**  
 11032

**DESCRIPTION:**  
 PROPOSED LANDSCAPE PLAN

**L10**

**SHEET**



# PROPOSED 1601 N. JACKSON STREET BUILDING

## N. JACKSON STREET & E. PLEASANT STREET

### CITY OF MILWAUKEE, WI

#### PROJECT NOTES

##### EXISTING CONDITIONS AND DEMOLITION NOTES:

1. CONTRACTOR TO FIELD VERIFY EXISTING SITE PRIOR TO BIDDING. CONTRACTOR SHALL REMOVE, RELOCATE, REPLACE OR DEMOLISH ANY OTHER ITEMS AS DIRECTED BY THE CONSTRUCTION MANAGER.

##### SITE NOTES:

1. THE PROPOSED CIVIL PLANS ILLUSTRATE SITE IMPROVEMENTS ASSOCIATED WITH THE NEW BUILDING CONSTRUCTION. CONTRACTOR TO REFER TO ARCHITECTURAL PLANS FOR ADDITIONAL CONSTRUCTION INFORMATION.
2. CONTRACTOR TO OBTAIN ALL NECESSARY PERMITS AND APPROVALS FOR CONSTRUCTION.

##### GRADING AND EROSION CONTROL NOTES:

1. SEE PLANS FOR EROSION CONTROL DETAILS & CONSTRUCTION SEQUENCE.
2. THE PROPOSED BUILDING PROJECT WILL DISTURB APPROXIMATELY 0.3 ACRES OF LAND, THEREFORE UNDER NR 151 AND NR 216 PERMITTING REQUIREMENTS ARE NOT APPLICABLE. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY NECESSARY CONSTRUCTION SITE AND/OR EROSION CONTROL PERMITS FROM THE CITY OF MILWAUKEE.

##### UTILITY NOTES:

1. OWNER AND CONTRACTOR TO COORDINATE WITH UTILITY COMPANY REGARDING OVERHEAD UTILITY LINE PROTECTION AND/OR RELOCATION ALONG WEST ALLEY.
2. CONTRACTOR TO FIELD VERIFY EXISTING UNDERGROUND UTILITIES ON SITE. CONNECTIONS AND VERIFY PROPOSED UTILITY ROUTE IS CLEAR TO COME OF ALL EXISTING UTILITIES AND OTHER OBSTRUCTIONS PRIOR TO CONSTRUCTION. COSTS INCURRED FOR FAILURE TO DO SO SHALL BE THE CONTRACTORS RESPONSIBILITY.
3. CONTRACTOR SHALL PROVIDE NOTIFICATION TO UTILITY OWNERS (INCLUDING SEWER AND WATER) AT LEAST 72 HOURS PRIOR TO EXCAVATION. ALL PROPOSED WATERMAIN PIPE SHALL BE C900 PVC FOR PIPE DIAMETERS OF 6" OR GREATER UNLESS OTHERWISE NOTED.
4. ALL UTILITIES SHALL BE INSTALLED WITH PLASTIC COATED TRACER WIRE (10 TO 14 GAUGE SOLID COPPER, OR COPPER COATED STEEL WIRE). PLASTIC WIRE MAY BE TAPPED TO PLASTIC WATER OR DRAIN PIPE. IF ATTACHED THE TRACER WIRE SHALL BE SECURED EVERY 6 TO 20 FEET AND AT ALL BENDS. TRACER WIRE SHALL HAVE ACCESS POINTS AT LEAST EVERY 300 FEET.
5. SEE PLANS FOR ADDITIONAL UTILITY SPECIFICATIONS AND DETAILS.
6. SITE UTILITY CONTRACTOR SHALL RUN SANITARY SERVICE TO A POINT WHICH IS A MINIMUM 5 FEET FROM THE EXTERIOR WALL OF FOUNDATION. SITE UTILITY CONTRACTOR SHALL RUN WATER SERVICE TO A POINT WITHIN THE FOUNDATION SPECIFIED BY THE PLUMBING PLANS. CONTRACTOR TO CUT AND CAP WATER SERVICE 12" ABOVE FINISH FLOOR ELEVATION (OR AS OTHERWISE DIRECTED BY THE CONSTRUCTION MANAGER).

##### LANDSCAPE NOTES:

1. CONTRACTOR SHALL SEED, FERTILIZE AND MULCH LAWN AREAS AND DISTURBED AREAS AFTER COMPLETION OF CONSTRUCTION.



EXISTING SITE PHOTOGRAPH



LOCALITY MAP

NORTH PART OF THE WEST 1/2 OF THE SOUTHWEST 1/4 OF SECTION 21, TOWN 7 NORTH, RANGE 22 EAST, IN THE CITY OF MILWAUKEE, COUNTY OF MILWAUKEE, STATE OF WISCONSIN

#### LEGEND


- X 36.00 - DENOTES EXISTING SPOT ELEVATION
- P/L - DENOTES PROPERTY LINE
- - DENOTES CATCH BASIN
- - DENOTES UTILITY POLE
- ⊗ - DENOTES WATER VALVE
- ⊗ - DENOTES GAS VALVE
- ⊗ - DENOTES ELECTRIC MANHOLE
- ⊗ - DENOTES WEP/CO MANHOLE
- ⊗ - DENOTES SEWER MANHOLE
- - DENOTES OVERHEAD UTILITY
- - DENOTES UNDERGROUND GAS
- - DENOTES UNDERGROUND WATER
- - DENOTES UNDERGROUND TELECOMMUNICATION
- - DENOTES UNDERGROUND ELECTRIC
- - DENOTES UNDERGROUND SANITARY SEWER
- - DENOTES UNDERGROUND WATER
- - DENOTES COMBINED SEWER
- - DENOTES STORM SEWER
- - DENOTES SANITARY SEWER
- - DENOTES UNDERGROUND ELECTRIC
- - DENOTES UNDERGROUND TELECOMMUNICATION
- - DENOTES UNDERGROUND WATER
- - EXTERIOR PROPERTY LINE
- - PROPOSED STORM
- - PROPOSED 6" SANITARY
- - PROPOSED 6" WATER
- - PROPOSED DRAINAGE FLOW
- - PROPOSED SPOT ELEVATIONS (FLOW LINE OF CURB UNLESS OTHERWISE SPECIFIED)
- - PROPOSED GATE VALVE
- - PROPOSED SANITARY CLEANOUT

#### CIVIL PLAN SHEET LIST

- C1.0 - EXISTING SITE PLAN
- C1.1 - PROPOSED SITE PLAN
- C1.2 - MASTER GRADING & EROSION CONTROL PLAN
- C1.3 - UTILITIES PLAN

#### LANDSCAPE PLAN SHEET LIST

- L1.0 - PROPOSED LANDSCAPE PLAN



strigel-agacki studio  
architects  
milwaukee - los angeles



17700 W. CAPITOL DRIVE  
BROOKFIELD, WI 53045  
PHONE: (262) 796-1480  
FAX: (262) 796-1481  
EMAIL: j.pudzelko@strigelagacki.com



**PROJECT:**  
**1601 N. JACKSON STREET**  
1601 N. JACKSON STREET  
Milwaukee, Wisconsin  
**BY:**  
Dermond Property Investments LLC  
757 N. Water Street, Milwaukee, WI 53202

**PLAN DATE:**  
DECEMBER 22, 2011

**JOB NUMBER:**  
11032

**DESCRIPTION:**  
COVER SHEET


SHEET

T1



**PLAT OF SURVEY**  
**ALL OF LOTS 16, 17 AND 18 NORTH OF STREET, BLOCK E, HATHAWAY'S SUBDIVISION AS**  
**altered and amended by Otis B. Hopkins after the vacation of a portion thereof by Act of the**  
**Legislature located in the North part of the West 1/2 of the Southeast 1/4 of Section 21, Town 7 North,**  
**Range 2 East, in the City of Milwaukee, Milwaukee County, Wisconsin.**  
 Address: 1601 N. Jackson Street and 522 - 526 E. Pleasant Street

# EXISTING SITE PLAN



## EXISTING SITE DATA

LOT ZONED:	LB2 District
LOT AREA:	9,995.1 S.F. (0.23 Acres)
EXISTING PAVEMENT & SIDEWALK	7,276.1 S.F. (0.167 Acres)
EXISTING BUILDING	2,496.6 S.F. (0.057 Acres)
TOTAL IMPERVIOUS AREA:	9,772.7 S.F. (0.224 Acres) [97.78% of Site]
TOTAL OPEN SPACE:	222.4 S.F. (0.005 AC.) [2.22% of Site]


## LEGEND

- X 38.00 - DENOTES EXISTING SPOT ELEVATION
- P/L - DENOTES PROPERTY LINE
- - DENOTES CATCH BASIN
- - DENOTES UTILITY POLE
- ⊗ - DENOTES WATER VALVE
- ⊗ - DENOTES GAS VALVE
- ⊗ - DENOTES ELECTRIC MANHOLE
- ⊗ - DENOTES WEP/O MANHOLE
- ⊗ - DENOTES SEWER MANHOLE
- ⊗ - DENOTES OVERHEAD UTILITY
- ⊗ - DENOTES UNDERGROUND GAS
- ⊗ - DENOTES COMBINED SEWER
- ⊗ - DENOTES SANITARY SEWER
- ⊗ - DENOTES UNDERGROUND ELECTRIC
- ⊗ - DENOTES UNDERGROUND TELECOMMUNICATION
- ⊗ - DENOTES UNDERGROUND WATER




2554 N. 100TH STREET  
 P.O. BOX 26596  
 WAUWATOSA, WISCONSIN 53226  
 (414) 257-2212 FAX: (414) 257-2443  
 FREDERICK W. SHIBLSKI R.L.S.

**NOTES:**  
 \* THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.\*



CONTRACTOR IS REQUIRED TO CONTACT DIGGERS HOTLINE TOLL FREE TO OBTAIN LOCATION OF UNDERGROUND UTILITIES PRIOR TO COMMENCING THE WORK. WISCONSIN STATUTE 182.0715 REQUIRES MIN. OF 3 WORK DAYS NOTICE BEFORE YOU EXCAVATE. CALL DIGGERS HOTLINE 1-800-242-8511





	<b>strigel-agacki studio</b> architects milwaukee - los angeles		17700 W. CAPITOL DRIVE BROOKFIELD, WI 53045 PHONE: (262) 796-1480 FAX: (262) 784-1481 EMAIL: j.pudelo@strigelagacki.com		<b>PROJECT:</b> <b>1601 N. JACKSON STREET</b> 1601 N. JACKSON STREET Milwaukee, Wisconsin <b>BY:</b> Dermond Property Investments LLC 757 N. Water Street, Milwaukee, WI 53202
					<b>PLAN DATE:</b> DECEMBER 22, 2011
<b>JOB NUMBER:</b> 1032	<b>DESCRIPTION:</b> EXISTING SITE PLAN	<b>SHEET</b> <b>C10</b>			






CONTRACTOR IS REQUIRED TO CONTACT DIGGERS HOTLINE TOLL FREE TO OBTAIN LOCATION OF UNDERGROUND UTILITIES PRIOR TO THE START OF ANY WORK. IN ACCORDANCE WITH WISCONSIN STATUTE 182.0715 CALL DIGGERS HOTLINE 1-800-242-8511

NOTE: EXISTING UNDERGROUND UTILITY INFORMATION WAS OBTAINED SURVEYING ASSOCIATES, INC. FROM AVAILABLE RECORDS. THE ENGINEER MAKES NO GUARANTEE AS TO THE ACCURACY OF THIS INFORMATION. VERIFICATION TO THE SATISFACTION OF THE CONTRACTOR OF ALL UNDERGROUND UTILITIES, WHETHER OR NOT SHOWN ON THE PLANS, SHALL BE ASSUMED AS A CONDITION OF THE CONTRACT. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN LOCATION OF UTILITIES IN THE FIELD AND LOCATIONS SHOWN ON THE PLANS.






# PROPOSED SITE PLAN



## SITE DATA

EXISTING ZONING:	LB2
PROPOSED ZONING:	DPD
* Sec 295-05-2-f: The lot coverage standards set forth in table 295-05-2 relate to the proportion of a lot occupied by principal buildings. Accessory structures shall not be included when determining principal building lot coverage)	
LOT AREA:	9,995.1 S.F. (0.23 Acres)
BUILDING FOOTPRINT (maximum):	9,722.3 S.F. (0.223 Acres) [97.27% of Lot]
PROPOSED PAVEMENT & SIDEWALK: - Outside building footprint:	47.8 S.F. (0.001 Acres) [0.48% of Lot]
TOTAL IMPERVIOUS AREA:	9,770.1 S.F. (0.224 Acres) [97.75% of Lot]
TOTAL OPEN SPACE:	225 S.F. (0.0260 Acres) [2.25% of Lot]
PARKING SPACES: - All parking within building	34 SPACES ON SITE
OPEN SPACE CREATED IN RIGHT-OF-WAY:	2,093 S.F. (0.048 Acres)
STORM WATER MANAGEMENT is not required per MMSD and City requirements because the total land disturbance is less than 1 acre and no additional impervious area of 0.5 acres or more is added (the project has no net increase in impervious area).	



**strigel-agacki studio**  
architectural  
milwaukee - los angeles



17700 W. CAPITOL DRIVE  
BROOKFIELD, WI 53045  
PHONE: (262) 796-1480  
FAX: (262) 796-1481  
EMAIL: j.pudenko@strigelagacki.com



**PROJECT:**  
**1601 N. JACKSON STREET**  
1601 N. JACKSON STREET  
Milwaukee, Wisconsin  
**BY:**  
Dermond Property Investments LLC  
757 N. Water Street, Milwaukee, WI 53202

**PLAN DATE:**  
DECEMBER 22, 2011

**JOB NUMBER:**  
11032


**DESCRIPTION:**  
PROPOSED SITE PLAN

**SHEET**

**C11**




# MASTER GRADING & EROSION CONTROL PLAN



## CONSTRUCTION SEQUENCE PLAN

1. INSTALL SILT FENCE, CONSTRUCTION FENCE AND TRACKING PAD.
2. RAZE EXISTING BUILDING AFTER SECURING ALL REQUIRED PERMITS FROM CITY. INCLUDES DISCONNECTING EXISTING UTILITIES AND PROPERLY DISPOSING OF DEMOLITION MATERIAL.
3. REMOVE EXISTING ON-SITE PAVEMENT AND WALLS AS NEEDED FOR BUILDING CONSTRUCTION.
4. ROUGH GRADE SITE AND REMOVE EXCESS SPILLS.
5. RELOCATE UTILITY LINES ALONG ALLEY AND OTHER AREAS AS NECESSARY FOR BUILDING CONSTRUCTION.
6. CONSTRUCT BUILDING.
7. INSTALL SANITARY SEWER AND WATER LATERALS. CONNECT BUILDING STORM SEWER DRAIN TO CATCH BASIN IN ALLEY. CONTACT CITY AND/OR WMSD PRIOR TO CONNECTING TO THE EXISTING SYSTEMS.
8. INSTALL NEW GAS/ELECTRIC/TELEPHONE UTILITIES PER PLANS BY OTHERS. REMOVE EXISTING DRIVEWAY, SIDEWALK AND CURB SECTIONS WITHIN PUBLIC RIGHT-OF-WAY (WITH CITY PERMIT AND PRIOR NOTICE).
9. INSTALL STONE BASE PAVEMENT AND SIDEWALK PER PLAN.
10. SPREAD TOPSOIL, SEED, MULCH AND STABILIZE DISTURBED AND PROPOSED OPEN SPACE AREAS.
11. INSTALL LANDSCAPING PER PLAN.
12. REMOVE ANY REMAINING SILT FENCE AND CONSTRUCTION FENCE.
13. NOTE THAT CONSTRUCTION MANAGER MAY MODIFY THIS SEQUENCE PLAN TO BEST SUIT THE NEEDS OF THE PROJECT.

## LEGEND




## STANDARD DETAIL DRAWINGS:

WISCONSIN DEPARTMENT OF NATURAL RESOURCES  
CONSTRUCTION EROSION CONTROL STANDARDS  
1059 - SILT FENCE  
1067 - STONE TRACKING PAD AND THE WASHING  
1068 - STORM DRAIN INLET PROTECTION


## EROSION CONTROL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION, STATE OF WISCONSIN, LATEST EDITION, UNLESS OTHERWISE CALLED FOR ON THE PLANS, SPECIFICATIONS OR SPECIAL.
2. EROSION CONTROL MEASURES SPECIFIED ON THIS PLAN SHALL MEET THE DESIGN CRITERIA, STANDARDS AND SPECIFICATIONS AS SET FORTH IN THE WISCONSIN DEPARTMENT OF NATURAL RESOURCES TECHNICAL STANDARDS.
3. ALL EROSION CONTROL DEVICES (I.E. SILT FENCE, GRAVEL ENTRANCE, ETC.) SHALL BE INSTALLED PRIOR TO COMMENCING ALL GRADING OR UTILITY CONSTRUCTION.
4. ALL ACTIVITIES ON THE SITE SHALL BE CONDUCTED IN A LOGICAL SEQUENCE TO MINIMIZE THE AREA OF BARE SOIL EXPOSED AT ANY ONE TIME. REFER TO THE CONSTRUCTION SEQUENCING PLAN FOR ADDITIONAL INFORMATION.
5. THE OWNER IS RESPONSIBLE FOR OBTAINING A GRADING AND/OR EROSION CONTROL PERMIT (OR ANY OTHER APPLICABLE PERMITS) PRIOR TO CONSTRUCTION.
6. THE OWNER WILL PROVIDE ALL SUPERVISING AND CONSTRUCTION STAKING FOR THIS PROJECT. THE CONTRACTOR SHALL EXERCISE CARE AND DILIGENCE IN PROTECTING THE SAME. ANY EXPENSE INCURRED FOR ADDITIONAL RESTAKING CAUSED BY CONTRACTOR'S NEGLIGENCE MAY BE CHARGED TO THE CONTRACTOR AND DEDUCTED FROM THE Sums DUE HIM UNDER THIS CONTRACT.
7. THE CONTRACTOR SHALL NOTIFY DIGGERS HOTLINE: ALL UTILITIES CITY DEPARTMENTS, AND GOVERNMENT UNITS WHOSE PROPERTY MAY BE AFFECTED BY THE CONTRACTOR'S OPERATIONS AT LEAST THREE (3) DAYS BEFORE BREAKING GROUND. PUBLIC ROADS SHALL NOT BE CLOSED TO TRAFFIC AT ANY TIME. ALL INGRESS AND EGRESS TRAFFIC TO THE PROJECT SHALL BE LIMITED TO THE EXISTING AND/OR GRAVEL ENTRANCE TO THE PROPERTY.
8. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE CLEANLINESS OF THE PROJECT AND PUBLIC ROADWAYS DURING CONSTRUCTION PER THE REQUIREMENTS SET FORTH BY THE LOCAL AND COUNTY AGENCIES. STREETS SHALL BE KEPT FREE OF SILT OR DIRT TRACKED FROM AREAS UNDER CONSTRUCTION BY SWEEPING OR OTHER APPROPRIATE MEASURES. DUST TREATMENT, CONSTRUCTION SCHEDULING OR OTHER APPROPRIATE METHODS.
9. MULCH SHALL BE PLACED AROUND THE INLET STRUCTURE UNTIL THE FRAME AND GRATE HAS BEEN SET IN PLACE. FREQUENT INSPECTION AND TIMELY MAINTENANCE IS REQUIRED.
10. UPON COMPLETION OF THE WORK AS SPECIFIED, RESPAWD SIX (6") INCHES OF SALVAGED TOPSOIL OVER ALL DISTURBED AREAS AND PROVIDE SEED, FERTILIZER AND MULCH PER THE STANDARD SPECIFICATIONS.
11. ALL DISTURBED AREAS INSIDE AND OUTSIDE OF THE ROAD RIGHT OF WAY SHALL BE REVEGETATED WITHIN SEVEN (7) DAYS AFTER BEING DISTURBED. HIGHWAY MIX #40 SHALL BE USED FOR SEEDING WITH AN APPLICATION RATE OF 2.5 LBS./1000 SF.
12. ALL EROSION CONTROL DEVICES SHALL BE ROUTINELY INSPECTED EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF A RAINFALL GREATER THAN 0.5 INCHES. CONTRACTOR IS REQUIRED TO PERFORM INSPECTIONS, KEEP A LOG, AND REPAIR BMP'S AS NEEDED.



CONTRACTOR IS REQUIRED TO CONTACT DIGGERS HOTLINE TOLL FREE TO OBTAIN LOCATION OF UNDERGROUND UTILITIES PRIOR TO BEGINNING THE WORK. THE WISCONSIN STATUTE 182.0715 REQUIRES THE CONTRACTOR TO CALL DIGGERS HOTLINE 1-800-942-8511

NOTE: EXISTING UNDERGROUND UTILITY INFORMATION WAS OBTAINED SURVEYING ASSOCIATES, INC. FROM AVAILABLE RECORDS. THE ENGINEER MAKES NO GUARANTEE AS TO THE ACCURACY OF THIS INFORMATION. VERIFICATION TO THE SATISFACTION OF THE CONTRACTOR OF ALL UNDERGROUND UTILITIES, WHETHER OR NOT SHOWN ON THE PLANS, SHALL BE ASSUMED AS A CONDITION OF THE CONTRACT. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN LOCATION OF UTILITIES IN THE FIELD AND LOCATIONS SHOWN ON THE PLANS.



<p><b>PROJECT:</b> <b>1601 N. JACKSON STREET</b> 1601 N. JACKSON STREET Milwaukee, Wisconsin</p> <p><b>BY:</b> Dermond Property Investments LLC 757 N. Water Street, Milwaukee, WI 53202</p>		<p><b>PLAN DATE:</b> DECEMBER 22, 2011</p>	<p><b>JOB NUMBER:</b> 1032</p>	<p><b>DESCRIPTION:</b> MASTER GRADING &amp; EROSION CONTROL PLAN</p> <p><b>SHEET</b> <b>C12</b></p>	<p><b>TRIO</b> DESIGN, LAND SURVEYING &amp; CIVIL ENGINEERING</p> <p>17700 W. CAPITOL DRIVE BROOKFIELD, WI 53045 PHONE: (262) 796-1480 FAX: (262) 796-1481 EMAIL: pdudek@trioengineering.com</p>	<p><b>strigel-agacki studio</b> architectural interior - los angeles</p>	<p><b>WISCONSIN</b> PROFESSIONAL ENGINEER JOSHUA D. PUDILKO E-39420 WV410754</p>
--	--	--	------------------------------------	---	--	--	--





CONTRACTOR IS REQUIRED TO CONTACT DIGGERS HOTLINE TOLL FREE TO OBTAIN LOCATION OF UNDERGROUND UTILITIES PRIOR TO COMMENCEMENT OF ANY WORK. MISSOURI STATE 182.0715 REQUIRES CONTRACTOR TO CALL DIGGER'S HOTLINE 1-800-249-8511

# UTILITIES PLAN

## SANITARY SEWER & WATERMAIN NOTES

- SANITARY SEWER**
- ALL PVC SEWER PIPE SHALL MEET THE REQUIREMENTS SET FORTH IN SECTION 8.10.0 (SSSWCW).
  - ALL SANITARY SEWER LATERALS (OUTSIDE OF BUILDINGS) SHALL BE MADE OF GASKETED PVC FITTINGS MEETING ASTM D-3034, SDR 35. TRACER WIRE IS REQUIRED FOR ALL SANITARY SEWER LATERALS.

## WATERMAIN



- ALL 6" PVC WATERMAIN CONSTRUCTED AS PART OF THIS PLAN SHALL BE PVC, C-900, CLASS 150 (DR18). PVC PIPE SHALL HAVE PUSH-ON JOINTS WITH RUBBER GASKET.
- ALL WATERMANS (AND SERVICES) CALLED FOR ON THESE PLANS ARE TO BE INSTALLED WITH CLASS "B" BEDDING AS SPECIFIED IN CH. 4.3.0, LAYING OF WATERMAIN, AND FILE NO. 36, PART VII (SSSWCW).
- BLUE TRACER WIRE IS REQUIRED FOR ALL WATERMAIN LATERALS.

## TRACER WIRE NOTE

- CONTRACTOR SHALL INSTALL PLASTIC COATED TRACER WIRE (10 TO 14 GAUGE SOLID COPPER, OR COPPER COATED STEEL WIRE) PER COMM 82.30(1)(H). PLASTIC WIRE MAY BE TAPED TO PLASTIC DRAIN PIPE. IF ATTACHED, THE TRACER SHALL BE SECURED EVERY 6 TO 20 FEET AND AT ALL BENDS. TRACER WIRE SHALL HAVE ACCESS POINTS AT LEAST EVERY 300 FEET.

## STORM SEWER NOTES

- ALL PVC STORM SEWER PIPE SHALL BE ASTM D-3024, SDR 35. SCHEDULE 40 PIPE SHALL BE INSTALLED FOR ALL PIPE WITHIN THE PROPOSED BUILDING FOOTPRINT, PER MANUFACTURER SPECIFICATIONS.
- CONTRACTOR SHALL INSTALL PLASTIC COATED TRACER WIRE (10 TO 14 GAUGE SOLID COPPER, OR COPPER COATED STEEL WIRE). PLASTIC WIRE MAY BE TAPED TO PLASTIC DRAIN PIPE. IF ATTACHED, THE TRACER SHALL BE SECURED EVERY 6 TO 20 FEET AND AT ALL BENDS. TRACER WIRE SHALL HAVE ACCESS POINTS AT LEAST EVERY 300 FEET. CONNECT TO BUILDING STORM SEWER CONVEYANCE PIPING PER COMM 82 AND CITY OF MILWAUKEE SPECIFICATIONS AND REQUIREMENTS.



**strigel-agacki studio**  
architects  
milwaukee - los angeles



17700 W. CAPITOL DRIVE  
BROOKFIELD, WI 53045  
PHONE: (262) 796-1480  
FAX: (262) 796-1481  
EMAIL: j.pudelo@strigelagacki.com



**PROJECT:**  
**1601 N. JACKSON STREET**  
1601 N. JACKSON STREET  
Milwaukee, Wisconsin  
**BY:**  
Dermond Property Investments LLC  
757 N. Water Street, Milwaukee, WI 53202

**PLAN DATE:**  
**DECEMBER 22, 2011**

**JOB NUMBER:**  
**1032**  
**DESCRIPTION:**  
**UTILITIES PLAN**

SHEET

**C13**