


SE PORTION OF BLOCK 3 (PART OF 430 W STATE ST) MILWAUKEE, WI 53203

DPD ZONING SUBMITTAL FOR PORTION OF BLOCK 3 OR MILWAUKEE BUCKS ARENA DEVELOPMENT (SUBMITTAL DATE: JANUARY 10, 2025) CITY OF MILWAUKEE DPD FILE NO. 241340


GBA PROJECT NO. 202208

BRAND JOB NO. XXXXXX

VICINITY LOCATION MAP:



PROJECT LOCATION MAP:



PROJECT LOCATION

PROJECT TEAM / CONTACTS

OWNER: MILWAUKEE LODGING INVESTORS II, LLC 1600 ASPEN COMMONS, SUITE 200 MIDDLETON, WI 53562

PH: (608) 279-2488 CONTACT: ANDY INMAN E: AINMAN@NCGHOSPITALITY.COM

INTERIOR DESIGNER: THE SOCIETY

1505 5TH AVE, SUITE 300 SEATTLE, WASHINGTON 98101 PH: (208) 660-2106 CONTACT: COURTNEY MACLEAN E: COURTNEY@WELCOMETOTHESOCIETY.COM ARCHITECT:

GARY BRINK AND ASSOCIATES, INC KAPUR

2248 DEMING WAY, SUITE 120 MIDDLETON, WI 53762 PH: (608) 829-1750 CONTACT: JEFF BRENKUS E: JEFF.BRENKUS@GARYBRINK.COM

STRUCTURAL ENGINEER:

PIERCE ENGINEERS, INC.

222 W WASHINGTON AVE, SUITE 650 MADISON, WI 53703 PH: (608) 729-1414 CONTACT: LUCAS MARSHALL E: LMARSHALL@PIERCEENGINEERS.COM CIVIL / LANDSCAPE:

7711 N PORT WASHINGTON RD MILWAUKEE, WI 53217 PH: (414) 659-8193 CONTACT: MICHAEL FROEHLICH E: MFROEHLICH@KAPURINC.COM

MECHANICAL DESIGNER: **EXCEL ENGINEERING** 100 CAMELOT DRIVE FOND DU LAC, WI 54935 PH: (920) 926-9800 CONTACT: RANDY LIETZ

E: randy.lietz@excelengineer.com


PLUMBING / F.P. DESIGNER: **EXCEL ENGINEERING**

100 CAMELOT DRIVE FOND DU LAC, WI 54935 PH: (920) 926-9800 CONTACT: NICK STREETER E: nick.streeter@excelengineer.com

ELECTRICAL DESIGNER: **EXCEL ENGINEERING**

100 CAMELOT DRIVE FOND DU LAC, WI 54935 PH: (920) 926-9800 CONTACT: MELISSA REISINGER E: melissa.reisinger@excelengineer.com

PROJECT HEIGHT SUMMARY:



PROJECT INFORMATION / STATISTICS

Moxy MKE Hotel									
Floor	1st	2nd	3rd	4th	5th	6th	7th	Total	
Hotel Area	11,759sf	11,119sf	10,621sf	10,521sf	10,521sf	10,521sf	10,521sf	75,583sf	485sf/GR
King (210sf)	0	11	14	15	15	15	15	85	55.1%
Acc King (316sf)	0	0	1	0	0	0	0	1	33.1%
Double Queen (289sf)	0	7	7	7	7	7	7	42	
Nested Double Queen (260sf)	0	0	2	2	2	2	2	10	37.2%
Acc Double Queen (411sf)	0	1	1	1	1	1	1	6	
Double Queen Suite (495sf)	0	1	1	1	1	1	1	6	
King Suite (738sf)	0	0	1	1	1	1	1	5	7.7%
Acc King Suite (738sf)	0	1	0	0	0	0	0	1	
Total Rooms	0	21	27	27	27	27	27	156	

PROJECT COVER SHEET & CONTACTS

DD ITE 200


PROJECT:

MOXY HOTEL
PART OF BLOCK 3 - PHASE 2 / F
MILWAUKEE, WI 53203
CLIENT:

MILWAUKEE D
1600 ASPEN COMMONS, SUITE PROJECT: DRAWN BY: 12/13/24 DATE: AS NOTED

Initial Pricing Set 2024-12-13
DPD 1st Submittal 2025-01-10









AERIAL VIEW OF SITE LOOKING NORTH

AERIAL VIEW OF SITE LOOKING EAST



AERIAL VIEW OF SITE LOOKING SOUTH



AERIAL VIEW OF SITE LOOKING WEST

PART OF BLOCK 3 - PHASE 2 / PART OF 430 W. STATE STREET (SOUTHEAST CORNER OF W STATE STREET & N VEL R. PHILLIPS AVENUE)

MILWAUKEE, WI 53203

CLIENT:

MILWAUKEE DD LODGING INVESTORS II, LLC

© 2024 GARY BRINK & ASSOC.
Any duplication, reproduction, or use by any other party is prohibited unless proper written authorization is received from GBA Architecure | Design

PROJECT: 202208

DRAWN BY:


DATE: 12/13/24

SCALE: AS NOTED


Initial Pricing Set 2024-12-13
DPD 1st Submittal 2025-01-10

EXISTING AERIAL SITE IMAGES







AERIAL VIEW OF OVERALL BLOCK 3 SITE



PEDESTRIAN VIEW LOOKING WEST FROM N. VEL R. PHILLIPS AVENUE



PEDESTRIAN VIEW LOOKING NORTHWEST FROM CORNER OF N VEL R. PHILLIPS / WEST STATE STREET



PEDESTRIAN VIEW LOOKING NORTH FROM WEST STATE STREET

MOXY HOTEL
PART OF BLOCK 3 - PHASE 2 / PART OF 430 W. STATE STREET (SOUTHEAST CORNER OF W STATE STREET & N VEL R. PHILLIPS AVENUE
PART OF BLOCK 3 - PHASE 2 / PART OF 430 W. STATE STREET (SOUTHEAST CORNER OF W STATE STREET & N VEL R. PHILLIPS AVENUE
MILWAUKEE, WI 53203
CLIENT:
MILWAUKEE DD LODGING INVESTORS II, LLC
1600 ASPEN COMMONS, SUITE 200

12/13/24 AS NOTED



BUCKS ARENA DEVELOPMENT

LOCATION MAP


PROJECT: 202208

DRAWN BY:

DATE: 12/13/24

SCALE: AS NOTED

Initial Pricing Set 2024-12-13
DPD 1st Submittal 2025-01-10



BLOCK PLAN


EXISTING BLOCK PLAN

EXISTING BLOCK PLAN

Initial Pricing Set 2024-12-13
DPD 1st Submittal 2025-01-10

AS NOTED

DRAWN BY:



7711 N. Port Washington Road Milwaukee, Wisconsin 53217

kapurinc.com

PROJECT:

FRANK PRODUCTIONS -BLOCK 3

LOCATION:

1001 VEL R. PHILLIPS AVE., MILWAUKEE, WI 53203




RELEASE:

EXHIBIT

REVISIONS:						
#	DATE	DESCRIPTION				
NODTH ADDOM:						


I NORTH ARROW:





PROPOSED BOUNDARY EXHIBIT WITH TOPOGRAPHY


PROJECT MANAGER: PROJECT NUMBER: 24.0804 02/04/2025


SHEET NUMBER:














EROSION CONTROL MEASURES

- . CONTRACTOR TO INSTALL AND MAINTAIN EROSION CONTROL MEASURES AS INDICATED ON THIS PLAN AND PER THE LATEST WDNR TECHNICAL STANDARDS. TECHNICAL STANDARDS MAY BE VIEWED ONLINE AT: http://dnr.wi.gov/topic/stormwater/standards/const_standards.htm 2. INLETS AND CATCH BASINS SHALL BE PROTECTED WITH INLET FILTERS THAT ARE PHASED IN WITH CONSTRUCTION TO REDUCE SEDIMENT FROM ENTERING THESE AREAS PER WDNR TECHNICAL
- ALL FABRIC BARRIERS SELECTED FOR INLET/CATCH BASIN PROTECTION DEVICES SHALL BE SELECTED FROM THE LIST OF APPROVED FABRICS CERTIFIED FOR INLET PROTECTION. GEOTEXTILE FABRIC, TYPE FF IN THE CURRENT EDITION OF THE WiscDOT PRODUCT ACCEPTABILITY LIST, TO OBTAIN THE PAL, PLEASE REFER TO THIS WEBSITE: http://wisconsindot.gov/Documents/doing-bus/eng-consultants <u>/cnslt-rsrces/tools/pal/pal-7-14.pdf</u>

STANDARD 1060 AS FOLLOWS:

DISCOURAGED AND PROHIBITED.

- A. INLET PROTECTION SHALL BE AT A MINIMUM INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT OF 1/2 INCH OR GREATER DURING A 24-HOUR PERIOD.
- B. PLACEMENT OF SPOIL MATERIAL, DEBRIS, SOILS, ETC. ON TOP OF INLETS/CATCH BASINS, EVEN IF TEMPORARY, IS STRICTLY
- C. SEDIMENT DEPOSITS SHALL BE REMOVED AND THE INLET PROTECTION DEVICE RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED BETWEEN 1/3 TO $\frac{1}{2}$ THE DESIGN DEPTH OF THE DEVICE FOR TYPES A-C, WHEN SEDIMENT IS WITHIN 6" OF THE BOTTOM OF THE OVERFLOW HOLE FOR TYPE D, OR WHEN THE DEVICE IS NO LONGER FUNCTIONING PER MANUFACTURER'S SPECIFICATIONS. ALL SEDIMENT COLLECTED SHALL BE PROPERLY DISPOSED OF TO
- PREVENT DISCHARGE INTO AREA WATERWAYS AND WETLANDS. D. DUE CARE SHALL BE TAKEN TO ENSURE SEDIMENT DOES NOT FALL INTO THE INLETS/CATCH BASINS AND IMPEDE THE INTENDED FUNCTION OF THE DEVICE. ANY MATERIAL FALLING INTO THE INLET/CATCH BASIN SHALL BE REMOVED AND

PROPERLY DISPOSED OF PER NOTE C ABOVE.

- E. INLET FILTERS MAY BE REMOVED AND PROPERLY DISPOSED OF UPON COMPLETION OF CONSTRUCTION, HAULING OR MOVEMENT OF CONSTRUCTION EQUIPMENT THROUGHOUT THE SITE, AND ONCE THE SITE IS ADEQUATELY STABILIZED, UNLESS AS OTHERWISE NOTIFIED BY THE WDNR.
- 3. A TRACKING PAD SHALL BE INSTALLED AS SHOWN ON THE PLAN SHEET PRIOR TO THE START OF CONSTRUCTION TO REDUCE OFF-SITE SEDIMENTATION BY ELIMINATING THE TRACKING OF SEDIMENT FROM THE SITE PER WDNR TECHNICAL STANDARD 1057 AS
- A. AGGREGATE USED FOR TRACKING PADS SHALL BE 3 TO 6 INCH CLEAR OR WASHED STONE. ALL MATERIAL TO BE RETAINED
- BY 3 INCH SIEVE. B. THE AGGREGATE SHALL BE PLACED IN A LAYER OF AT LEAST 12 INCHES THICK. ON SITES WITH A HIGH WATER TABLE, OR WHERE SATURATED CONDITIONS ARE EXPECTED, TRACKING
- C. THE TRACKING PAD SHALL BE THE FULL WIDTH OF THE EGRESS POINT (MIN. 15 FEET WIDE) AND BE AT LEAST 50 FEET LONG.

PADS WILL BE UNDERLAIN WITH WISDOT TYPE R GEOTEXTILE

- D. VEHICLES TRAVELING ACROSS THE TRACKING PAD SHALL MAINTAIN A SLOW CONSTANT SPEED.
- E. ANY SEDIMENT OR ROCK ACCUMULATION ONTO LOCAL ROADWAYS SHALL BE REMOVED BY STREET CLEANING, NOT FLUSHING BEFORE THE END OF EACH WORKING DAY.
- F. THE TRACKING PAD SHALL, AT A MINIMUM BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT OF 1/2 INCH OF RAIN OR MORE DURING A 24-HOUR
- G. THE TRACKING PAD PERFORMANCE SHALL BE MAINTAINED AT A MINIMUM OF 12" BY SCRAPING OR TOP-DRESSING WITH ADDITIONAL AGGREGATE.

- 4. THE CONSTRUCTION SITE PERIMETER AND TOPSOIL STOCKPILE AREA SHALL BE PROTECTED WITH SILT FENCE AS SHOWN ON THE PLAN SHEET PRIOR TO THE START OF CONSTRUCTION TO INTERCEPT AND REDUCE THE FLOW OF SEDIMENT-LADEN SHEET FLOW RUNOFF FROM THE CONSTRUCTION SITE PER WDNR TECHNICAL
- STANDARD 1056 AS FOLLOWS: A. SILT FENCE ENDS SHALL BE EXTENDED UPSLOPE TO PREVENT WATER FROM FLOWING AROUND THE ENDS OF THE FENCE AS SHOWN ON THE PLAN
- B. INSTALLED SILT FENCE SHALL BE A MINIMUM 14 INCHES HIGH AND SHALL NOT EXCEED 28 INCHES IN HEIGHT MEASURED FROM THE INSTALLED GROUND ELEVATION.
- C. SILT FENCE SHALL BE SUPPORTED BY EITHER STEEL OR WOOD SUPPORT POSTS.
- D. THE MAXIMUM SPACING OF POSTS FOR NONWOVEN SILT FENCE SHALL BE 3 FEET OR
- FOR WOVEN FABRIC 8 FEET. E. SILT FENCE SHALL HAVE A SUPPORT CORD AT THE TOP OF THE FENCE.
- F. WHERE JOINTS ARE NEEDED, EACH END OF THE FABRIC SHALL BE SECURELY FASTENED TO A POST. THE POSTS SHALL BE WRAPPED AROUND EACH OTHER TO PRODUCE A STABLE AND SECURE JOINT OR SHALL BE OVERLAPPED THE DISTANCE BETWEEN TWO POSTS.
- G. A MINIMUM OF 20 INCHES OF THE POSTS SHALL EXTEND INTO THE GROUND AFTER INSTALLATION. H. SILT FENCE SHALL BE ANCHORED BY SPREADING AT LEAST 8 INCHES OF THE FABRIC IN A 4 INCH WIDE BY 6 INCH DEEP TRENCH, OR 6 INCH DEEP
- V-TRENCH ON THE UPSLOPE SIDE OF THE FENCE. THE TRENCH SHALL BE BACKFILLED AND COMPACTED. TRENCHES SHALL NOT BE EXCAVATED ANY WIDER OR DEEPER THAN NECESSARY FOR PROPER INSTALLATION. . ON THE TERMINAL ENDS OF THE SILT FENCE THE
- FABRIC SHALL BE WRAPPED AROUND THE POST SUCH THAT THE STAPLES ARE NOT VISIBLE. J. GEOTEXTILE FABRIC SPECIFICATIONS SHALL MEET VALUES ESTABLISHED IN TECHNICAL STANDARD
- K. SILT FENCE SHALL BE REMOVED ONCE THE SITE IS ADEQUATELY STABILIZED. WHEN PLACING SILT FENCE NEAR TREES, CARE SHALL BE TAKEN TO MINIMIZE DAMAGE TO THE ROOT SYSTEM BY AVOIDING COMPACTION AND

ROOT CUTTING WITHIN A RADIUS OF 1.5 FEET

PRECIPITATION EVENT THAT PRODUCES 1/2 INCH

- MULTIPLIED BY THE INCH DIAMETER OF THE M. THE CONTRACTOR MAY FURTHER STRENGTHEN THE SILT FENCE BY USING HAY BALES ON THE DOWN SLOPE SIDE AS NEEDED. N. SILT FENCE SHALL AT A MINIMUM BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY
- OF RAIN OR MORE DURING A 24 HOUR PERIOD. O. DAMAGED OR DECOMPOSED SILT FENCE, UNDERCUTTING, OR FLOW CHANNELS AROUND THE END OF BARRIERS SHALL BE REPAIRED OR
- P. SEDIMENT SHALL BE PROPERLY DISPOSED OF ONCE THE DEPOSITS REACH 1/2 THE HEIGHT OF THE FENCE TO PREVENT DISCHARGE INTO AREA WATERWAYS AND WETLANDS.

- 5. SEEDING AND MULCHING TECHNIQUES SHALL BE USED ON AREAS OF EXPOSED SOIL WHERE THE ESTABLISHMENT OF VEGETATION IS DESIRED. TEMPORARY SEEDING APPLIES TO DISTURBED AREAS THAT WILL NOT BE BROUGHT TO FINAL GRADE OR ON WHICH LAND-DISTURBING ACTIVITIES WILL NOT BE PERFORMED FOR A PERIOD GREATER THAN 14 CALENDAR DAYS, REQUIRING VEGETATIVE COVER FOR LESS THAN ONE YEAR. SEED AND MULCH SHALL BE UTILIZED THROUGHOUT THE DURATION OF CONSTRUCTION TO ESTABLISH TEMPORARY VEGETATION TO HELP REDUCE EROSION PER WDNR TECHNICAL STANDARDS 1059 AND 1058 RESPECTIVELY AS FOLLOWS:
- A. TEMPORARY SEEDING REQUIRES A SEEDBED OF LOOSE SOIL TO A MINIMUM DEPTH OF 2 INCHES.
- B. FERTILIZER APPLICATION IS NOT GENERALLY REQUIRED FOR TEMPORARY SEEDING. HOWEVER, ANY APPLICATION OF FERTILIZER OR LIME SHALL BE BASED ON SOIL TESTING.
- C. THE SOIL SHALL HAVE A PH RANGE OF 5.5 TO 8.0. D. ALL SEED SHALL CONFORM TO THE REQUIREMENTS OF THE WISCONSIN STATE STATUTES AND OF THE ADMINISTRATIVE CODE CHAPTER ATCP 20.01
- REGARDING NOXIOUS WEED SEED CONTENT AND LABELING. E. SEED SHALL NOT BE USED LATER THAN ONE YEAR AFTER THE TEST DATE
- F. IN THE SUMMER—SPRING, CONTRACTOR SHALL USE OATS APPLIED AT 131 LBS/ACRE FOR TEMPORARY SEEDING PURPOSES. IN THE FALL THE CONTRACTOR SHALL USE ANNUAL RYEGRASS APPLIED AT 80 LBS/ACRE OR WINTER WHEAT OR CEREAL RYE APPLIED AT 131 LBS/ACRE. THE CONTRACTOR SHALL USE STRAW MULCH APPLIED AT 1.5 TONS/ACRE. DORMANT SEED SHALL BE USED WHEN SOIL TEMPERATURE IS CONSISTENTLY BELOW 53 DEGREES FAHRENHEIT (TYPICALLY NOV. 1 UNTIL SNOW COVER ANNUALLY). NEVER PLACE SEED ON TOP OF SNOW. IF COVER IS NEEDED AFTER SNOW FALL, CONTRACTOR MAY CHOOSE TO USE A DRY, NONTOXIC TYPE B SOIL STABILIZER PER MANUFACTURER'S SPECIFICATIONS AS REQUIRED BY THE WDNR.
- G. SEEDING SHALL NOT TAKE PLACE WHEN THE SOIL IS TOO WET.
- H. CONTRACTOR MAY CONSIDER WATERING TO HELP ESTABLISH THE SEED. WATER APPLICATION RATES SHALL BE CONTROLLED TO HELP PREVENT RUNOFF AND EROSION.
- DURING CONSTRUCTION, AREAS THAT HAVE BEEN SEEDED AND MULCHED SHALL AT A MINIMUM BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 1/2 INCH OF RAIN OR MORE DURING A 24 HOUR PERIOD. INSPECT WEEKLY DURING THE GROWING SEASON UNTIL VEGETATION IS DENSELY ESTABLISHED OR THE SOD IS LAID. REPAIR AND RESEED AREAS THAT HAVE EROSION DAMAGE AS NECESSARY.
- J. CONTRACTOR IS TO LIMIT VEHICLE TRAFFIC AND OTHER FORMS OF COMPACTION IN AREAS THAT ARE SEEDED AS MUCH AS POSSIBLE. RE-SEED DRIVEN OVER AREAS AS NEEDED.
- K. MULCH SHOULD BE PLACED WITHIN 24 HOURS OF SEEDING.
- L. MULCHING OPERATIONS SHALL NOT TAKE PLACE DURING PERIODS OF EXCESSIVELY HIGH WINDS THAT WOULD PRECLUDE THE PROPER PLACEMENT
- M. MULCH THAT IS DISPLACED SHALL BE REAPPLIED AND PROPERLY ANCHORED. MAINTENANCE SHALL BE COMPLETED AS SOON AS POSSIBLE WITH CONSIDERATION TO SITE CONDITIONS.
- N. WHEN CHANNEL EROSION MAT IS USED WITHIN CONSTRUCTION SITE
- DIVERSION AREAS, TECHNICAL STANDARDS 1053 AND 1066 SHALL BE
- O. WHEN NON-CHANNEL EROSION MAT IS USED TECHNICAL STANDARD 1052 SHALL BE FOLLOWED. P. DEPENDING ON DURATION OF CONSTRUCTION, THE CONTRACTOR MAY NEED
- TO RE-SEED AND RE-STABILIZE THE TOPSOIL STOCKPILE AS NECESSARY TO DISCOURAGE SEDIMENT AND EROSION. 6. A COPY OF EROSION CONTROL INSPECTION REPORTS AND THE APPROVED EROSION CONTROL PLANS SHALL BE KEPT ON SITE.
- 7. CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL PRACTICES BY THE END OF EACH WORKDAY. 8. LOCAL ROADS SHALL BE CLEAN BY THE END OF EACH WORKDAY. CONTRACTOR SHALL HAVE LOCAL ROADS SWEPT WHERE SEDIMENT ACCUMULATES.

EROSION CONTROL OPERATION SEQUENCE + SCHEDULE

AFTER BIDS ARE RECEIVED AND A MASS GRADING CONTRACTOR IS SELECTED, A PRE-CONSTRUCTION MEETING SHALL TAKE PLACE WITH ALL RELEVANT PARTIES IN ATTENDANCE. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING ALL SILT FENCES, SILT SOCK. STONE TRACKING PADS, INLET PROTECTION, AND OTHER EROSION CONTROL MEASURES. GENERAL CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PRIOR TO COMMENCING GRADING, GRUBBING, OR OTHER LAND DISTURBING ACTIVITIES. EROSION CONTROL MEASURES MUST BE INSPECTED WEEKLY AND WITHIN 24 HOURS OF EVERY PRECIPITATION EVENT THAT PRODUCES 1/2-INCH OF RAIN OR MORE DURING A 24-HOUR PERIOD. IN ADDITION, THE ACTIVE CONTRACTOR SHALL CONDUCT DAILY INSPECTIONS AND DOCUMENT CONDITIONS AND REPAIRS MADE, ALONG WITH DATE, TIME OF INSPECTION, AND WEATHER CONDITIONS IN A DAILY LOG BOOK.

ALL REGULATORY PERMITS, PROJECT PLANS, AND INSPECTION LOGS SHALL BE KEPT ON SITE IN AN ACCESSIBLE LOCATION, SUCH AS A MAILBOX, AVAILABLE TO REGULATORY AGENCIES UPON REQUEST. CONTRACTORS ARE TO MAINTAIN THE CONSTRUCTION SITE IN A NEAT AND TIDY MANNER FOR THE DURATION OF THE PROJECT.

- THE TIMING AND SEQUENCE OF CONSTRUCTION IS SCHEDULED AS FOLLOWS: 1. OBTAIN PLAN APPROVAL FROM THE CITY OF MILWAUKEE, AND ALL APPLICABLE PERMITS, INCLUDING
- EROSION CONTROL PERMIT. 2. CONSTRUCTION IS SCHEDULED TO BEGIN OCTOBER 2025 AND ANTICIPATED TO BE COMPLETED BY FEBRUARY OF 2026, DEPENDING ON WEATHER & GROUND CONDITIONS.
- 3. SILT FENCE, SILT SOCK AND INLET FILTER PROTECTION SHALL BE INSTALLED AS SHOWN ON THE PLANS, AND INSPECTED PRIOR TO COMMENCING OF ANY LAND DISTURBING ACTIVITIES PER PROJECT PLANS AND DETAILS. SEDIMENT DEPOSITS WILL BE REMOVED FROM BEHIND THE SILT FENCE WHEN THEY REACH A DEPTH OF 1/2 FENCE HEIGHT.
- 4. SITE DEMOLITION OF PAVEMENT, ETC. WILL OCCUR AFTER ALL EROSION CONTROL MEASURES ARE IN
- 5. CONSTRUCTION OF THE BUILDING, STARTING WITH THE FOUNDATION, WILL BEGIN IMMEDIATELY AFTER THE SITE DEMOLITION IS COMPLETE IN THE BUILDING PAD AREA.
- AFTER ROUGH GRADING IS COMPLETE IN HARD SURFACE AREAS SUCH AS DRIVEWAYS, LOADING AREAS, AND THE BUILDING, THE REQUIRED THICKNESS OF DENSE GRADED BASE COURSE, PER THE

6. UTILITY INSTALLATION WILL OCCUR NEXT AND CONTINUE UNTIL ALL THE SITE UTILITIES ARE INSTALLED.

- 8. AFTER STABILIZATION IS UNDERWAY, DRIVEWAY, LOADING AREA, AND SIDEWALK SURFACE MATERIAL (I.E. ASPHALT OR CONCRETE) WILL BE INSTALLED PER PROJECT PLANS AND SPECIFICATIONS. 9. THE GENERAL CONTRACTOR WILL REQUEST A FINAL INSPECTION BY THE CITY. UPON APPROVAL, ALL SILT FENCES, SILT SOCK AND INLET FILTER PROTECTION SHALL BE REMOVED, AND ACCUMULATED SEDIMENT IN THE UNDERGROUND STORM WATER DETENTION SYSTEM SHALL BE DREDGED AND
- 10. IF REQUIRED, FINAL "AS-BUILT" SURVEYS ARE TO BE CONDUCTED BY THE OWNER AND FINAL

PROJECT PLANS AND DETAILS WILL BE APPLIED FOR STABILIZATION.

DOCUMENTS FORWARDED TO THE CITY.

IF CONSTRUCTION SCHEDULES SHOULD CHANGE SIGNIFICANTLY, THIS PLAN NARRATIVE WILL BE UPDATED AND RESUBMITTED BY THE GENERAL CONTRACTOR TO THE CITY AND WDNR.

INSPECT ALL EROSION CONTROL MEASURES PRIOR TO COMMENCING GRADING, GRUBBING OR OTHER LAND DISTURBING ACTIVITIES. EROSION CONTROL MEASURES MUST BE INSPECTED WEEKLY AND WITHIN 24 HOURS OF EVERY PRECIPITATION EVENT OF 0.50 INCH OR GREATER. IN ADDITION THE CONTRACTOR SHALL CONDUCT DAILY INSPECTIONS AND DOCUMENT CONDITIONS AND REPAIRS MADE. ALONG WITH DATE. TIME OF INSPECTION AND WEATHER CONDITIONS IN A DAILY LOG BOOK, THE DAILY LOG BOOK, WEEKLY A 0.50 INCH PRECIPITATION REPORTS, APPROVED PLANS WPDES PERMIT & CHAPTER 30 PERMIT SHALL BÉ KEPT IN AN ACCESSIBLE LOCATION, LIKE A MAILBOX, WITHIN THE STAGING AREA.

AT ABSOLUTELY NO TIME MAY CONSTRUCTION EQUIPMENT, DEBRIS, FILL, ETC. BE PLACED WITHIN WETLANDS, WATERWAYS OR FLOODPLAINS UNLESS IDENTIFIED IN THE PLANS & APPROVED BY DNR/

DEWATERING PLAN

- TO FACILITATE CONSTRUCTION AT THE PROJECT SITE, DEWATERING MAY TAKE PLACE BY THE SELECTED CONTRACTOR. CONTRACTOR TO FOLLOW THESE INSTRUCTIONS WHILE PERFORMING DEWATERING ACTIVITIES ON-SITE. IF DEWATERING IS TO TAKE PLACE AT THE SITE, IT WILL OCCUR BETWEEN STEPS 3 AND 14 OF THE EROSION CONTROL OPERATION SEQUENCE.
- NOTE: THESE INSTRUCTIONS DO NOT APPLY TO WATER BEING DISCHARGED DIRECTLY TO GROUNDWATER OR KARST FEATURES OR WELL DEWATERING SYSTEMS. CONTRACTOR SHALL COORDINATE ACCORDINGLY FOR OTHER DEWATERING ACTIVITIES AS DEEMED NECESSARY WITH THE WDNR.
- 1. THE CONTRACTOR SHALL ENSURE THAT THE DEWATERING PRACTICES CARRIED OUT MEET OR EXCEED WNDR TECHNICAL STANDARD NUMBER 1061.
- ANY SPILLS. OILS, GASOLINE, ETC. SHALL NOT BE STORED WITHIN WETLANDS, NEAR THE STORMWATER POND, OR OTHER ON-SITE WATER AREAS.

2. A PAN OR OTHER CONTAINMENT DEVICE SHALL BE PLACED UNDERNEATH THE PUMP TO CAPTURE

- 3. A TYPE 2 GEOTEXTILE BAG THAT IS NO SMALLER THAN 100 SQUARE FEET; HAS A MAXIMUM APPARENT OPENING SIZE OF 0.212 mm; HAS A GRAB TENSILE STRENGTH OF 300 LBS; MULLEN BURST OF 580 PSI; PERMEABILITY OF 0.2 CM/SEC; FABRIC WEIGHT OF 12 OZ SHALL BE USED. THE GEOTEXTILE BAG AREA AND DOWNGRADE FLOW AREA SHALL CONSIST OF VEGETATED AND UNDISTURBED SOILS. 4. POLYMER APPROVED BY THE WDNR MEETING WDNR TECHNICAL STANDARD 1051 MAY BE USED IN
- COMBINATION WITH THE DEWATERING BAG IF THE DEWATERING BAG IS NOT DOING AN ADEQUATE JOB ALONE OF FILTERING SEDIMENTS. THE CONTRACTOR SHALL SUPPLY TOXICITY TESTING DATA TO THE WDNR BEFORE USE ON-SITE FOR WDNR APPROVAL. POLYMER SHALL NOT BE DIRECTLY APPLIED TO SURFACE WATER. CONTRACTOR SHALL OBTAIN THE MATERIAL SAFETY DATA SHEETS (MSDS) FOR THE SELECTED POLYMER, MANUFACTURER'S INFORMATION AND WDNR USE RESTRICTIONS (SEE TECHNICAL STANDARD 1051) AND KEEP ALL THIS INFORMATION ON-SITE. CONTRACTOR SHALL ADHERE TO MANUFACTURER AND WDNR'S APPLICATION RATES FOR THE POLYMER, WITH THE WDNR'S RATE TAKING PRECEDENCE. THE CONTRACTOR SHALL TAKE STEPS TO ENSURE THAT THE POLYMER IS NOT SPILLED. SPILL KITS SHALL BE KEPT ON SITE; THE MANUFACTURER'S RECOMMENDED CLEANUP PROCEDURES
- 5. A TARP MAY BE UTILIZED UNDERNEATH THE TYPE 2 GEOTEXTILE BAG AND JUST DOWN SLOPE OF THE BAG TO DISCOURAGE EROSION AND SCOUR.
- 6. A FLOATING SUCTION HOSE OR OTHER FLOTATION METHOD SHALL BE UTILIZED WHEN PUMPING FROM AN AREA WITH STANDING WATER TO AVOID SUCKING SEDIMENT FROM GRADE.
- 7. IF TURBID WATER IS LEAVING THE GEOTEXTILE BAG, THE CONTRACTOR SHALL SHUT OFF THE PUMP TO ALLOW SEDIMENTS TO SETTLE INTO THE BAG. CONTRACTOR SHALL FOLLOW THE MANUFACTURER'S SPECIFICATIONS FOR DETERMINING THE SEDIMENT CAPACITY OF THE GEOTEXTILE BAG USING GOOD COMMON SENSE. SEDIMENT LEVELS CONTAINED IN THE BAG SHALL BE MONITORED TO MEASURE THE LOSS OF STORAGE CAPACITY OVER TIME. THE CONTRACTOR SHALL PROPERLY DISPOSE OF THE GEOTEXTILE BAG IN A WASTE RECEPTACLE ONCE IT IS NO LONGER USED.
- 8. DURING DEWATERING ACTIVITIES THE CONTRACTOR SHALL MONITOR DEWATERING PRACTICES AND KEEP A LOG OF THE FOLLOWING:
- A. DISCHARGE DURATION AND SPECIFIED PUMPING RATE.

SHALL BE FOLLOWED IN THE EVENT OF A SPILL.

B. OBSERVED WATER TABLE AT TIME OF DEWATERING.

METHOD OF APPLICATION.

- C. MAINTENANCE ACTIVITIES
- D. NAME AND QUANTITY OF POLYMER USED. PRODUCT TYPE. APPLICATION RATE OF POLYMER IN POUNDS/ACRE FEET OF WATER. DATE AND TIME APPLIED. WEATHER CONDITIONS DURING APPLICATION.
- THIS LOG NEEDS TO BE KEPT ON SITE FOR WDNR REGULATORY REVIEW. COPIES OF THIS DOCUMENTATION SHOULD BE KEPT IN THE CONTRACTOR'S MONITORING LOG AND MADE AVAILABLE UPON
- REVIEW THE FOLLOWING FOR MORE INFORMATION: WDNR TECHNICAL STANDARD 1061 FOR DEWATERING -

http://dnr.wi.gov/topic/stormWater/documents/dnr1051.pdf

http://dnr.wi.gov/topic/stormWater/documents/Dewatering_1061.pdf WDNR TECHNICAL STANDARD 1051 FOR POLYMER -





GENERAL NOTES MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE


WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY. 🅤 FINISHED SIZE SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL. SIDE FLAPS, ' WHERE REQUIRED SHALL BE A MIN. OF TWO INCHES LONG. FOLD THE FABRIC OVER AND REINFORCE WITH MULTIPLE STITCHES.

🅱 FOR INLET PROTECTION, TYPE C (WITH CURB BOX), FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2"X4". THE REBAR,

STEEL PIPE, OR WOOD SHALL BE INSTALLED IN THE FLAP AND NOT BLOCK THE TOP HALF OF THE CURB BOX OPENING.







WITHOUT A CURB BOX) INSTALLATION NOTES

TRIM EXCESS FABRIC A MINIMUM OF 10" AROUND GRATE FOR MAINTENANCE OR REMOVAL. THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.

TYPE D UTILIZE INLET PROTECTION TYPE D IN INLETS DEEPER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE. THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3". WHERE NECESSARY THE CONTRACTOR MAY CINCH THE BAG, USING PLASTIC ZIP TIES, TO FIT INLETS LESS THAN 30" DEPTH. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.

2024 GBA Architecture | Design Any duplication, reproduction, or use by any other party is prohibited unless prior written authorization is received from GBA.

2248 DEMING WAY, SUITE 120

MIDDLETON, WI 53562

608-829-1750

www.garybrink.com

788 N. Jefferson St. Ste 900 Milwaukee, Wisconsin 53202

kapurinc.com

DPD SUBMITTAL 03/08/2021 DPD SUBMITTAL 2 03/08/2021 DPD SUBMITTAL 3 03/08/2021 CITY COUNCIL FILE NO: 201351 DPD SUBMITTAL 4 04/15/2021 BID PKG. NO. 1 06/30/2021 BID PKG. NO. 2 09/20/2021


SCALE: AS NOTED

PROJECT:

DATE:

DRAWN BY:

SITE EROSION



2248 DEMING WAY, SUITE 120 MIDDLETON, WI 53562 608-829-1750 www.garybrink.com 788 N. Jefferson St. Ste 900 Milwaukee, Wisconsin 53202