

## **Certificate of Appropriateness**

Milwaukee Historic Preservation Commission/841 N Broadway/Milwaukee, WI 53202/phone 414-286-5712

## Property Description of work

## North Point North HD

**Description of work** Install new concrete cap on chimney. There shall be a barrier layer of Type N mortar between the brick of the chimney and the new concrete cap. Corbelling must be rebuilt as it exists now with all stone pieces retained and reinstalled. Where brick is damaged, replace with matching rug-faced brick.

## Date issued

4/22/2024

**2912 E Belleview Place** 

Under the provisions of Section 320-21 (11) and (12) of the Milwaukee Code of Ordinances, the Milwaukee Historic Preservation Commission has granted a certificate of appropriateness for the work listed above. The work was found to be consistent with preservation guidelines. The following conditions apply to this certificate of appropriateness:

The (partially) rebuilt chimney must be rebuilt to exactly match the historic including bonding pattern, corbeling, and other details. Accurate measurements shall be taken prior to disassembling so the new chimney exactly matches the historic without alteration. When installing new flashing at a masonry feature, the flashing must be stepped or cut into the mortar joints. The bricks may not be cut to install flashing at an angle. New mortar must match the original mortar in terms of color, texture, grain size, joint width, and joint finish/profile. The compressive strength of the repointing mortar shall be equal or less than the compressive strength of the original mortar and surrounding brick or stone. The replacement mortar shall contain approximately the same ingredient proportions of the original mortar. Mortar that is too hard is subject to premature failure and could damage the masonry. In most cases, this means a lime mortar with natural hydraulic cement rather than Portland cement. No joint of a width less than 3/8" may be cleaned of damaged/decomposed mortar with power disc grinders. No over-cutting of the joints is permitted. Remove decomposed mortar back into the wall 2.5 times the height of the joint before repointing.

Where brick is damaged, replace with matching rug-faced brick.


All work must be done in a craftsman-like manner. Staff must approve any changes or additions to this certificate before work begins. Work that is not completed in accordance with this certificate may be subject to correction orders or citations. If you require technical assistance, please contact Historic Preservation staff as follows: Phone: (414) 286-5712 E-mail: hpc@milwaukee.gov.

Permits and timeline


You are responsible for determining if permits are required and obtaining them prior to commencing work. Consult the Development Center on the web or by telephone for details <u>www.milwaukee.gov/lms</u> (414) 286-8210. If permits are <u>not</u> required, work must be completed within one year of the date this certificate was issued. If permits are required, permits must be obtained within one year of the date this certificate was issued.

m ans

City of Milwaukee Historic Preservation



Detail at top of chimney



Chimney details. Note two complete courses of stone and one half course.