

Project Description - MPA Tavern (Catherine Foley Building)

Duration - Months		8			
Total Cost no bond		\$ 2,971,708.74			
Work Task	Comment	Quantity	Unit	Total	
GENERAL CONDITIONS:					
		1 LS			
Preconstruction - DONATED TIME	0	0.00	HRS	\$ -	
On Site Super	40	1,392.00	HRS	\$ 187,920.00	
Project Manager John P - DONATED TIME	0	0.00	HRS	\$ -	
Project Manager Assistant / Admin.	8	278.40	HRS	\$ 19,488.00	
Quality / Safety	2	69.60	HRS	\$ 7,656.00	
General Field Super	2	69.60	HRS	\$ 7,656.00	
Staging Area Set Up				\$ -	
Sidewalk Barricades				\$ -	
Permits					
Sidewalk/Barricade		200.00	LF	\$ 5,000.00	
Building/Repair			LS	\$ 17,500.00	
Lane Closure/Curb Lane/Alley		50.00	LF	\$ 1,000.00	
Expediter Costs			LS	\$ -	
Storage Trailer				\$ 4,100.00	
Job Site Office				\$ 3,500.00	
Job Site Bathroom				\$ 1,600.00	
Temporary Electric Hook Ups				\$ 5,000.00	
Temporary Water				\$ 5,000.00	
Power Line Moving/Covering (See allowances)				\$ -	
Construction Signs & Berglund Signs				\$ 500.00	
Engineering				\$ 7,500.00	
Dumpsters		16.00	EA	\$ 5,600.00	
Final Construction Clean Up		1.00	LS	\$ 5,000.00	
		278.40	MD	\$ 284,020.00	

1.) Demolition		1			
Remove Roof				\$ 82,468.80	
Interior Demolition (Included)				\$ -	
Remove Fire Escape				\$ 8,500.00	
Remove Basement Access Door				\$ 2,500.00	
		0.00	MD	\$ 93,468.80	

2.) Shoring/Scaffolding		1			
Exterior Scaffolding		1.00	LS	\$ 67,888.80	
Engineering		1.00	LS	\$ 1,500.00	
Temp Canopy Lighting		2.00	LS	\$ 4,500.00	
Wall Bracing for Demolition (Included)				\$ -	
Shoring for foundation walls		1.00	LS	\$ 10,000.00	
Shoring for steel replacement		1.00	LS	\$ 5,000.00	
		0.00	MD	\$ 88,888.80	

3.) Concrete		1			
Infill at North Where hatch removed		30.00	SF	\$ 3,700.00	

Duration - Months		8			
Total Cost no bond		\$ 2,971,708.74			
Work Task	Comment	Quantity	Unit	Total	
Building .xls				Page 2 of 5 1/26/2024	
Concrete Floor crack repair				\$	5,000.00
		3.80	MD	\$	8,700.00

4.) Masonry		1			
Remove paint from Exterior Brick (NICL EAST)	1	3,320.00	SF	\$	74,700.00
Repoint 100% (NICL EAST)	1	3,320.00	SF	\$	64,740.00
Masonry Coating	1	5,656.00	SF	\$	21,210.00
Rebuild Outer Wythe at North	2	450.00	SF	\$	45,000.00
Rebuild Outer Wythe at South	2	150.00	SF	\$	15,000.00
Rebuild Tripple Wythe wall at East Incl parpet (est in g	2	1,736.00	SF	\$	288,176.00
Individual Brick Repair	3	200.00	EA	\$	9,600.00
Remove Abandoned Penetration	4	4.00		\$	440.00
Replace Sealant (None)	5			\$	-
Rebuild Parapet (included with East Wall)	6			\$	-
Foundation Wall Rebuild	7	150.00	SF	\$	32,850.00
Remove Masonry for Window/Door Opening	8, 9	7.00		\$	5,145.00
Rebuild Chimney (Remove only - with demo)	14	2.00	EA	\$	-
Rebuild Bearing wall in basmenet		72.00	SF	\$	15,768.00
Helical Ties @ original Structure		1,973.88	EA	\$	48,360.07
Helical Ties @ Addition		200.00	EA	\$	4,900.00
Place new control joints		1.00	LS	\$	7,850.00
Tuckpoint foundation Rubble Walls		1,476.00	SF	\$	40,590.00
Rebuild Wall above south-East Window		30.00	SF	\$	3,000.00
Remove door & Infill with Masonry	16	1.00	EA	\$	3,320.00
Joist pocket repairs		50.00	EA	\$	30,000.00
Trucking & Mobilization				\$	-
Load Trucks At Yard		8.00	HRS	\$	800.00
Initial Trucking At Project Start		8.00	HRS	\$	1,200.00
Weekly Trucking	2	69.60	HRS	\$	10,440.00
Demobilization Trucking		8.00	HRS	\$	1,200.00
Unload Trucks At Yard		8.00	HRS	\$	800.00
Mobilization		32.00	HRS	\$	3,040.00
Demobilization		32.00	HRS	\$	3,040.00
Mock-Ups		16.00	HRS	\$	2,170.00
				\$	-
		750.75	MD	\$	733,339.07

5.) Steel		1			
New Beam and Column at Bearing Wall				\$	10,000.00
Replace Column at 1st floor				\$	20,000.00
Steel Lintel at South-East Window				\$	4,180.00
		2.85	MD	\$	34,180.00

6.) Carpentry		1			
ROUGH					
Roof Truss system		34.00	EA	\$	65,930.00
Roof Decking (See roofing)		-	SF	\$	-
Fascia Trim				\$	12,960.00
Turret Re-Framing		1.00	EA	\$	2,760.00
Interior Wall Framing (See framing & Drwyall)				\$	-

Duration - Months		8			
Total Cost no bond		\$	2,971,708.74		
Work Task	Comment	Quantity	Unit	Total	
Building .xls				Page 3 of 5 1/26/2024	

Level 3 Floor Framing (Roof) (Exlcuded)				\$	-
Stair Reconstruction		2.00	EA	\$	22,740.00
Floor Framing Repair & Redeck		2.00	LS	\$	46,480.00
Interior Wall Blocking				\$	1,850.00
FINISH					
Interior Doors and Frames		20.00	EA	\$	23,870.00
Interior Trim (Base & Moulding)		810.00	LF	\$	20,331.00
Kitchenette Casework		24.00	LF	\$	8,316.00
Other Misc Carpentry				\$	10,750.00
		192.06	MD	\$	215,987.00

7.) Insulation		1			
In Wall Insualtion Mineral wool & Foil Face AVP		5,500.00	SF	\$	35,750.00
Roofing Isulation - With roofer				\$	-
		0.00	MD	\$	35,750.00

8.) Roofing		1			
EDPM at Flat Roof				\$	35,744.00
Shingles at slope Roof				\$	59,756.00
Gutters & Downspouts				\$	11,951.00
Roof Decking				\$	26,951.00
		0.00	MD	\$	134,402.00

9.) Windows and Doors		1			
New Custom Wood Windows 2'-6" x 5'-10"	10	44.00		\$	124,080.00
New Custom Wood Windows 1'-9" x 4'-0"	11	4.00		\$	11,280.00
New Exterior Doors	15, 16	3.00		\$	9,960.00
		48.45	MD	\$	145,320.00

10.) Division 9 Finishes		1			
Drywall & Framing		1.00	LS	\$	110,500.00
Wood Flooring		3,460.00	SF	\$	76,120.00
Ceramic		172.00	SF	\$	4,300.00
Paint		1.00	LS	\$	17,000.00
Paint at trim & doors		1.00	LS	\$	12,000.00
		0.00	MD	\$	219,920.00

11.) Division 10 - 12		1			
Toilet Accessories		3.00	EA	\$	4,500.00
Appliances		2.00	EA	\$	2,000.00
Window Treatments		48.00	EA	\$	19,200.00
		0.00	MD	\$	25,700.00

Duration - Months	8				
Total Cost no bond	\$ 2,971,708.74				
Work Task	Comment	Quantity	Unit	Total	
Building .xls					Page 4 of 5 1/26/2024

12.) Fire Protection		1			
Not Figured				\$	-
		0.00	MD	\$	-

13.) Plumbing		1			
Plumbing		1.00	LS	\$	32,500.00
		0.00	MD	\$	32,500.00

14.) HVAC		1			
HVAC Systems		1.00	LS	\$	123,000.00
		0.00	MD	\$	123,000.00

15.) Electrical		1			
Electrical, Fire Alarm, tele/data		1.00	LS	\$	46,500.00
AV		1.00	EA	\$	15,000.00
		0.00	MD	\$	61,500.00

16.) Allowances		1			
Service Tie-In				\$	125,000.00
Foundation Underpinning				\$	75,000.00
		0.00	MD	\$	200,000.00

17.) Design & Construction Contingency		1			
D&C Contingency (15%)				\$	365,501.35
		0.00	MD	\$	365,501.35

GENERAL CONDITIONS:	10%	1	LS	\$	284,020.00
1.) Demolition		1	0	\$	93,468.80
2.) Shoring/Scaffolding		1	0	\$	88,888.80
3.) Concrete		1	0	\$	8,700.00
4.) Masonry		1	0	\$	733,339.07
5.) Steel		1	0	\$	34,180.00
6.) Carpentry		1	0	\$	215,987.00
7.) Insulation		1	0	\$	35,750.00
8.) Roofing		1	0	\$	134,402.00
9.) Windows and Doors		1	0	\$	145,320.00
10.) Division 9 Finishes		1	0	\$	219,920.00
11.) Division 10 - 12		1	0	\$	25,700.00
12.) Fire Protection		1	0	\$	-
13.) Plumbing		1	0	\$	32,500.00
14.) HVAC		1	0	\$	123,000.00

Duration - Months		8			
Total Cost no bond		\$ 2,971,708.74			
Work Task	Comment	Quantity	Unit	Total	
15.) Electrical		1	0	\$	61,500.00
16.) Allowances		1	0	\$	200,000.00
17.) Design & Construction Contingency		1	0	\$	365,501.35
Total Costs				\$	2,802,177.03
OH&P	5.0%			\$	140,108.85
Subtotal				\$	2,942,285.88
Insurance	1%			\$	29,422.86
Total				\$	2,971,708.74