

PABST MANSION EXTERIOR RESTORATION


2000 WEST WISCONSIN AVENUE
MILWAUKEE, WI 53233

for:
PABST MANSION

2000 WEST WISCONSIN AVENUE
MILWAUKEE, WI 53233

by:
KLEIN AND HOFFMAN, INC.

328 EAST MASON STREET
MILWAUKEE, WI 53202
414-261-1345



SHEET INDEX:

A - ARCHITECTURAL	
A000	TITLESHEET & GENERAL NOTES
A001	SITE PLAN
A100	BASEMENT FLOOR PLAN
A101	FIRST FLOOR PLAN
A102	SECOND FLOOR PLAN
A103	ROOF PLAN
A200	SOUTH ELEVATION
A201	WEST ELEVATION
A202	NORTH ELEVATION
A203	EAST ELEVATION
A300	SOUTHWEST GABLE DETAIL ELEVATION
A301	SOUTHEAST GABLE DETAIL ELEVATION
A302	WEST GABLE DETAIL ELEVATION
A303	NORTHWEST GABLE DETAIL ELEVATION
A304	NORTHEAST GABLE DETAIL ELEVATION
A305	EAST GABLE DETAIL ELEVATION
A306	DORMER DETAIL ELEVATIONS
A307	CHIMNEY REPAIR DETAILS
A308	FIRE ESCAPE DETAIL ELEVATION
A400	GABLE REPAIR DETAILS
A401	GABLE AND MASONRY REPAIR DETAILS
A402	SIDE PORCH FLOOR DETAILS
A403	PORTE COCHERE RESTORATION DETAILS
A404	SOUTH PORCH RESTORATION DETAILS
A405	SOUTH PORCH RESTORATION DETAILS
A406	CONSERVATORY RESTORATION DETAILS
A407	IRONING PORCH RESTORATION DETAILS
A408	MISC. MASONRY REPAIR DETAILS
A500	ROOF DETAILS
A501	ROOF DETAILS
A502	WINDOW DETAILS
A503	WINDOW DETAILS
A504	WINDOW SCHEDULE
A505	WINDOW SCHEDULE
A506	WINDOW SCHEDULE
A600	MASONRY REPAIR
A601	MASONRY REPAIR
A602	TERRA COTTA TYPES

E - ELECTRICAL	
ED001	SITE DEMOLITION PLAN
E001	SITE PLAN
E002	ELECTRICAL SPECIFICATIONS
E100	BASEMENT PLAN

BUILDING DESCRIPTION:

THE FREDERICK PABST MANSION IS A HISTORIC THREE-STORY PLUS ATTIC MASONRY BEARING WALL BUILDING, LISTED ON THE NATIONAL REGISTER OF HISTORIC PLACES. DESIGNED BY GEORGE BOWMAN FERRY OF THE MILWAUKEE ARCHITECTURE FIRM FERRY AND CLAS, IT WAS CONSTRUCTED IN 1890-1892 AS THE RESIDENCE OF THE CAPTAIN FREDERICK PABST, SR. FAMILY. IT NOW SERVES AS A HISTORIC HOUSE MUSEUM OFFERING A VARIETY OF TOURS EDUCATING VISITORS ON THE HISTORY AND LIFESTYLE OF THE PABST FAMILY, INCLUDING THE ARCHITECTURE OF THE BUILDING.

THE BUILDING WAS DESIGNED IN THE FLEMISH RENAISSANCE REVIVAL STYLE. IT IS A LOAD-BEARING MASONRY STRUCTURE, WITH MULTI-WYTHE BRICK INTERIOR AND EXTERIOR BEARING WALLS ON STONE FOUNDATIONS. THE EXTERIOR WYTHE OF THE EXTERIOR MASONRY WALLS IS COMPOSED PRIMARILY OF BROWNISH PRESSED BRICK LAID IN FLEMISH BOND EXTENSIVELY ORNAMENTED WITH BROWN GLAZED TERRA COTTA.

THREE ARCHITECTURAL ELEMENTS WHICH PROJECT FROM THE MAIN VOLUME OF THE HOUSE ARE CLAD ALMOST ENTIRELY WITH TERRA COTTA: THE SIDE PORCH AND PORTE COCHERE ON THE WEST SIDE, THE SOUTH PORCH ON THE SOUTH SIDE, AND THE CONSERVATORY ON THE EAST SIDE.

PUNCHED WINDOW OPENINGS SPANNED BY TERRA COTTA FLAT ARCHES INCLUDE PRIMARILY WOOD DOUBLE-HUNG WINDOWS, WITH SOME ISOLATED UNIQUE WINDOW AND GLAZING TYPES.

THE MAIN STEEP-SLOPE ROOF IS A MANSARD ROOF WITH DUTCH PANTILE CLAY TILE. THE ROOF HAS COPPER FLASHINGS AT VALLEYS, RIDGES, AND WHERE THE ROOF ABUTS THE BACK OF MASONRY GABLE END WALLS. COPPER INLAY GUTTERS DRAIN TO COPPER DOWNSPOUTS WITH DECORATIVE COPPER COLLECTOR BOXES AND STRAPS.

LOW-SLOPE ROOFS AT THE MAIN ROOF AND AT THE PORTE COCHERE, SOUTH PORCH, AND CONSERVATORY ARE COMPOSED OF MODIFIED BITUMEN MEMBRANES ON WOOD DECKS SUPPORTED BY WOOD FRAMING.

SCOPE OF WORK SUMMARY:

THE AREA OF WORK FOR THE CURRENT EXTERIOR RESTORATION PROJECT INCLUDES ALL BUILDING FACADES AND ROOFS OF THE PABST MANSION, AND LIMITED AREAS OF THE SITE. NO WORK AT THE PABST PAVILION IS INCLUDED IN THE CURRENT PROJECT. THE SCOPE OF WORK GENERALLY INCLUDES:

- MASONRY: RESTORATION OF THE BUILDING'S MASONRY FACADES, INCLUDING: REBUILDING OF DETERIORATED ELEMENTS SUCH AS CHIMNEYS, PARAPETS, AND BALUSTRADES, REPAIR OR REPLACEMENT OF TERRA COTTA, ISOLATED REBUILDING OF THE OUTER WYTHE OF BRICK MASONRY, REPOINTING BRICK AND TERRA COTTA.
- LOW-SLOPE ROOFS: REMOVAL OF EXISTING MODIFIED BITUMEN ROOFS DOWN TO THE WOOD ROOF DECK. REPAIR OF WOOD ROOF DECK AND INSTALLATION OF NEW COVER BOARD, INSULATION, AND EPDM ROOF MEMBRANES.
- STEEP-SLOPE ROOFS: REMOVAL AND SALVAGE OF CLAY TILE ROOFING AS NECESSARY TO ALLOW FOR MASONRY RESTORATION. REPLACEMENT OF COPPER BASE AND COUNTER FLASHINGS AT BACK SIDES OF MASONRY PARAPETS. REINSTALLATION OF CLAY TILE ROOFING. REPAIR OR REPLACEMENT OF ISOLATED COPPER COLLECTOR BOXES AND DOWNSPOUTS.
- EXTERIOR WINDOWS AND DOORS: RESTORATION OF EXISTING WOOD WINDOWS, DOORS, AND FRAMES, AS INDICATED ON WINDOW SCHEDULE. PROVIDE NEW WOOD WINDOWS AS INDICATED TO MATCH ORIGINAL HISTORIC WINDOWS WHERE ORIGINAL HISTORIC WINDOWS HAVE BEEN REMOVED.
- STRUCTURAL REPAIRS: REBUILDING OF PORTE COCHERE MASONRY ARCHES INCLUDING REPLACEMENT OF EMBEDDED STRUCTURAL STEEL AND INSTALLATION OF NEW STEEL FLOOR BEAM SUPPORTING SIDE PORCH FLOOR.
- FLOORING RESTORATION: REMOVAL OF SIDE PORCH TILE AND GRANITE FLOORING AND GRANITE STAIR TREADS, INSTALLATION OF WATERPROOFING MEMBRANE, REINSTALLATION OF TILE AND GRANITE, AND RESTORATION OF SOUTH PORCH MOSAIC FLOOR.
- SITework: REMOVAL OF BUILDING-MOUNTED SECURITY LIGHTING AND INSTALLATION OF NEW POLE-MOUNTED SECURITY LIGHTING. JETTING OF UNDERGROUND STORM DRAINAGE SYSTEM TO ENSURE FREE-FLOWING DRAINAGE TO STREET.

TERRA COTTA PROCUREMENT PHASE:


DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. CONTRACTOR SHALL PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION, INCLUDING FULL HEIGHT OF CHIMNEYS AND BACKSIDES OF GABLE PARAPETS. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE, OR 3 DIMENSIONALLY LASER SCAN, SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.

ALTERNATES:

ALTERNATE NO. 1: REPAIRS TO SOUTH TERRACE WALLS, BALUSTRADE, AND STAIRS.

PROJECT PHASING:

PROJECT CONSTRUCTION WILL BE COMPLETED IN TWO PHASES UNDER TWO SEPARATE CONTRACTS. PHASE I TO BE COMPLETED IN 2025, PHASE II TO BE COMPLETED IN 2027. WORK TO BE COMPLETED AS PART OF PHASE II WHICH IS DEPICTED IN THESE DRAWINGS IS INDICATED AS REMOVED FROM THE SCOPE OF PHASE I BY HATCHED REVISION CLOUDS:



GENERAL PROJECT NOTES:

- CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO COMMENCING CONSTRUCTION.
- ALL WORK OF THE CONTRACTOR AND ITS SUBCONTRACTORS SHALL BE IN ACCORDANCE WITH ALL APPLICABLE BUILDING CODES AND COMPLY WITH ALL GOVERNING LAWS - FEDERAL, STATE, AND LOCAL JURISDICTIONS.
- CONTRACTOR SHALL REPORT IMMEDIATELY ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND THOSE ON THE CONSTRUCTION DOCUMENTS TO THE ARCHITECT/ENGINEER (A/E).
- PRIOR TO THE COMMENCEMENT OF THE WORK, THE CONTRACTOR SHALL CAREFULLY EXAMINE THE CONSTRUCTION AREA TO VERIFY UTILITIES AND OTHER EXISTING CONDITIONS, WHETHER OR NOT SHOWN ON THE DRAWINGS.
- MAINTAIN ACCESS TO BUILDING AT ALL TIMES DURING THE DURATION OF CONSTRUCTION. MAINTAIN EXISTING MEANS OF EGRESS AT ALL TIMES.
- DO NOT SCALE DRAWINGS.
- USE MEANS NECESSARY TO PREVENT DUST FROM BECOMING A NUISANCE TO THE PUBLIC, NEIGHBORS, AND TO OTHER WORK BEING PERFORMED ON OR NEAR THE CONSTRUCTION SITE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING, FITTING, OR PATCHING THAT MAY BE REQUIRED TO COMPLETE THE WORK.
- REPETITIVE FEATURES IN THE CONSTRUCTION DOCUMENTS ARE OFTEN DRAWN ONLY ONCE AND SHALL BE COMPLETELY PROVIDED AS IF DRAWN IN FULL.
- CONTRACTOR TO PROVIDE GENERAL BLOCKING AS REQUIRED TO COMPLETE WORK AS DRAWN AND/OR SPECIFIED.
- THE A/E WILL NOT RECOMMEND OWNER ACCEPTANCE OF ANY WORK PERFORMED BY CONTRACTOR OR SUB-CONTRACTORS THAT DEVIATES FROM THESE CONSTRUCTION DOCUMENTS, UNLESS FIRST APPROVED BY THE A/E.
- THE WORK INCLUDES THE FURNISHING OF ALL LABOR, MATERIALS, EQUIPMENT, AND SERVICES NECESSARY FOR THE COMPLETION OF ALL WORK SHOWN AND DESCRIBED IN THE CONSTRUCTION DOCUMENTS PREPARED BY THE A/E. ALL WORK IS TO BE DONE BY THE CONTRACTOR AND/OR ITS SUB-CONTRACTORS, UNLESS NOTED OTHERWISE, IN A WORKMANLIKE MANNER.
- WHERE SPECIFIC PRODUCTS AND MANUFACTURERS ARE SPECIFIED, THE CONTRACTOR MAY USE AN EQUIVALENT IF SUBMITTED TO AND APPROVED BY THE ARCHITECT. IN SUCH A CASE THE CONTRACTOR SHALL SUBMIT SPECIFICATION SHEETS AND SAMPLES AS APPLICABLE FOR THE A/E'S REVIEW PRIOR TO SUBMITTING BID.
- THE CONTRACTOR SHALL HAVE THE CONSTRUCTION AREA SWEEPED AND IN ORDER ON A DAILY BASIS. DAILY REMOVE ALL DEBRIS. PERFORM A FINAL CLEAN-UP AT THE SUBSTANTIAL COMPLETION OF CONSTRUCTION.
- CONTRACTOR SHALL PROVIDE ALL PERMITS NECESSARY FOR CONSTRUCTION.

GENERAL REPAIR NOTES:

- THESE NOTES ARE GENERAL AND SUPPLEMENTAL TO THE SPECIFICATIONS. THESE NOTES APPLY TO THE ENTIRE PROJECT UNLESS MODIFIED OR NOTED OTHERWISE IN THE CONTRACT DOCUMENTS.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR ALL METHODS AND MEANS OF CONSTRUCTION AND FOR JOB SITE SAFETY. PROVIDE PROPER PROTECTIVE CANOPIES AND BARRICADES TO MAINTAIN THE PUBLIC SAFETY AND TO PREVENT DAMAGE TO ADJACENT PROPERTY. DESIGN AND CONSTRUCT IN ACCORDANCE WITH THE LOCAL PREVAILING CODES AND OF ALL OTHER APPLICABLE REGULATORY AGENCIES.
- THE INFORMATION CONTAINED ON THE DRAWINGS IS IN ITSELF INCOMPLETE AND VOID UNLESS USED IN CONJUNCTION WITH ALL THE CONTRACT DOCUMENTS AND WITH ALL THE SPECIFICATIONS, TRADE PRACTICES OR APPLICABLE STANDARDS, CODES, ETC., INCORPORATED THEREIN BY REFERENCE WHICH THE CONTRACTOR CERTIFIES KNOWLEDGE OF BY SIGNING THE CONTRACT.
- ALL SECTIONS, DETAILS, AND NOTES ARE INTENDED TO BE TYPICAL AND SHALL APPLY TO SIMILAR SITUATIONS.
- ALL DIMENSIONS AND SIZES OF EXISTING CONSTRUCTION INDICATED ON DRAWINGS SHALL BE CONSIDERED APPROXIMATE AND SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR.
- CONTRADICTIONS BETWEEN ACTUAL FIELD CONDITIONS SHOWN ON THE DRAWINGS SHALL BE REPORTED TO THE ARCHITECT. MODIFICATIONS REQUIRED BY SUCH CONTRADICTIONS SHALL BE APPROVED BY THE A/E OR IF NECESSARY, FURTHER DETAILS WILL BE DEVELOPED.
- THE EXTENT OF THE REPAIR WORK MAY NOT BE LIMITED TO THE DETAILS OR LOCATIONS SHOWN. IF THE NECESSITY FOR ADDITIONAL REPAIR WORK BECOMES APPARENT AS THE CONSTRUCTION PROCEEDS, ADDITIONAL DETAILS, IF REQUIRED, WILL BE DEVELOPED AND PROVIDED.
- THE CONTRACTOR SHALL NOTIFY THE A/E OF ANY ITEMS NOT SHOWN OR INDICATED IN THE CONSTRUCTION DOCUMENTS THAT, IN HIS OPINION, REQUIRE REPAIR OR MODIFICATION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF ALL SHORING, BRACING AND FALSEWORK REQUIRED FOR THE REPAIR WORK.
- IF THE CONTRACTOR ENCOUNTERS PROBLEMS IN PERFORMANCE OF THE WORK INDICATED, HE SHALL BRING SUCH PROBLEMS TO THE ATTENTION OF THE A/E FOR PROPER ACTION BEFORE WORK CONTINUES.
- REPLACEMENT STEEL LINTELS, SHELF ANGLES, OR ANY OTHER STRUCTURAL SHAPES REQUIRED SHALL BE ASTM A36, FY = 36,000 P.S.I. (MIN.), GALVANIZED.
- ANCHORS AND FASTENERS FOR MASONRY SHALL BE FABRICATED FROM THE FOLLOWING MATERIAL.
 - TERRA COTTA: STAINLESS STEEL AISI GRADE 304, UNLESS SPECIFIED OTHERWISE.
 - BRICK: STAINLESS STEEL AISI GRADE 304, UNLESS SPECIFIED OTHERWISE.
 - BOLTS: STAINLESS STEEL AISI GRADE 304 FOR EXPANSION BOLTS AND ADHESIVE ANCHORS. NUTS AND WASHERS SHALL BE TYPE 304 STAINLESS STEEL.
- THE CONTRACTOR SHALL PROTECT FROM DAMAGE DUE TO WORK OPERATIONS AND SCAFFOLD RIGGING EQUIPMENT THE FOLLOWING EXISTING CONSTRUCTION, BUT NOT LIMITED TO:
 - COPINGS.
 - PROJECTING TERRA COTTA BELT COURSES, CORNICES, AND ORNAMENT.
 - GUTTERS AND DOWNSPOUTS.
 - CHIMNEYS AND STACKS.
 - VENTS AND SOIL PIPES.
 - FLASHING.
 - ROOFING.
 - WINDOWS & DOORS.
 - MECHANICAL UNITS AND DUCTWORK.
 - OTHER EXISTING CONSTRUCTION.
- THE PABST MANSION IS ON THE NATIONAL REGISTER OF HISTORIC PLACES AND IS A DESIGNATED HISTORIC STRUCTURE IN THE CITY OF MILWAUKEE. ALL NEW MATERIALS, INCLUDING NEW TERRA COTTA AND BRICK MASONRY, MORTAR, AND PATCHING MATERIAL WILL MATCH HISTORIC COLOR, JOINT PROFILE, TEXTURE, AND STRENGTH/TYPE TO MATCH HISTORIC CLEANED MASONRY. SAMPLES AND MOCK-UPS SHALL BE REVIEWED AND APPROVED BY THE A/E, OWNER, AND THE MILWAUKEE HISTORIC PRESERVATION COMMISSION PRIOR TO ORDER AND INSTALLATION.

For Local Approvals:

Klein & Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title

**TITLESHEET & GENERAL
NOTES**

KH Job# 10446.0001

Drawing Number

Date JUNE 2023

Designed DLW



Drawn DLW

Checked TAG

A000

of 38

Jun 21, 2023 - 8:56:03 am Dwerick H:\JOBS\Pabst Mansion-10446\10446.0001R_Envelope_Restoration\01-TITLE SHEET & SITE PLAN.dwg




NOTES:

1. ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.
2. BUILDING TO REMAIN ACCESSIBLE TO THE PUBLIC FOR THE DURATION OF CONSTRUCTION. CONTRACTOR TO MAINTAIN PUBLIC SAFETY AT ENTIRE SITE INCLUDING BUILDING PERIMETER AND ENTRANCES. PROVIDE PEDESTRIAN PROTECTION.
3. CONTRACTOR SHALL COORDINATE WITH CITY FOR ANY PROPOSED OCCUPATION OF PUBLIC RIGHTS OF WAY FOR EQUIPMENT, STORAGE, OR STAGING.
4. CONTRACTOR SHALL COORDINATE WITH UTILITY COMPANIES TO TEMPORARILY PROTECT OR RELOCATED UTILITY INFRASTRUCTURE IF NECESSARY TO ALLOW FOR THE WORK.

LEGEND:

PROPOSED STAGING AREAS. PROTECT AND SECURE WITH FENCING.



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.


LICENSE EXPIRES NOVEMBER 30, 2024
Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
SITE PLAN

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A001

Jun 21, 2023 - 8:56:58 am D:\DBS\Project\Restoration\10446\10446_0001R_Envelope_Restoration\02-FLOOR PLANS.dwg



NOTES:

- ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.
- WORK SHOWN ON FLOOR PLANS AND ROOF PLAN SHALL BE COORDINATED WITH WORK SHOWN ON ELEVATIONS. REFER TO ELEVATION DRAWINGS A200 - A203.

LEGEND:

- X
XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- X
XXX DOOR NUMBER
- DX
DOWNSPOUT NUMBER
- XXX ROOM NUMBER

REPAIR LEGEND:

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
BASEMENT FLOOR PLAN

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A100

0 4 8 12 16
SCALE: 3/16" = 1'-0"



- NOTES:**
1. ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.
 2. WORK SHOWN ON FLOOR PLANS AND ROOF PLAN SHALL BE COORDINATED WITH WORK SHOWN ON ELEVATIONS. REFER TO ELEVATION DRAWINGS A200 - A203.

LEGEND:

- | | |
|--|--|
| | WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506) |
| | DOOR NUMBER |
| | DOWNSPOUT NUMBER |
| | ROOM NUMBER |

REPAIR LEGEND:

Date	Description
01/19/24	IFC - PHASE I
01/21/23	ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED
UNDER MY SUPERVISION AND TO THE BEST OF MY
KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN
COMMERCIAL BUILDING CODE

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

FIRST FLOOR PLAN

KH Job# 10446.0001

Drawing Number

Date **JUNE 2023**

A 10

Designed	DLW
----------	-----


 $A \mid ()$

Drawn	DLW
-------	-----


7. A. 100

38

Jun 21, 2023 - 8:56:58 am Dweirick H:\DBS\pabst Mansion-10446\0001R_Envelope Restoration\02-FLOOR PLANS.dwg



1 SECOND FLOOR PLAN
SCALE: 3/16" = 1'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE

LICENSE EXPIRES NOVEMBER 30, 2024


Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**


Drawing Title
SECOND FLOOR PLAN

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A102

Jun 21, 2023 - 8:56:58 am Dweirick H:\DBS\Pabst Mansion-10446\10446.0001R_Envelope_Restoration\02-FLOOR PLANS.dwg



1 ROOF PLAN
SCALE: 3/16" = 1'-0"



NOTES:

- ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.
- COORDINATE ROOF REPAIR AND REPLACEMENT WORK WITH MASONRY FACADE, PARAPET, AND CHIMNEY RESTORATION. REFER TO DETAIL ELEVATIONS ON SHEETS A300-A308 FOR SCOPE OF MASONRY FACADE, PARAPET, AND CHIMNEY RESTORATION.

LEGEND:

X
XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE)

X
XXX DOOR NUMBER


DXX DOWNSPOUT NUMBER

REPAIR LEGEND:

REMOVE EXISTING MODIFIED BITUMEN ROOF SYSTEM AND PROVIDE NEW FULLY ADHERED COVER BOARD AND EPDM ROOF MEMBRANE. REFER TO DETAILS 1/A501 AND 2/A501.

REMOVE AND REINSTALL CLAY TILE ROOFING TO ALLOW FOR MASONRY RESTORATION WORK. REFER TO DETAIL 4/A500.

REPLACE EXISTING COPPER RIDGE FLASHING WITH NEW TO MATCH EXISTING. REFER TO DETAILS 4/A500 AND 4/A501.



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

No.	Date	Description
	12/19/24	IFC - PHASE I
	6/21/23	ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
ROOF PLAN

KH Job#	10446.0001	Drawing Number
Date	JUNE 2023	A103
Designed	DLW	
Drawn	DLW	
Checked	TAG	


of 38

Jun 21, 2023-9:07:59 am Dweirick H:\DBS\Pabst Mansion-10446\0001R_Envelope_Restoration\03-ELEVATIONS.dwg

- TOP OF FINIAL
EL. 57'-0"
- ROOF
EL. 47'-5"
- GUTTER
EL. 30'-10"
- FIFTH BELT COURSE
EL. 27'-7"
- THIRD FLOOR
EL. 25'-5"
- FOURTH BELT COURSE
EL. 24'-7"
- THIRD BELT COURSE
EL. 15'-2 3/4"
- SECOND FLOOR
EL. 13'-0"
- SECOND BELT COURSE
EL. 13'-0"
- FIRST BELT COURSE
EL. 1'-11"
- FIRST FLOOR
EL. 0'-0"



1 SOUTH ELEVATION
SCALE: 1/4" = 1'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**


**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
SOUTH ELEVATION

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A200

Jun 21, 2023--9:07:59 am Dweirick H:\JOBS\Pabst Mansion--10446\10446.0001R_Envelope_Restoration\03-ELEVATIONS.dwg

- TOP OF FINIAL
EL. 57'-0"
- ROOF
EL. 47'-5"
- GUTTER
EL. 30'-10"
- FIFTH BELT COURSE
EL. 27'-7"
- THIRD FLOOR
EL. 25'-5"
- FOURTH BELT COURSE
EL. 24'-7"
- THIRD BELT COURSE
EL. 15'-2 3/4"
- SECOND FLOOR
EL. 13'-0"
- SECOND BELT COURSE
EL. 13'-0"
- FIRST BELT COURSE
EL. 1'-11"
- FIRST FLOOR
EL. 0'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**
**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**



Drawing Title
WEST ELEVATION

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A201




Jun 21, 2023--9:07:59 am D:\Projects\10446\10446_0001R_Envelope_Restoration\03-ELEVATIONS.dwg

- TOP OF FINIAL
EL. 57'-0"
- ROOF
EL. 47'-5"
- GUTTER
EL. 30'-10"
- FIFTH BELT COURSE
EL. 27'-7"
- THIRD FLOOR
EL. 25'-5"
- FOURTH BELT COURSE
EL. 24'-7"
- THIRD BELT COURSE
EL. 15'-2 3/4"
- SECOND FLOOR
EL. 13'-0"
- SECOND BELT COURSE
EL. 13'-0"
- FIRST BELT COURSE
EL. 1'-11"
- FIRST FLOOR
EL. 0'-0"

REPAIR LEGEND:


-  REBUILD FULL DEPTH OF BRICK AND TERRA COTTA MASONRY WALL.
-  REBUILD OUTER WYTHE OF BRICK AND/OR TERRA COTTA AND REPOINT BACK-UP MASONRY 100%.

LEGEND:


-  WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
-  DOOR NUMBER
-  DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE 1 WORK FOR A/E INSPECTION. PHASE 1 INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



1 NORTH ELEVATION
SCALE: 1/4" = 1'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION


2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233


Drawing Title

NORTH ELEVATION

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38

A202



	12/19/24	IFC - PHASE I	
	6/21/23	ISSUED FOR BID	
No.	Date	Description	
<p>I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.</p>			
<p>LICENSE EXPIRES NOVEMBER 30, 2024</p>			
Project Description			
<p>PABST MANSION EXTERIOR RESTORATION</p>			
<p>2000 WEST WISCONSIN AVENUE MILWAUKEE, WI 53233</p>			
Drawing Title			
<p>EAST ELEVATION</p>			
KH Job# 10446.0001 Date JUNE 2023 Drawn DLW Checked TAG		Drawing Number <div style="font-size: 48pt; font-weight: bold;">A203</div> of 38	

Jun 21, 2023--9:09:08 am Dweirick H:_DBS\Pabst Mansion--10446\10446.0001R_Envelope Restoration\03.1--DETAIL ELEVATIONS.dwg

TOP OF FINIAL
EL. 57'-0"


ROOF
EL. 47'-5"

GUTTER
EL. 30'-10"

FIFTH BELT COURSE
EL. 27'-7"

REPOINT BRICK AND TERRA COTTA MASONRY, WHICH IS
NOT INDICATED FOR REPAIR, TO THE OUTER WYTHE
REBUILD, 100% ABOVE FIFTH BELT COURSE.

REPOINT FIFTH
BELT COURSE 100%



- NOTES:
1. REMOVE CLAY TILE ROOFING ALONG BACK-SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK-SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK-SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

1 SOUTH ELEVATION - WEST GABLE

SCALE: 1/2" = 1'-0"

REPAIR LEGEND:

- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:

1. TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
2. DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE 1 WORK FOR A/E INSPECTION. PHASE 1 INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - 2.1. REMOVE AND REINSTALL TERRA COTTA
 - 2.2. REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - 2.3. GROUT INJECT TERRA COTTA CRACK
 - 2.4. REBUILD OUTER WYTHE OF BRICK
 - 2.5. LIMESTONE REPLACEMENT
 - 2.6. LIMESTONE DUTCHMAN REPAIR
 - 2.7. INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - 2.8. REPOINT MORTAR JOINTS

- REPOINT BRICK AND TERRA COTTA DORMERS 100%.
- PERFORM IN-SITU REPAIRS TO TERRA COTTA AS DESIGNATED BY A/E.
- PROVIDE BACKER ROD AND SEALANT AT WATER TABLE 100%. SEALANT TYPE 3.
- PROVIDE COPPER DRIP EDGE FLASHING. REFER TO DETAIL 4/A401.
- PROVIDE BACKER ROD AND SEALANT AT TRANSOM WINDOW SILL WASH JOINT. SEALANT TYPE 3.
- EXISTING COPPER GUTTER TO REMAIN. REPLACE SEALANT AT COPPER TERMINATIONS 100%. SEALANT TYPE 2.

- REMOVE AND REINSTALL ALL DOWNSPOUTS TO ALLOW FOR MASONRY REPAIR WORK. REPAIR OR REPLACE DOWNSPOUTS AS DESIGNATED BY A/E. REFER TO DETAILS 5/A500 AND 6/A500.

0 2 4 6
SCALE: 1/2" = 1'-0"

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No: 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**SOUTHWEST GABLE
DETAIL ELEVATION**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A300

Jun 21, 2023--9:09:08 am Dweirick H:\DBS\Pabst Mansion--10446\10446.0001R_Envelope Restoration\03.1--DETAIL ELEVATIONS.dwg

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:


- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE I WORK FOR A/E INSPECTION. PHASE I INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



NOTES:

- REMOVE CLAY TILE ROOFING ALONG BACK-SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK-SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK-SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

1 SOUTH ELEVATION - EAST GABLE
SCALE: 1/2" = 1'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**SOUTHEAST GABLE
DETAIL ELEVATION**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A301

Jun 21, 2023--9:09:08 am Dweirick H:_DSS\Pabst Mansion--10446\10446.0001R_Envelope_Restoration\03.1--DETAIL ELEVATIONS.dwg

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHER TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHER OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- X
XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- X
XXX DOOR NUMBER
- DXX DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE I WORK FOR A/E INSPECTION. PHASE I INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHER OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



NOTES:

- ACTUAL CONFIGURATION OF STRUCTURAL STEEL IS UNKNOWN. STEEL SHOWN IN THIS DETAIL IS CONJECTURAL. ACTUAL CONFIGURATION TO BE CONFIRMED IN THE FIELD DURING CONSTRUCTION.

2 LINTEL DETAIL SECTION

SCALE: 3" = 1'-0"

ROOF
EL. 47'-5"


GUTTER
EL. 30'-10"

FIFTH BELT COURSE
EL. 27'-7"

REPOINT BRICK AND TERRA COTTA MASONRY, WHICH IS NOT INDICATED FOR FULL DEPTH OR OUTER WYTHER REBUILD, 100% ABOVE FIFTH BELT COURSE.

REPOINT FIFTH BELT COURSE 100%.

D10




NOTES:

- REMOVE CLAY TILE ROOFING ALONG BACK-SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK-SIDE OF PARAPETS 100%. REBUILD OUTER WYTHER OF BRICK AT BACK-SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

1 WEST GABLE

SCALE: 1/2" = 1'-0"



CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK AND TERRA COTTA PARAPET ABOVE ROOF LINE AS INDICATED. SALVAGE AND REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. SALVAGE AND REUSE EXISTING TERRA COTTA EXCEPT FOR UNITS DESIGNATED BY A/E TO BE REPLACED. REPAIR EXISTING TERRA COTTA TO BE REUSED AS DESIGNATED BY A/E.

ROOF LINE BEYOND.

REBUILD OUTER WYTHER OF BRICK, INCLUDING FLEMISH BOND HEADERS. SALVAGE AND REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

REMOVE AND REINSTALL ALL DOWNSPOUTS TO ALLOW FOR MASONRY REPAIR WORK. REPAIR OR REPLACE DOWNSPOUTS AS DESIGNATED BY A/E. REFER TO DETAILS 5/A500 AND 6/A500.

REBUILD TERRA COTTA, OUTER WYTHER BRICK, AND BACK-UP MASONRY TO ALLOW FOR CLEANING, PAINTING, AND FLASHING OF STEEL LINTEL. REFER TO DETAIL 2/A302.

D11

EXISTING STEEL LINTEL TO REMAIN. CLEAN, PAINT, AND FLASH. REFER TO DETAIL 2/A302.

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**WEST GABLE DETAIL
ELEVATION**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38

A302

Jun 21, 2023--9:09:08 am Dwerick H:_DBS\Pabst Mansion--10446\10446.0001R_Envelope Restoration\03.1--DETAIL ELEVATIONS.dwg

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA; REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHER TERRA COTTA; REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL; REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE; MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHER OF BRICK MASONRY WALL, INCLUDING HEADERS; REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE; MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT/INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHER OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

NORTHWEST GABLE
DETAIL ELEVATION

KH Job# 10446.0001
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG

Drawing Number

A303
of 38

Jun 21, 2023--9:09:08 am D:_DBS\Project Mansion--10446\10446.0001R_Envelope Restoration\03.1--DETAIL ELEVATIONS.dwg

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT/INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



NOTES:

- REMOVE CLAY TILE ROOFING ALONG BACK-SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK-SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK-SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

1 NORTH ELEVATION - EAST GABLES
SCALE: 1/2" = 1'-0"

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**





**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**NORTHEAST GABLE
DETAIL ELEVATION**




KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A304

Jun 21, 2023-9:09:08 am Dwerick H:\JOBS\Pabst Mansion-10446\10446.0001R_Envelope Restoration\03.1-DETAIL ELEVATIONS.dwg

REPAIR LEGEND:

-  CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
-  CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
-  CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
-  CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

-  WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
-  DOOR NUMBER
-  DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT/INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS

ROOF
EL. 47'-5"

GUTTER
EL. 30'-10"

FIFTH BELT COURSE
EL. 27'-7"

REPOINT BRICK AND TERRA COTTA MASONRY WHICH IS NOT INDICATED FOR FULL DEPTH OR OUTER WYTHE REBUILD. 100% ABOVE FIFTH BELT COURSE.

REPOINT FIFTH BELT COURSE 100%

NOTES:

- REMOVE CLAY TILE ROOFING ALONG BACK-SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK-SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK-SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER-BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

1 EAST GABLE
SCALE: 1/2" = 1'-0"

CAREFULLY REMOVE AND REINSTALL FULL DEPTH TERRA COTTA UNITS. REUSE EXISTING TERRA COTTA EXCEPT FOR UNITS DESIGNATED BY A/E TO BE REPLACED. REPAIR EXISTING TERRA COTTA TO BE REUSED AS DESIGNATED BY A/E.

ROOF LINE BEYOND.

PROVIDE REGLET-SET COPPER DRIP EDGE FLASHING.

REMOVE AND REINSTALL ALL DOWNSPOUTS TO ALLOW FOR MASONRY REPAIR WORK. REPAIR OR REPLACE DOWNSPOUTS AS DESIGNATED BY A/E. REFER TO DETAILS 5/A500 AND 6/A500.

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title

**EAST GABLE DETAIL
ELEVATION**

KH Job# 10446.0001

Date JUNE 2023

Designed DLW

Drawn DLW

Checked TAG

Drawing Number

A305

of 38

Jun 21, 2023 - 9:09:08 am Dwerick H:\JOBS\Pabst Mansion-10446\10446.0001R_Envelope Restoration\03.1-DETAIL ELEVATIONS.dwg

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT/INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS




NOTES:

- REMOVE CLAY TILE ROOFING ALONG BACK SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

1 WEST ELEVATION DORMERS

SCALE: 1/2" = 1'-0"




NOTES:

- REMOVE CLAY TILE ROOFING ALONG BACK SIDE OF PARAPETS TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPOINT BACK SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK SIDE OF PARAPETS AS DESIGNATED BY A/E. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%, AND REINSTALL EXISTING CLAY TILE ROOFING.

2 EAST ELEVATION DORMERS

SCALE: 1/2" = 1'-0"



For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title

**DORMER DETAIL
ELEVATIONS**

KH Job# 10446.0001

Date JUNE 2023

Designed DLW

Drawn DLW

Checked TAG

Drawing Number

A306

of 38

Jun 21, 2023--9:09:08 am Dweirick H:_DSS\Project Mansion--10446\10446.0001R_Envelope Restoration\03.1--DETAIL ELEVATIONS.dwg

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:


- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:



- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE I WORK FOR A/E INSPECTION. PHASE I INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



1 WEST FREESTANDING CHIMNEY
SCALE: 1/2" = 1'-0"



2 CENTER CHIMNEY
SCALE: 1/2" = 1'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**


Drawing Title

CHIMNEY REPAIR DETAILS

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38

A307

Jun 21, 2023--9:09:08 am Dweirick H:_0BS\pabst Mansion--10446\10446.0001R_Envelope_Restoration\03.1--DETAIL ELEVATIONS.dwg



1 PARTIAL EAST ELEVATION - FIRE ESCAPE REMOVAL
SCALE: 3/8" = 1'-0"

NOTES:


- DRAWINGS 1/A308 AND 2/A308 SHOW PARTIAL ELEVATIONS FOLLOWING REMOVAL OF THE EXISTING FIRE ESCAPE. REFER TO DRAWING 1/A203 FOR CONFIGURATION OF EXISTING FIRE ESCAPE TO BE REMOVED.
- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE I WORK FOR A/E INSPECTION. PHASE I INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS

REPAIR LEGEND:


- REMOVE THROUGH-BOLT ANCHOR AND REPAIR BRICK. REFER TO DETAILS 5/A401 AND 6/A401.
- REMOVE SCREW BOLT ANCHOR AND REPAIR BRICK. REFER TO DETAIL 7/A401.
- REMOVE THROUGH-BOLT ANCHOR AND REPAIR TERRA COTTA. REFER TO DETAILS 8/A401 AND 9/A401.
- REMOVE SCREW BOLT ANCHOR AND REPAIR TERRA COTTA. REFER TO DETAIL 10/A401.
- REMOVE SCREW BOLT ANCHOR FROM WOOD WINDOW FRAME AND PROVIDE WOOD EPOXY REPAIR TO FRAME.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER



2 PARTIAL NORTH ELEVATION - FIRE ESCAPE REMOVAL
SCALE: 3/8" = 1'-0"



For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024


Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**FIRE ESCAPE DETAIL
ELEVATION**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A308

Jun 21, 2023 - 9:09:08 am Dweirick H:\DBS\Pabst Mansion-10446\0001R_Envelope Restoration\03.1-DETAIL ELEVATIONS.dwg



NOTES:

1. TERRA COTTA ANCHORAGE SHOWN IS CONCEPTUAL. REVIEW TERRA COTTA ANCHORAGE IN THE FIELD WITH A/E.
2. TERRA COTTA CELL AND WEB CONFIGURATIONS ARE ASSUMED AND ARE TO BE VERIFIED IN THE FIELD UPON REMOVAL.

1 GABLE PARAPET REBUILD DETAIL ELEVATION

SCALE: 1 1/2" = 1'-0"

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:

1. TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
2. DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE 1 WORK FOR A/E INSPECTION. PHASE 1 INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - 2.1. REMOVE AND REINSTALL TERRA COTTA
 - 2.2. REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - 2.3. GROUT INJECT TERRA COTTA CRACK
 - 2.4. REBUILD OUTER WYTHE OF BRICK
 - 2.5. LIMESTONE REPLACEMENT
 - 2.6. LIMESTONE DUTCHMAN REPAIR
 - 2.7. INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - 2.8. REPOINT MORTAR JOINTS




NOTES:

1. TERRA COTTA ANCHORAGE SHOWN IS CONCEPTUAL. REVIEW TERRA COTTA ANCHORAGE IN THE FIELD WITH A/E.
2. TERRA COTTA CELL AND WEB CONFIGURATIONS ARE ASSUMED AND ARE TO BE VERIFIED IN THE FIELD UPON REMOVAL.

2 GABLE PARAPET REBUILD DETAIL SECTION

SCALE: 1 1/2" = 1'-0"

CAREFULLY REMOVE AND SALVAGE CLAY TILE ROOFING ALONG BACK-SIDE OF PARAPET TO ALLOW FOR MASONRY AND FLASHING REPAIRS. REPLACE EXISTING COPPER BASE AND COUNTER FLASHINGS 100%. REFER TO ROOFING DETAILS ON SHEET A500.



NOTES:

1. TERRA COTTA ANCHORAGE SHOWN IS CONCEPTUAL. REVIEW TERRA COTTA ANCHORAGE IN THE FIELD WITH A/E.
2. TERRA COTTA CELL AND WEB CONFIGURATIONS ARE ASSUMED AND ARE TO BE VERIFIED IN THE FIELD UPON REMOVAL.
3. RAFTER ANCHOR CONFIGURATION IS ASSUMED AND IS TO BE VERIFIED IN THE FIELD DURING CONSTRUCTION.

3 GABLE PARAPET REBUILD DETAIL SECTION

SCALE: 1 1/2" = 1'-0"



SCALE: 1 1/2" = 1'-0"

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

GABLE REPAIR DETAILS

KH Job# 10446.0001

Date JUNE 2023

Designed DLW

Drawn DLW


Checked TAG

Drawing Number

A400


of 38

Jun 21, 2023--9:09:08 am Dweirick H:_DBS\Pabst Mansion--10446\10446.0001R_Envelope_Restoration\03.1--DETAIL ELEVATIONS.dwg




NORTH GABLE PARAPET REBUILD DETAIL ELEVATION

1
SCALE: 1 1/2" = 1'-0"




NORTH GABLE PARAPET REBUILD DETAIL SECTION

2
SCALE: 1 1/2" = 1'-0"




DORMER JAMB REBUILD - DETAIL PLAN

3
SCALE: 3" = 1'-0"




DORMER DRIP EDGE - DETAIL SECTION

4
SCALE: 3" = 1'-0"




THROUGH BOLT REMOVAL- BRICK

5
SCALE: 3" = 1'-0"




THROUGH BOLT REMOVAL - BRICK

6
SCALE: 3" = 1'-0"




SCREW BOLT REMOVAL - BRICK

7
SCALE: 3" = 1'-0"




SCREW BOLT REMOVAL - TERRA COTTA

10
SCALE: 3" = 1'-0"




GABLE WALL DRIP EDGE - DETAIL SECTION

11
SCALE: 1' = 1'-0"



THROUGH BOLT REMOVAL - TERRA COTTA

8
SCALE: 3" = 1'-0"



THROUGH BOLT REMOVAL - TERRA COTTA

9
SCALE: 3" = 1'-0"

REPAIR LEGEND:


- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD FULL DEPTH TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE, SALVAGE, AND REBUILD OUTER WYTHE TERRA COTTA. REPAIR OR REPLACE TERRA COTTA AS DESIGNATED BY A/E.
- CAREFULLY DISMANTLE AND REBUILD FULL DEPTH OF BRICK MASONRY WALL. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.
- CAREFULLY DISMANTLE AND REBUILD OUTER WYTHE OF BRICK MASONRY WALL, INCLUDING HEADERS. REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE. MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT DIMENSIONS AND PROFILES.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

NOTES:

- TERRA COTTA PROCUREMENT PHASE. DUE TO THE FACT THAT TERRA COTTA HAS AN ESPECIALLY LONG LEAD TIME, 100% OF TERRA COTTA ON THE BUILDING SHALL BE SURVEYED AND UNITS REQUIRING REPLACEMENT SHALL BE IDENTIFIED AS PART OF A TERRA COTTA PROCUREMENT PHASE AT LEAST 8 MONTHS PRIOR TO THE START OF GENERAL RESTORATION WORK. PROVIDE ACCESS TO 100% OF THE BUILDING FACADES FOR A/E INSPECTION. A/E WILL IDENTIFY TERRA COTTA UNITS REQUIRING REPLACEMENT. BASED ON THE A/E'S SURVEY, THE CONTRACTOR SHALL IDENTIFY AND REMOVE SAMPLES OF EACH UNIQUE TERRA COTTA UNIT TYPE WHICH REQUIRES REMOVAL FROM THE BUILDING FOR USE AS A MODEL BY THE TERRA COTTA MANUFACTURER.
- DURING GENERAL RESTORATION WORK, PROVIDE ACCESS TO 100% OF THE BUILDING FACADES IN THE AREA OF PHASE I WORK FOR A/E INSPECTION. PHASE I INCLUDES THE SOUTH ELEVATION AND PART OF THE WEST ELEVATION. COMPLETE FACADE REPAIRS AS INDICATED ON THE DRAWINGS AND AS DESIGNATED BY A/E DURING INSPECTIONS. REPAIRS WILL INCLUDE, BUT MAY NOT BE LIMITED TO:
 - REMOVE AND REINSTALL TERRA COTTA
 - REMOVE, REPAIR (PIN AND EPOXY), AND REINSTALL TERRA COTTA
 - GROUT INJECT TERRA COTTA CRACK
 - REBUILD OUTER WYTHE OF BRICK
 - LIMESTONE REPLACEMENT
 - LIMESTONE DUTCHMAN REPAIR
 - INSTALL ANCHORED STONE OR TERRA COTTA PATCH
 - REPOINT MORTAR JOINTS



For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

**PABST MANSION
EXTERIOR RESTORATION**






**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title

**GABLE AND MASONRY
REPAIR DETAILS**

KH Job# 10446.0001 Drawing Number
Date **JUNE 2023**
Designed **DLW**
Drawn **DLW**
Checked **TAG** of 38
A401

Jun 21, 2023 - 9:47:44 am Dwerick H:_0BS\ Pabst Mansion - 10446\ 10446.0001R_Envelope_Restoration\04- DETAIL DRAWINGS.dwg



NOTES:

- ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

- X XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A304-A306)
- X XXX DOOR NUMBER
- DXX DOWNSPOUT NUMBER

REPAIR LEGEND:

- REMOVE EXISTING GRANITE STAIR TREADS AND BORDER. SALVAGE AND REINSTALL OR REPLACE WITH NEW TO MATCH EXISTING AS INDICATED ON DRAWINGS.

For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**



Drawing Title
**SIDE PORCH FLOOR
DETAILS**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38

A402

SCALE: 3/8" = 1'-0"

Jun 21, 2023-9:47:41 am Dweirick H:_DBS\Pabst Mansion-10446\10446.0001R_Envelope Restoration\04-DETAIL DRAWINGS.dwg



NOTES:

- ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

X
XXX
WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)

X
XXX
DOOR NUMBER

DXX
DOWNSPOUT NUMBER

REPAIR LEGEND:

CAREFULLY REMOVE AND SALVAGE TERRA COTTA UNIT. UNIT SHALL BE USED FOR REBUILD AS-IS, OR SHALL BE REPAIRED OR REPLACED AS DESIGNATED BY A/E.

For Local Approvals:

Klein-Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.


LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**


**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**PORTE COCHERE
RESTORATION DETAILS**


KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A403




Jun 21, 2023-9:47:41 am Dweirick H:\DBS\Pabst Mansion-10446\0001R_Envelope Restoration\04-DETAIL DRAWINGS.dwg




1 SOUTH PORCH FLOOR PLAN
SCALE: 3/8" = 1'-0"




4 SOUTH PORCH E-W SECTION
SCALE: 3/8" = 1'-0"




2 SOUTH PORCH FLOOR SECTION
SCALE: 1:8



3 SOUTH PORCH MOSAIC FLOOR DETAIL
SCALE: 1:2



5 SOUTH PORCH REFLECTED CEILING PLAN
SCALE: 3/8" = 1'-0"



6 PORCH CEILING WOODWORK DETAIL
SCALE: 1:4


NOTES:

- ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

- WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- DOOR NUMBER
- DOWNSPOUT NUMBER

REPAIR LEGEND:



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024


Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
**SOUTH PORCH
RESTORATION DETAILS**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A404


Jun 21, 2023-9:47:41 am Dweirick H:_DBS\Pabst Mansion-10446\10446.0001R_Envelope Restoration\04-DETAIL DRAWINGS.dwg




1 SOUTH PORCH WEST ELEVATION
SCALE: #####

2 SOUTH PORCH SOUTH ELEVATION
SCALE: #####

3 SOUTH PORCH EAST ELEVATION
SCALE: #####



4 BALUSTRADE ELEVATION DETAIL
SCALE: ###



- NOTES:
1. PROVIDE SHORING FOR SOUTH PORCH, PORTE COCHERE, AND CONSERVATORY ROOF STRUCTURES AS NECESSARY DURING MASONRY WALL REBUILD.

5 BALUSTRADE SECTION DETAIL
SCALE: ###

NOTES:

1. ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

- Window Number (Refer to Window Schedule on Sheets A504-A506)
- Door Number
- Downspout Number

REPAIR LEGEND:

- Carefully Remove and Salvage Terra Cotta Unit. Unit Shall be Used for Rebuild AS-IS, or Shall be Repaired or Replaced as Designated by A/E.

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

SOUTH PORCH
RESTORATION DETAILS

KH Job# 10446.0001

Date JUNE 2023

Designed DLW

Drawn DLW

Checked TAG



Drawing Number

A405

of 38

0 2 4 6 8
SCALE: 3/8" = 1'-0"

Jun 21, 2023-9:47:41 am D:_JBS\Projects\Restoration-10446\0001R_Envelope_Restoration\04-DETAIL DRAWINGS.dwg



NOTES:

1. ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

- X
XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- X
XXX DOOR NUMBER
- DXX DOWNSPOUT NUMBER

REPAIR LEGEND:

- CAREFULLY REMOVE AND SALVAGE TERRA COTTA UNIT. UNIT SHALL BE USED FOR REBUILD AS-IS, OR SHALL BE REPAIRED OR REPLACED AS DESIGNATED BY A/E.

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

CONSERVATORY
RESTORATION DETAILS

KH Job# 10446.0001

Date JUNE 2023

Designed DLW



Drawn DLW

Checked TAG


Drawing Number

A406

of 38



Jun 21, 2023-9:47:41 am Dwerick H:\0BS\Pabst Mansion-10446\10446.0001R_Envelope Restoration\04-DETAIL DRAWINGS.dwg



1 IRONING PORCH ELEVATION
SCALE: 1" = 1'-0"

NOTES:

1. ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E. AS MAY BE REQUIRED, ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

- X
XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- X
XXX DOOR NUMBER
- DXX DOWNSPOUT NUMBER

REPAIR LEGEND:

- CAREFULLY REMOVE AND SALVAGE TERRA COTTA UNIT. UNIT SHALL BE USED FOR REBUILD AS-IS, OR SHALL BE REPAIRED OR REPLACED AS DESIGNATED BY A/E.

CAREFULLY REMOVE AND REINSTALL EXISTING IRONING PORCH WOOD WINDOW TO ALLOW FOR BALUSTRADE REBUILD.

REMOVE EXISTING WROUGHT IRON RAILING. SANDBLAST TO REMOVE EXISTING PAINT 100%. STRAIGHTEN BENT ELEMENTS. WHERE ORIGINAL ELEMENTS ARE MISSING, PROVIDE NEW CUSTOM ELEMENTS TO MATCH ORIGINAL. APPLY NEW HIGH-PERFORMANCE COATING SYSTEM AND REINSTALL.

REPLACE EXISTING TERRA COTTA DAMAGED BY RAILING EMBEDMENTS. A/E TO DESIGNATE TERRA COTTA FOR REPLACEMENT DURING TERRA COTTA PROCUREMENT PHASE.

CAREFULLY REMOVE AND REINSTALL FULL-DEPTH TERRA COTTA UNITS. REUSE EXISTING TERRA COTTA EXCEPT FOR UNITS DESIGNATED BY A/E TO BE REPLACED. REPAIR EXISTING TERRA COTTA TO BE REUSED AS DESIGNATED BY A/E.

REPLACE EXISTING "OPEN WORK" TERRA COTTA WITH NEW, "SOLID" TERRA COTTA TO MATCH EXISTING DESIGN BUT WITHOUT FULL-DEPTH VOIDS. REBUILD BALUSTRADE WITH STUD WALL BACK-UP.


CAREFULLY DISMANTLE AND REBUILD BRICK AS NECESSARY TO ALLOW FOR RAILING REMOVAL. SALVAGE AND REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE.

RESTORE AND REINSTALL EXISTING DECORATIVE WROUGHT IRON ESCUTCHEON. SECURE WITH STAINLESS STEEL ROUND HEAD MASONRY SCREWS, PAINTED TO MATCH RESTORED RAILING.

CUT OFF EXISTING RAILING EMBEDMENTS PRIOR TO REINSTALLATION OF RAILING. REPAIR OR REPLACE MASONRY AT PREVIOUS EMBEDMENT LOCATION AS DESIGNATED BY A/E. TYPICAL ALL RAILING EMBEDMENTS.

PROVIDE NEW STEEL BRACKET ANCHORED TO MASONRY WITH STAINLESS STEEL MASONRY ANCHORS AND TO RAILING WITH STAINLESS STEEL COUNTERSUNK DRILL AND TAP BOLTS. PRIME AND PAINT ALL SIDES OF BRACKET TO MATCH RESTORED RAILING PRIOR INSTALL. PAINT STAINLESS STEEL ANCHORS TO MATCH BRACKET AND RAILING.

2 BALUSTRADE DETAIL SECTION - EXISTING
SCALE: 3" = 1'-0"



4 RAILINGS ATTACHMENT DETAIL
SCALE: 6" = 1'-0"

REINSTALL EXISTING IRONING PORCH WOOD WINDOW. PROVIDE NEW PERIMETER SEALANT.

PROVIDE NEW STEEL BRACKET ANCHORED TO MASONRY WITH STAINLESS STEEL MASONRY ANCHORS AND TO RAILING WITH STAINLESS STEEL COUNTERSUNK DRILL AND TAP BOLTS. PRIME AND PAINT ALL SIDES OF BRACKET TO MATCH RESTORED RAILING PRIOR INSTALL. PAINT STAINLESS STEEL ANCHORS TO MATCH BRACKET AND RAILING.

REINSTALL RESTORED WROUGHT IRON RAILING. CUT OFF POST EMBEDMENTS AND REPAIR AT PREVIOUS EMBEDMENT LOCATION AS DESIGNATED BY A/E.

PROVIDE BACKER ROD AND SEALANT AT COPING JOINTS. SEALANT TYPE 3.

REINSTALL EXISTING TERRA COTTA. REPAIR AS DESIGNATED BY A/E.

REMOVE EXISTING INTERIOR WOOD PANELING. DOCUMENT DIMENSIONS AND PROFILES FOR ACCURATE REPLICATION.

CONTINUOUS SELF-ADHERED FLASHING MEMBRANE WITH END DAMS. MEMBRANE TO BE COMPATIBLE WITH WRB.

PROVIDE TREATED 2x4 @ 12" O.C. STUD FRAME WALL WITH 3/4" EXTERIOR GRADE PLYWOOD SHEATHING AT INTERIOR AND EXTERIOR.

VAPOR PERMEABLE SELF-ADHERED WEATHER RESISTIVE BARRIER (WRB).

NEW "SOLID" TERRA COTTA TO MATCH EXISTING DESIGN BUT WITHOUT FULL-DEPTH VOIDS.

ANCHOR NEW TERRA COTTA WITH STAINLESS STEEL ANCHORS SECURED TO STUD WALL BACK-UP. MIN. TWO ANCHORS PER UNIT. SEAL PENETRATIONS IN WRB AT FASTENER LOCATIONS.


EXISTING TILE FLOOR TO REMAIN

PROVIDE ROPE WICKS AT HEAD JOINTS.

PROVIDE NEW COPPER DRIP EDGE SET IN SEALANT.

PROVIDE BACKER ROD AND SEALANT AT SECOND BELT COURSE WASH JOINTS. SEALANT TYPE 3.

3 BALUSTRADE DETAIL SECTION - NEW
SCALE: 3" = 1'-0"



PROVIDE NEW INTERIOR WOOD PANELING TO MATCH EXISTING. PRIME AND PAINT.

FIBER GLASS BATT INSULATION

PROVIDE 2x4 @ 12" O.C. STUD FRAME WALL WITH 3/4" EXTERIOR GRADE PLYWOOD SHEATHING AT INTERIOR AND EXTERIOR.


CONTINUOUS SELF-ADHERED VAPOR PERMEABLE WRB WITH END DAMS.

NEW "SOLID" TERRA COTTA TO MATCH EXISTING DESIGN BUT WITHOUT FULL-DEPTH VOIDS.

ANCHOR NEW TERRA COTTA WITH STAINLESS STEEL ANCHORS SECURED TO STUD WALL BACK-UP. MIN. TWO ANCHORS PER UNIT. SEAL PENETRATIONS IN WRB AT FASTENER LOCATIONS.

EXISTING BRICK MASONRY TO REMAIN. REPAIR AS DESIGNATED BY A/E.

5 BALUSTRADE DETAIL PLAN - NEW
SCALE: 3" = 1'-0"



For Local Approvals:

Klein-Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024


Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**


Drawing Title
**IRONING PORCH
RESTORATION DETAILS**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A407


Jun 21, 2023 - 9:47:41 am Dwerick H:\JOBS\Pabst Mansion-10446\10446.0001R_Envelope_Restoration\04-DETAIL DRAWINGS.dwg




1 WEST WING WALL - PLAN
SCALE: 1" = 1'-0"




4 EAST WING WALL - PLAN
SCALE: 1" = 1'-0"




2 WEST WING WALL - WEST ELEV.
SCALE: 1" = 1'-0"



3 WEST WING WALL - SOUTH ELEV.
SCALE: 1" = 1'-0"



5 EAST WING WALL - EAST ELEV
SCALE: 1" = 1'-0"



6 EAST WING WALL - SOUTH ELEV.
SCALE: 1" = 1'-0"

NOTES:


- ALL DIMENSIONS SHOWN ARE BASED ON PRELIMINARY SITE SURVEYS BY A/E. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR AND COORDINATED WITH THE ASSISTANCE OF A/E, AS MAY BE REQUIRED. ANY DIMENSIONAL VARIATIONS THAT REQUIRE A MATERIAL REVISION TO THE DETAILS SHALL BE REPORTED TO THE A/E.

LEGEND:

- X/XXX WINDOW NUMBER (REFER TO WINDOW SCHEDULE ON SHEETS A504-A506)
- X/XXX DOOR NUMBER
- DXX DOWNSPOUT NUMBER

REPAIR LEGEND:

- REPLACE DAMAGED LIMESTONE WITH NEW SIMILAR TO EXISTING.
- REMOVE AND REINSTALL INTACT LIMESTONE.
- CAREFULLY SALVAGE AND REBUILD BRICK. REPLACE DAMAGED BRICK AS DESIGNATED BY A/E.
- CAREFULLY SALVAGE AND REBUILD TERRA COTTA. REPLACE DAMAGED TERRA COTTA AS DESIGNATED BY A/E.



For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024


Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**


Drawing Title
**MISC. MASONRY REPAIR
DETAILS**

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A408


Jun 21, 2023-9:55:19 am Dweirick H:\OBS\Pabst Mansion-10446\10446.0001R_Envelope Restoration\06-MASONRY-ROOF REPAIR DETAILS.dwg



5 TYPICAL DOWNSPOUT
SCALE: 1" = 1'-0"




6 DOWNSPOUT STRAP
SCALE: 3" = 1'-0"




1 TYPICAL BACK OF PARAPET FLASHING
SCALE: 1" = 1'-0"


NOTES:
1. THIS DETAIL SHOWS NEW COPPER FLASHINGS AND REINSTALLED CLAY ROOFING TILE AT THE BACK OF A TYPICAL PARAPET. REMOVE EXISTING CLAY TILE, COPPER BASE FLASHINGS, AND COUNTER FLASHINGS ALONG BACK-SIDE OF PARAPETS TO ALLOW FOR MASONRY FACADE RESTORATION. REPOINT BACK-SIDE OF PARAPETS 100%. REBUILD OUTER WYTHE OF BRICK AT BACK-SIDE OF PARAPETS AS DESIGNATED BY A/E.



4 TYPICAL TILE REMOVAL
SCALE: 1" = 1'-0"



2 TYPICAL RIDGE FLASHING
SCALE: 3" = 1'-0"



3 TYPICAL FLASHING AT PARAPET
SCALE: 3" = 1'-0"

0 1
SCALE: 3" = 1'-0"

0 1 2 3
SCALE: 1" = 1'-0"

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.


LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
ROOF DETAILS


KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A500



NOTES:
1. REMOVE EXISTING ROOF SYSTEM 100% DOWN TO EXISTING TONGUE AND GROOVE WOOD DECK.

1 LOW SLOPE ROOF SYSTEM - EXISTING REMOVAL


SCALE: 6" = 1'-0"



NOTES:
1. NEW ROOF SYSTEM TO BE COVERED BY ROOF MANUFACTURER'S 20 YEAR NDL WARRANTY. CONTRACTOR IS SOLELY RESPONSIBLE FOR ENSURING THAT ALL DETAILS ARE REVIEWED AND APPROVED BY ROOFING MANUFACTURER TO VERIFY COMPLIANCE WITH WARRANTY REQUIREMENTS.


2 LOW SLOPE ROOF SYSTEM - NEW

SCALE: 6" = 1'-0"




3 TYPICAL FLASHING

SCALE: 3" = 1'-0"




5 TYPICAL BALUSTRADE FLASHING

SCALE: 3" = 1'-0"




4 LOW SLOPE TO STEEP SLOPE

SCALE: 3" = 1'-0"




6 TYPICAL ZERO HEIGHT BALUSTRADE FLASHING

SCALE: 3" = 1'-0"



7 SKYLIGHT CURB

SCALE: 3" = 1'-0"



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION


2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

ROOF DETAILS

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38

Jun 21, 2023-9:50:48 am Dweirick H:\DBS\Past Mansion-10446\10446_0001R_Envelope_Restoration\05-WINDOW RESTORATION.dwg




- EXISTING WOOD DOUBLE-HUNG WINDOW SASHES. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING GLASS TYPE VARIES. REFER TO WINDOW SCHEDULE FOR GLASS TYPE AND SCOPE OF RESTORATION.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.

EXISTING COPPER SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.

1 WINDOW TYPE A

SCALE: 3/4" = 1'-0"




- EXISTING WOOD FIXED SASH. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING SHEET METAL SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING TERRA COTTA TRANSOM SILL TO REMAIN.
- EXISTING WOOD SINGLE-HUNG WINDOW SASH SLIDES UP BEHIND TERRA COTTA TRANSOM SILL AND TRANSOM WINDOW.

- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- REFER TO WINDOW SCHEDULE FOR GLASS TYPE AND SCOPE OF RESTORATION.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.
- EXISTING COPPER SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.

2 WINDOW TYPE B

SCALE: 3/4" = 1'-0"



- EXISTING WOOD FIXED SASH. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING WOOD DOUBLE-HUNG WINDOW SASHES. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING GLASS TYPE VARIES. REFER TO WINDOW SCHEDULE FOR GLASS TYPE AND SCOPE OF RESTORATION.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.
- EXISTING COPPER SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.


3 WINDOW TYPE C

SCALE: 3/4" = 1'-0"

- EXISTING WOOD CASEMENT WINDOW SASH. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING LEADED GLASS. REFER TO WINDOW SCHEDULE FOR SCOPE OF RESTORATION.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.
- EXISTING COPPER SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.

4 WINDOW TYPE D

SCALE: 3/4" = 1'-0"




- EXISTING WOOD FIXED SASH. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING SHEET METAL SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING TERRA COTTA TRANSOM SILL TO REMAIN.
- EXISTING WOOD SINGLE-HUNG WINDOW SASH SLIDES UP BEHIND TERRA COTTA TRANSOM SILL AND TRANSOM WINDOW.

- EXISTING WOOD FRAME. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- REFER TO WINDOW SCHEDULE FOR GLASS TYPE AND SCOPE OF RESTORATION.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.
- EXISTING COPPER SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.

5 WINDOW TYPE E


SCALE: 3/4" = 1'-0"



- EXISTING COPPER EYEBROW WINDOW AND FRAME CLADDING TO REMAIN.
- EXISTING WOOD HOPPER WINDOW SASH. RESTORE EXISTING AS INDICATED ON WINDOW SCHEDULE.
- EXISTING WOOD FRAME AND SILL. RESTORE EXISTING AS INDICATED ON WINDOW SCHEDULE.
- REPLACE SEALANT AT COPPER PERIMETER 100%.

6 WINDOW TYPE F


SCALE: 3/4" = 1'-0"



- EXISTING WOOD DOUBLE-HUNG WINDOW SASHES. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING GLASS TYPE VARIES. REFER TO WINDOW SCHEDULE FOR GLASS TYPE AND SCOPE OF RESTORATION.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.

8 WINDOW TYPE H


SCALE: 3/4" = 1'-0"



- REMOVE AND REINSTALL EXISTING WOOD STORM WINDOW TO ALLOW FOR RESTORATION OF WINDOW FRAME. LIGHTLY RESTORE STORM WINDOW TO REPAIR DAMAGE RESULTING FROM THE WORK.
- REMOVE AND REINSTALL EXISTING WOOD BRICKMOLD TO ALLOW FOR RESTORATION OF WINDOW FRAME. LIGHTLY RESTORE BRICKMOLD TO REPAIR DAMAGE RESULTING FROM THE WORK.
- RESTORE EXISTING BENT WOOD WINDOW FRAME. CAREFULLY REMOVE AND SALVAGE EXISTING BENT WOOD BOARDS AND REPAIR MASONRY OPENING AS DESIGNATED BY A/E. RESTORE AND REINSTALL BENT WOOD BOARDS.
- REMOVE AND REINSTALL EXISTING WINDOW SASHES AND MULLION TO ALLOW FOR RESTORATION OF WINDOW FRAME. LIGHTLY RESTORE SASHES AND MULLION TO REPAIR DAMAGE RESULTING FROM THE WORK.
- REPLACE PERIMETER SEALANT 100%. SEALANT TYPE 4.

7 WINDOW TYPE G



SCALE: 3/4" = 1'-0"



- EXISTING WOOD FIXED SASH. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- EXISTING WOOD FIXED SASH. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD FRAME. RESTORE EXISTING AS INDICATED IN WINDOW SCHEDULE.
- EXISTING WOOD BRICKMOLD. RESTORE EXISTING OR PROVIDE NEW AS INDICATED IN WINDOW SCHEDULE OR AS DESIGNATED BY A/E IN THE FIELD.
- REFER TO WINDOW SCHEDULE FOR GLASS TYPE AND SCOPE OF RESTORATION.
- EXISTING COPPER SILL COVER TO REMAIN. REPLACE OR RESECURE AS DESIGNATED BY A/E IN THE FIELD.

9 WINDOW TYPE I

SCALE: 3/4" = 1'-0"




TYPICAL STORM WINDOW SECTION

SCALE: 3" = 1'-0"

- ALIGN DAYLIGHT OPENING OF NEW STORM WINDOWS WITH DAYLIGHT OPENING OF EXISTING WINDOW.
- PROVIDE NEW WOOD STORM WINDOWS AS INDICATED ON WINDOW SCHEDULE.
- AT FIXED STORM WINDOWS, PROVIDE SIX (6) FASTENERS PER WINDOW, FOUR (4) FASTENERS PER TRANSOM WINDOW. FASTENERS INCLUDE THREADED INSERT INSTALLED IN WINDOW FRAME, THREADED INSERT WITH FLANGE INSTALLED IN STORM WINDOW, AND FLATHEAD BOLT.
- AT DOUBLE HUNG WINDOWS, ALIGN HORIZONTAL DIVISION OF STORM WINDOW WITH MEETING RAIL OF WINDOW.
- AT FIXED STORM WINDOWS, PROVIDE SIX (6) FASTENERS PER WINDOW, FOUR (4) FASTENERS PER TRANSOM WINDOW. FASTENERS INCLUDE THREADED INSERT INSTALLED IN WINDOW FRAME, THREADED INSERT WITH FLANGE INSTALLED IN STORM WINDOW, AND FLATHEAD BOLT. REFER TO DETAIL 11/A502.

10 TYPICAL STORM WINDOW ELEVATION

SCALE: 3/4" = 1'-0"



WINDOW RESTORATION GENERAL NOTES:

- CONTRACTOR TO VERIFY ALL DIMENSIONS, PROFILES, CONDITIONS, ETC. IN THE FIELD.
- PROVIDE TEMPORARY WEATHER-TIGHT PANELS OVER ALL WINDOW OPENINGS WHERE SASH HAVE BEEN REMOVED FOR RESTORATION WORK.
- ALL NEW MATERIALS, INCLUDING REPLACEMENT WOOD COMPONENTS, REPLACEMENT OF LEADED GLASS PANELS, ETC., SHALL MATCH EXISTING HISTORIC MATERIALS IN TYPE, STRENGTH, SIZE, AND PROFILE. THIS INCLUDES CREATION OF CUSTOM TEMPLATES FOR MATCHING WOOD MOLDING PROFILES AS NECESSARY.
- EACH WINDOW IS ASSIGNED A SCOPE OF WORK, WHICH MAY BE REPLACEMENT, VARYING LEVELS OF RESTORATION, OR NO WORK. PROVIDE THE SCOPE OF WORK INDICATED IN THE WINDOW SCHEDULE FOR EACH WINDOW.

For Local Approvals:

Klein Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024


Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**


Drawing Title
WINDOW DETAILS

KH Job# 10446.0001 Drawing Number
Date **JUNE 2023**
Designed **DLW**
Drawn **DLW**
Checked **TAG** of 38
A502


Jun 21, 2023-9:50:48 am Dwerick H:\DBS\Past Mansion-10446\10446_0001R_Envelope Restoration\05-WINDOW RESTORATION.dwg




1 WINDOW TYPE A TYPICAL SECTION
SCALE: 3" = 1'-0"




2 WINDOW TYPE B TYPICAL SECTION
SCALE: 3" = 1'-0"



3 WINDOW TYPE C TYPICAL SECTION
SCALE: 3" = 1'-0"



4 WINDOW TYPE D TYPICAL SECTION
SCALE: 3" = 1'-0"




5 WINDOW TYPE F TYPICAL SECTION
SCALE: 3" = 1'-0"

6 WINDOW TYPE G TYPICAL SECTION
SCALE: 3" = 1'-0"

WINDOW RESTORATION GENERAL NOTES:

- CONTRACTOR TO VERIFY ALL DIMENSIONS, PROFILES, CONDITIONS, ETC. IN THE FIELD.
- PROVIDE TEMPORARY WEATHER-TIGHT PANELS OVER ALL WINDOW OPENINGS WHERE SASH HAVE BEEN REMOVED FOR RESTORATION WORK.
- ALL NEW MATERIALS, INCLUDING REPLACEMENT WOOD COMPONENTS, REPLACEMENT OF LEADED GLASS PANELS, ETC., SHALL MATCH EXISTING HISTORIC MATERIALS IN TYPE, STRENGTH, SIZE, AND PROFILE. THIS INCLUDES CREATION OF CUSTOM TEMPLATES FOR MATCHING WOOD MOLDING PROFILES AS NECESSARY.
- EACH WINDOW IS ASSIGNED A SCOPE OF WORK, WHICH MAY BE REPLACEMENT, VARYING LEVELS OF RESTORATION, OR NO WORK. PROVIDE THE SCOPE OF WORK INDICATED IN THE WINDOW SCHEDULE FOR EACH WINDOW.



SCALE: 1/2" = 1'-0"

For Local Approvals:

Klein-Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

WINDOW DETAILS

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A503

WINDOW SCHEDULE:

[illegible]

WINDOW RESTORATION GENERAL NOTES:

1. CONTRACTOR TO VERIFY ALL DIMENSIONS, PROFILES, CONDITIONS, ETC. IN THE FIELD.
2. PROVIDE TEMPORARY WEATHER-TIGHT PANELS OVER ALL WINDOW OPENINGS WHERE SASH HAVE BEEN REMOVED FOR RESTORATION WORK.
3. CONTRACTOR TO NOTIFY A/E IF EXISTING CONDITIONS DIFFER FROM THOSE NOTED ON WINDOW SCHEDULE.
4. EACH WINDOW IS ASSIGNED A SCOPE OF WORK, WHICH MAY BE REPLACEMENT, VARYING LEVELS OF RESTORATION, OR NO WORK. PROVIDE THE SCOPE OF WORK INDICATED IN THE WINDOW SCHEDULE FOR EACH WINDOW.

WINDOW RESTORATION GENERAL NOTES:

LR LIGHT RESTORATION. WINDOW SASHES TO REMAIN IN PLACE. RESTORE FINISH OF WINDOW SASHES AND FRAME AS INDICATED IN THE WINDOW SCHEDULE. REMOVE, RESTORE, AND REINSTALL EXISTING STORM WINDOW.

SR STANDARD RESTORATION. FULL RESTORATION OF EXISTING WINDOW FRAME AND SASHES. INCLUDES REMOVAL OF EXISTING SASHES AND REMOVAL OF GLASS FROM SASHES. ASSUME 20% OF SASHES REQUIRE ISOLATED EPOXY CONSOLIDATION AND PATCHING AND REPLACEMENT OF GLASS. REMOVE EXISTING HARDWARE AND REINSTALL HARDWARE WITH SKIPPING OPERATOR. SCHEDULE. REINSTALL GLASS WITH NEW GLAZING POINTS AND PUTTY. REPAIR AND REFINISH EXISTING WINDOW FRAME AND BRICKMOLD. ASSUME 20% OF FRAMES/BRICKMOLDS REQUIRE ISOLATED EPOXY CONSOLIDATION AND PATCHING. FINISH FRAME AND BRICKMOLD AS INDICATED IN WINDOW SCHEDULE. PROVIDE NEW WEATHER STRIPPING SIMILAR TO EXISTING TO PROVIDE EXISTING HARDWARE. REMOVE EXISTING HARDWARE AND REINSTALL HARDWARE. REMOVE EXISTING STOPS AND HARDWARE TO PROVIDE NEW STOPS WITH OPERATOR. REMOVE EXISTING STORM WINDOWS AND PROVIDE NEW STORM WINDOW, OR REMOVE, RESTORE, AND REINSTALL EXISTING STORM WINDOW AS INDICATED IN WINDOW SCHEDULE.


R REPLACEMENT. REPLACE EXISTING WINDOW WITH NEW WOOD WINDOW TO MATCH ORIGINAL HISTORIC WINDOW. RESTORE EXISTING FRAME TO FACILITATE INSTALLATION AND PROPER OPERATION OF NEW SASHES, OR PROVIDE NEW FRAME AS INDICATED ON WINDOW SCHEDULE

X NO WORK.


WINDOW NOTES:

1. REMOVE AND DISASSEMBLE SASH. PROVIDE NEW BOTTOM RAIL TO MATCH EXISTING. REASSEMBLE SASH WITH DOWELED/GLUED JOINTS TO MATCH EXISTING CONSTRUCTION.
2. REMOVE AND DISASSEMBLE SASH. REASSEMBLE SASH WITH DOWELED/GLUED JOINTS TO MATCH EXISTING CONSTRUCTION.
3. REPLACE BRICKMOLD 100% TO MATCH EXISTING.
4. REMOVE EXISTING SHEET METAL SILL COVER. PROVIDE NEW COPPER SILL COVER SIMILAR TO EXISTING.
5. REMOVE ROTTED WOOD TO REACH SOUND WOOD. PRETREAT WOOD WITH WOOD CONSOLIDANT AS RECOMMENDED BY EPOXY PATCH MANUFACTURER. INSTALL EPOXY PATCH.
6. REPLACE CRACKED GLASS PANE.
7. REPLACE FAILED IGU IN EXISTING STORM WINDOW.
8. PROVIDE NEW SASH CHAIN TO MATCH EXISTING ADJACENT.
9. PROVIDE NEW SASH LOCK TO MATCH EXISTING ADJACENT.
10. PROVIDE NEW SASH LOCK TO MATCH EXISTING ADJACENT.
11. PROVIDE NEW SASH PULL TO MATCH EXISTING ADJACENT.
12. PROVIDE NEW LATCH AND STRIKE TO MATCH EXISTING HISTORIC HARDWARE AT SIMILAR ADJACENT WINDOWS.
13. PROVIDE NEW HINGES TO MATCH EXISTING HISTORIC HARDWARE AT SIMILAR ADJACENT WINDOWS.

WINDOW NUMBER LEGEND:



NUMBERING:



FINISH TYPES:

- P-1 STRIP EXISTING PAINT 100% - PREPARE AND PAINT (INTERIOR). FOR NEW WINDOWS, PREPARE AND PAINT.
- P-2 STRIP EXISTING PAINT 100% - PREPARE AND PAINT (EXTERIOR). FOR NEW WINDOWS, PREPARE AND PAINT.
- P-3 STRIP EXISTING TRANSPARENT FINISH 100% - PREPARE AND PAINT (EXTERIOR).
- P-4 REMOVE UNADHERED EXISTING PAINT (SCRAPE AND SAND) - PREPARE AND PAINT (INTERIOR)
- P-5 REMOVE UNADHERED EXISTING PAINT (SCRAPE AND SAND) - PREPARE AND PAINT (EXTERIOR)
- S-1 STRIP EXISTING TRANSPARENT FINISH AND PREPARE TO RECEIVE NEW STAIN AND TRANSPARENT FINISH - APPLY STAIN AND TRANSPARENT FINISH. FOR NEW WINDOWS, APPLY STAIN AND TRANSPARENT FINISH.
- S-2 SAND EXISTING STAIN/TRANSPARENT FINISHED TO REMOVE UNADHERED FINISH - SPOT APPLY STAIN AS NECESSARY AND APPLY TRANSPARENT COAT 100%.

GLASS TYPES:

- G-1 CLEAR GLASS
G-2 CLEAR LEADED GLASS
G-3 FIGURAL STAINED LEADED GLASS
G-4 ROUNDEL LEADED GLASS

SASH OPERATION:

- DH DOUBLE-HUNG
C CASEMENT
H HOPPER
A AWNING
F FIXED

WINDOW SCHEDULE:

WINDOW NUMBER	SASH NUMBER	WINDOW TYPE (OR SIMILAR)	SASH OPERATION		GLASS TYPE	WINDOW OPENING DIMENSIONS (W X H)	SASH DIMENSIONS (W X H)	WINDOW RESTORATION SCOPE	SASH SCOPE				FRAME SCOPE				STORM WINDOW SCOPE			WINDOW DRAWING DETAIL(S)	NOTE NO. 1: REPLACE BOTTOM SASH RAIL	NOTE NO. 2: REASSEMBLE SASH FRAME	NOTE NO. 3: REPLACE BRICK/MOLD	NOTE NO. 4: REPLACE SHEET METAL SILL COVER	NOTE NO. 5: EPOXY CONSOLIDATION/PATCH	NOTE NO. 6: REPLACE GLASS PANE IN SASH	NOTE NO. 7: REPLACE IGU IN STORM WINDOW	HARDWARE					REMARKS:		
			CURRENT	PROPOSED					RESTORE EXISTING	PROVIDE NEW	INTERIOR FINISH	EXTERIOR FINISH	NO WORK	RESTORE EXISTING	INTERIOR FINISH	EXTERIOR FINISH	NO WORK	REMOVE AND DISPOSE OF EXISTING STORM WINDOW	PROVIDE NEW WOOD STORM WINDOW									RESTORE EXISTING WOOD STORM WINDOW	NOTE NO. 8: NEW SASH CHAINS	NOTE NO. 9: NEW SASH LOCK	NOTE NO. 10: NEW SASH LIFT	NOTE NO. 11: NEW SASH PULL		NOTE NO. 12: NEW LATCH/STRIKE	NOTE NO. 13: NEW HINGES
W201	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
W202	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●		X	P-2		●	●		1/A502													
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
W203	1	A	DH	DH	G-1	3'-0" X 6'-6"	2'-9" X 3'-0"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-0" X 6'-6"	2'-9" X 3'-2"	SR	●		S-2	P-2																							
W204	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2				●	1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
W205	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2				●	1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
W206	1	D	C	C	G-2	2'-4" X 6'-5"	2'-1" X 6'-2"	SR	●		S-2	P-2		●	X	P-2		●	●		4/A502				●								RESTORE LEADED GLASS PANEL		
W207	1	D	C	C	G-2	2'-4" X 6'-5"	2'-1" X 6'-2"	SR	●		S-2	P-2		●	X	P-2		●	●		4/A502				●								RESTORE LEADED GLASS PANEL		
W208	1	D	C	C	G-2	2'-4" X 6'-5"	2'-1" X 6'-2"	SR	●		S-2	P-2		●	X	P-2		●	●		4/A502				●								RESTORE LEADED GLASS PANEL		
W209	1	D	C	C	G-2	2'-4" X 6'-5"	2'-1" X 6'-2"	SR	●		S-2	P-2		●	X	P-2		●	●		4/A502				●								RESTORE LEADED GLASS PANEL		
W210	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
W211	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
S201	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	LR	●		X	P-5			●	X	P-5				●	1/A502													
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	LR	●		X	P-5																							
S202	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	LR	●		X	P-5		●	X	P-5				●	1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	LR	●		X	P-5																							
S203	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	LR	●		X	P-5		●	X	P-5				●	1/A502												EXISTING STORM WINDOW IS HINGED		
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	LR	●		X	P-5																				EXISTING STORM WINDOW IS HINGED			
S204	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	LR	●		X	P-5		●	X	P-5				●	1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	LR	●		X	P-5																							
S205	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	LR	●		X	P-5		●	X	P-5				●	1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	LR	●		X	P-5																							
S206	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	LR	●		X	P-5		●	X	P-5				●	1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	LR	●		X	P-5																							
S207	1	A	DH	DH	G-1	3'-4" X 7'-8"	3'-1" X 3'-9"	SR	●		P-4	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-4" X 7'-8"	3'-1" X 3'-10"	SR	●		P-4	P-2																							
E201	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
E202	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
E203	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
E204	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
E205	1	A	DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	SR	●		S-2	P-2																							
E206	1	A	DH	DH	G-1	3'-0" X 6'-6"	2'-6" X 3'-0"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-0" X 6'-6"	2'-6" X 3'-2"	SR	●		S-2	P-2																							
E207	1	A	DH	DH	G-1	3'-0" X 6'-6"	2'-6" X 3'-0"	SR	●		S-2	P-2		●	X	P-2		●	●		1/A502														
	2		DH	DH	G-1	3'-0" X 6'-6"	2'-6" X 3'-2"	SR	●		S-2	P-2																							
E208	1	A		DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-9"	R		●	S-1	P-2		●	X	P-2			●		1/A502					●	●	●	●				PROVIDE ALL NEW DOUBLE HUNG HARDWARE		
	2			DH	G-1	3'-9" X 7'-8"	3'-6" X 3'-10"	R		●	S-1	P-2														●	●	●	●				PROVIDE ALL NEW DOUBLE HUNG HARDWARE		

WINDOW SCHEDULE:

WINDOW NUMBER	SASH NUMBER	WINDOW TYPE (OR SIMILAR)	SASH OPERATION		GLASS TYPE	WINDOW OPENING DIMENSIONS (W X H)	SASH DIMENSIONS (W X H)	WINDOW RESTORATION SCOPE	SASH SCOPE				FRAME SCOPE				STORM WINDOW SCOPE			WINDOW DRAWING DETAIL(S)	NOTE NO. 1: REPLACE BOTTOM SASH RAIL	NOTE NO. 2: REASSEMBLE SASH FRAME	NOTE NO. 3: REPLACE BRICKMOLD	NOTE NO. 4: REPLACE SHEET METAL SILL COVER	NOTE NO. 5: EPOXY CONSOLIDATION/PATCH	NOTE NO. 6: REPLACE GLASS PANE IN SASH	NOTE NO. 7: REPLACE IGU IN STORM WINDOW	HARDWARE					REMARKS:
			CURRENT	PROPOSED					RESTORE EXISTING	PROVIDE NEW	INTERIOR FINISH	EXTERIOR FINISH	NO WORK	PROVIDE NEW	RESTORE EXISTING	INTERIOR FINISH	EXTERIOR FINISH	NO WORK	REMOVE AND DISPOSE OF EXISTING STORM WINDOW									PROVIDE NEW WOOD STORM WINDOW	RESTORE EXISTING WOOD STORM WINDOW	NOTE NO. 8: NEW SASH CHAINS	NOTE NO. 9: NEW SASH LOCK	NOTE NO. 10: NEW SASH LIFT	
S301	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	LR	●		X	P-5		●	X	P-5		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	LR	●		X	P-5			●					●													
S302	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	LR	●		X	P-5		●	X	P-5		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	LR	●		X	P-5			●					●													
S303	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	LR	●		X	P-5		●	X	P-5		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	LR	●		X	P-5			●					●													
S304	1	B	F	F	G-1	2'-7" X 6'-10"	2'-4" X 1'-7"	LR	●		X	P-5		●	X	P-5		●	2/A502														
	2		SH	SH	G-1		2'-4" X 4'-6"	LR	●		X	P-5			●					●													
S305	1	B	F	F	G-1	2'-7" X 6'-10"	2'-4" X 1'-7"	LR	●		X	P-5		●	X	P-5		●	2/A502														
	2		SH	SH	G-1		2'-4" X 4'-6"	LR	●		X	P-5			●					●													
S306	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	LR	●		X	P-5		●	X	P-5		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	LR	●		X	P-5			●					●													
S307	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	LR	●		X	P-5		●	X	P-5		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	LR	●		X	P-5			●					●													
S308	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	LR	●		X	P-5		●	X	P-5		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	LR	●		X	P-5			●					●													
E301	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	SR	●		S-2	P-2		●	X	P-2		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	SR	●		S-2	P-2			●					●													
E302	1	E	A	A	G-1	2'-8" X 6'-10"	2'-2" X 1'-8"	SR	●		S-2	P-2		●	X	P-2		●	5/A502														
	2		SH	SH	G-1		2'-2" X 4'-1"	SR	●		S-2	P-2			●					●													
E303	1	D	C	C	G-1	3'-4" X 4'-0"	2'-6" X 3'-8"	SR	●		P-4	P-2		●	X	P-2		●	4/A502														
E304	1	B	F	F	G-1	2'-7" X 6'-10"	2'-4" X 1'-7"	SR	●		S-2	P-2		●	X	P-2		●	2/A502				●										
	2		SH	SH	G-1		2'-4" X 4'-6"	SR	●		S-2	P-2			●					●													
E305	1	B		F	G-1	2'-7" X 6'-10"	2'-4" X 1'-7"	R		●	S-1	P-2		●		S-1	P-2		2/A502							●	●	●	●		PROVIDE ALL NEW HARDWARE		
	2			SH	G-1		2'-4" X 4'-6"	R		●	S-1	P-2							●						●	●	●	●		PROVIDE ALL NEW HARDWARE			
ATTIC																																	
N401	1	H	DH	DH	G-1	1'-10" X 4'-8"	1'-4" X 2'-0"	SR	●		S-1	P-2		●	X	P-2		●	8/A502			●	●		●								
	2		DH	DH	G-1		1'-4" X 2'-2"	SR	●		S-1	P-2			●					●				●	●	●	●						
W401	1	F	H	H	G-1	2'-2" X 1'-5"	2'-2" X 1'-5"	SR	●		S-2	P-2		●	X	P-2		●	6/A502		●	●	●	●	●								
W402	1	F	H	H	G-1	2'-2" X 1'-5"	2'-2" X 1'-5"	SR	●		S-2	P-2		●	X	P-2		●	6/A502		●	●	●	●	●								
W403	1	F	H	H	G-1	2'-2" X 1'-5"	2'-2" X 1'-5"	SR	●		S-2	P-2		●	X	P-2		●	6/A502		●	●	●	●	●								
W404	1	F	H	H	G-1	2'-2" X 1'-5"	2'-2" X 1'-5"	SR	●		S-2	P-2		●	X	P-2		●	6/A502		●	●	●	●	●								
E401	1	F	H	H	G-1	2'-2" X 1'-5"	2'-2" X 1'-5"	SR	●		S-2	P-2		●	X	P-2		●	6/A502		●	●	●	●	●								
E402	1	F	H	H	G-1	2'-2" X 1'-5"	2'-2" X 1'-5"	SR	●		S-2	P-2		●	X	P-2		●	6/A502		●	●	●	●	●								

WINDOW RESTORATION GENERAL NOTES:

- CONTRACTOR TO VERIFY ALL DIMENSIONS, PROFILES, CONDITIONS, ETC. IN THE FIELD.
- PROVIDE TEMPORARY WEATHER-TIGHT PANELS OVER ALL WINDOW OPENINGS WHERE SASH HAVE BEEN REMOVED FOR RESTORATION WORK.
- CONTRACTOR TO NOTIFY A/E IF EXISTING CONDITIONS DIFFER FROM THOSE NOTED ON WINDOW SCHEDULE.
- EACH WINDOW IS ASSIGNED A SCOPE OF WORK, WHICH MAY BE REPLACEMENT, VARYING LEVELS OF RESTORATION, OR NO WORK. PROVIDE THE SCOPE OF WORK INDICATED IN THE WINDOW SCHEDULE FOR EACH WINDOW.

WINDOW RESTORATION GENERAL NOTES:


- LR LIGHT RESTORATION. WINDOW SASHES TO REMAIN IN PLACE. RESTORE FINISH OF WINDOW SASHES AND FRAME AS INDICATED IN THE WINDOW SCHEDULE. REMOVE, RESTORE, AND REINSTALL EXISTING STORM WINDOW.
- SR STANDARD RESTORATION. FULL RESTORATION OF EXISTING WINDOW FRAME AND SASHES. INCLUDES REMOVAL OF EXISTING SASHES AND REMOVAL OF GLASS FROM SASHES. ASSUME 20% OF SASHES REQUIRE ISOLATED EPOXY CONSOLIDATION AND PATCHING AND REPLACEMENT OF VENEER AND/OR GLUED UP COMPONENTS. REFINISH SASHES AS INDICATED IN WINDOW SCHEDULE. REINSTALL GLASS WITH NEW GLAZING POINTS AND PUTTY. REPAIR AND REFINISH EXISTING WINDOW FRAME AND BRICKMOLD. ASSUME 20% OF FRAMES/BRICKMOLDS REQUIRE ISOLATED EPOXY CONSOLIDATION AND PATCHING. FINISH FRAME AND BRICKMOLD AS INDICATED IN WINDOW SCHEDULE. PROVIDE NEW WEATHER STRIPPING SIMILAR TO EXISTING 100%. REMOVE EXISTING HARDWARE, REMOVE PAINT, AND REINSTALL HARDWARE. REINSTALL RESTORED SASHES AND ADJUST STOPS AND HARDWARE TO ENSURE SMOOTH OPERATION. REMOVE EXISTING STORM WINDOWS AND PROVIDE NEW STORM WINDOW, OR REMOVE, RESTORE, AND REINSTALL EXISTING STORM WINDOW AS INDICATED IN WINDOW SCHEDULE.
- R REPLACEMENT. REPLACE EXISTING WINDOW WITH NEW WOOD WINDOW TO MATCH ORIGINAL HISTORIC WINDOW. RESTORE EXISTING FRAME TO FACILITATE INSTALLATION AND PROPER OPERATION OF NEW SASHES, OR PROVIDE NEW FRAME AS INDICATED ON WINDOW SCHEDULE.

X NO WORK.


WINDOW NOTES:

- REMOVE AND DISASSEMBLE SASH. PROVIDE NEW BOTTOM RAIL TO MATCH EXISTING. REASSEMBLE SASH WITH DOWELED/GLUED JOINTS TO MATCH EXISTING CONSTRUCTION.
- REMOVE AND DISASSEMBLE SASH, REASSEMBLE SASH WITH DOWELED/GLUED JOINTS TO MATCH EXISTING CONSTRUCTION.
- REPLACE BRICKMOLD 100% TO MATCH EXISTING.
- REMOVE EXISTING SHEET METAL SILL COVER. PROVIDE NEW COPPER SILL COVER SIMILAR TO EXISTING.
- REMOVE ROTTED WOOD TO REACH SOUND WOOD. PRETREAT WOOD WITH WOOD CONSOLIDANT AS RECOMMENDED BY EPOXY PATCH MANUFACTURER. INSTALL EPOXY PATCH.
- REPLACE CRACKED GLASS PANE.
- REPLACE FAILED IGU IN EXISTING STORM WINDOW.
- PROVIDE NEW SASH CHAIN TO MATCH EXISTING ADJACENT.
- PROVIDE NEW SASH LOCK TO MATCH EXISTING ADJACENT.
- PROVIDE NEW SASH LOCK TO MATCH EXISTING ADJACENT.
- PROVIDE NEW SASH PULL TO MATCH EXISTING ADJACENT.
- PROVIDE NEW HINGES TO MATCH EXISTING HISTORIC HARDWARE AT SIMILAR ADJACENT WINDOWS.
- PROVIDE NEW HINGES TO MATCH EXISTING HISTORIC HARDWARE AT SIMILAR ADJACENT WINDOWS.

WINDOW NUMBER LEGEND:



NUMBERING:



FINISH TYPES:

- P-1 STRIP EXISTING PAINT 100% - PREPARE AND PAINT (INTERIOR). FOR NEW WINDOWS, PREPARE AND PAINT.
- P-2 STRIP EXISTING PAINT 100% - PREPARE AND PAINT (EXTERIOR). FOR NEW WINDOWS, PREPARE AND PAINT.
- P-3 STRIP EXISTING TRANSPARENT FINISH 100% - PREPARE AND PAINT (EXTERIOR).
- P-4 REMOVE UNADHERED EXISTING PAINT (SCRAPE AND SAND) - PREPARE AND PAINT (INTERIOR)
- P-5 REMOVE UNADHERED EXISTING PAINT (SCRAPE AND SAND) - PREPARE AND PAINT (EXTERIOR)
- S-1 STRIP EXISTING TRANSPARENT FINISH AND PREPARE TO RECEIVE NEW STAIN AND TRANSPARENT FINISH - APPLY STAIN AND TRANSPARENT FINISH. FOR NEW WINDOWS, APPLY STAIN AND TRANSPARENT FINISH.
- S-2 SAND EXISTING STAIN/TRANSPARENT FINISHED TO REMOVE UNADHERED FINISH - SPOT APPLY STAIN AS NECESSARY AND APPLY TRANSPARENT COAT 100%.

GLASS TYPES:

- G-1 CLEAR GLASS
- G-2 CLEAR LEADED GLASS
- G-3 FIGURAL STAINED LEADED GLASS
- G-4 ROUNDEL LEADED GLASS

SASH OPERATION:

- DH DOUBLE-HUNG
- C CASEMENT
- H HOPPER
- A AWNING
- F FIXED

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

WINDOW SCHEDULE

KH Job# 10446.0001

Drawing Number

Date JUNE 2023

Designed DLW


Drawn DLW

Checked TAG

A506

of 38


Jun 21, 2023--9:55:19 am Dweirick H:_DBS\Pabst Mansion--10446\10446.0001R_Envelope_Restoration\06-MASONRY--ROOF REPAIR DETAILS.dwg




NOTES:

- EXISTING BRICK MASONRY WALLS ARE FLEMISH BOND, WITH ALTERNATING HEADER BRICKS AND STRETCHER BRICKS IN EVERY COURSE.
- OUTER WYTHE REBUILD INCLUDES REMOVAL AND REINSTALLATION OF ALL HEADER BRICKS IN THE AREA DESIGNATED FOR REBUILD.
- MATCH EXISTING BRICK BOND PATTERN AND MORTAR JOINT WIDTH AND PROFILE.
- PERFORM OUTER WYTHE REBUILD IN LIMITED SECTIONS AS NECESSARY SO AS TO NOT CAUSE INSTABILITY OF THE INNER WYTHES. CONTRACTOR IS RESPONSIBLE FOR SEQUENCING OF THE WORK AND SHORING AS NECESSARY TO ENSURE STABILITY OF INNER WYTHES DURING OUTER WYTHE REBUILD.
- SALVAGE AND REUSE EXISTING BRICK TO GREATEST EXTENT POSSIBLE.


1 OUTER WYTHE REBUILD
SCALE: NTS




LIMESTONE REPLACEMENT




7 TYPICAL STONE REPLACEMENT
SCALE: NTS




2 BRICK REPOINTING PREPARATION
SCALE: NTS




4 TYPICAL BELT COURSE
SCALE: 1 1/2" = 1'-0"



8 TYPICAL STONE DUTCHMAN
SCALE: NTS




3 BRICK REPOINTING
SCALE: NTS



NOTES:

- PREPARE SUBSTRATE (CLEAN AND PRIME) PER SEALANT MANUFACTURER'S RECOMMENDATIONS.


5 TYPICAL WASH JOINT - NO LUG
SCALE: 1' = 1'-0"



NOTES:

- PREPARE SUBSTRATE (CLEAN AND PRIME) PER SEALANT MANUFACTURER'S RECOMMENDATIONS.

6 TYPICAL WASH JOINT - WITH LUG
SCALE: 1' = 1'-0"



NOTES:

- DO NOT USE CHISELS.
- REMOVE EXISTING CAULKING (IF PRESENT) PRIOR TO CUTTING NEW JOINT.
- SEE BID FORM FOR ESTIMATED QUANTITIES OF CRACK SEALING.
- THIS DETAIL APPLIES WHERE CRACK SEALING IS DESIGNATED BY THE A/E.
- WHERE EXISTING SILICONE CAULK IS REMOVED, SOME MASONRY MATERIAL WITHIN JOINTS MUST BE GROUND OUT TO REMOVE SILICONE RESIDUE.
- PREPARE SUBSTRATE (CLEAN AND PRIME) PER SEALANT MANUFACTURER'S RECOMMENDATIONS.

9 TYPICAL ROUTE AND SEAL CRACK
SCALE: NTS



For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

MASONRY REPAIR

KH Job# 10446.0001

Date JUNE 2023

Designed DLW

Drawn DLW

Checked TAG


Drawing Number

A600

2

of 38

Jun 21, 2023--9:55:19 am Dweirick H:\JOBS\Pabst Mansion--10446\10446_0001R_Envelope_Restoration\06-MASONRY--ROOF REPAIR DETAILS.dwg




INSTALLATION OF MULTIPLE ADJACENT UNITS


TABLE #1 - ANCHOR REQUIREMENTS				
WIDTH	HEIGHT	NO. ANCHORS OR DOWELS		BOTTOM (SEE NOTE 2)
		TOP	EACH SIDE	
LESS THAN 18"	LESS THAN 15"	1	0	1
18" TO 30"	LESS THAN 15"	2@18 MAX.	0	2@18 MAX.
30" TO 42"	LESS THAN 15"	3@18 MAX.	0	3@18 MAX.
OVER 42"	LESS THAN 15"	@18 MAX. (3 MIN.)	0	3@18
LESS THAN 18"	MORE THAN 15"	1	1	1
18" TO 30"	MORE THAN 15"	2@18 MAX.	1	2@18 MAX.
30" TO 42"	MORE THAN 15"	3@18 MAX.	1	3@18 MAX.
OVER 42"	MORE THAN 15"	@18 MAX. (3 MIN.)	1	3@18

NOTES:





- USE TABLE #1 FOR REMOVAL AND REPLACEMENT OF UNITS.
- ANCHORS IN BOTTOM ARE REQUIRED ONLY AT BED JOINTS BETWEEN ADJACENT REPLACED UNITS.



SINGLE UNIT INSTALLATION



SECTION "A"



NOTES:


- MIN. 2 LATERAL TIES PER TERRA COTTA UNIT.
- VERIFY TYPE AND CONDITION OF BACK-UP MASONRY TO BE ANCHORED INTO.

OPTIONAL ALTERNATIVE
TERRA COTTA ANCHORAGE

2 SCALE: NTS

1 TERRA COTTA ANCHORAGE

SCALE: NTS




NOTE:

APPLY COATING TO PATCH TO MATCH EXISTING GLAZE AS CLOSELY AS POSSIBLE.

3 FLAT PATCH

SCALE: NTS




NOTE:

APPLY COATING TO PATCH TO MATCH EXISTING GLAZE AS CLOSELY AS POSSIBLE.


4 ORNATE PATCH

SCALE: NTS



S.S. PIN REQUIREMENTS:


- FACE SHELL - MINIMUM ANCHORAGE - 2 PINS
1'-2" < L < 2'-0" HIGH OR WIDE - 3 PINS
2'-0" ≤ L < 3'-0" HIGH OR WIDE - 4 PINS
- INTERIOR AND TOP OR WEB WALLS - 1 PIN PER CRACKED WEB




NOTE:

COAT OUTSIDE OF FACE SHELL CRACKS WITH SPECIFIED COATING.

SECTION "B" THROUGH WEB



EXISTING UNIT





NEW UNIT INSTALLATION

NOTE:

INSTALL POINTING MORTAR IN THREE LIFTS AT ALL EXPOSED JOINTS

6 TERRA COTTA POINTING

SCALE: NTS



For Local Approvals:

Klein-Hoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title

MASONRY REPAIR

KH Job# 10446.0001

Drawing Number

Date JUNE 2023

Designed DLW

Drawn DLW

Checked TAG

A601


of 38

Jun 21, 2023--9:55:19 am Dwerick H:\JOBS\Pabst Mansion--10446\10446.0001R_Envelope Restoration\06--MASONRY--ROOF REPAIR DETAILS.dwg



NOTES:
1. TYPE A INCLUDES UNITS APPROXIMATELY 1 C.F. MAX IN VOLUME, 1 OR 2-SIDED, WITH FLAT SURFACES. INCLUDES ASHLARS, QUOINS, ETC.

1 TERRA COTTA UNIT TYPE A
SCALE: NTS




NOTES:
1. TYPE B INCLUDES UNITS APPROXIMATELY 1 C.F. MAX IN VOLUME, 1, 2, OR 3-SIDED, WITH CONSTANT PROFILES, MULTI-SIDED CONSTANT PROFILES, AND CONSTANT PROFILES WITH LUGS.

2 TERRA COTTA UNIT TYPE B
SCALE: NTS




NOTES:
1. TYPE C INCLUDES UNITS APPROXIMATELY 2-3 C.F. MAX IN VOLUME, 1, 2, OR 3-SIDED, WITH CONSTANT PROFILES, MULTI-SIDED CONSTANT PROFILES, AND CONSTANT PROFILES WITH LUGS.

3 TERRA COTTA UNIT TYPE C
SCALE: NTS




NOTES:
1. TYPE D INCLUDES UNITS APPROXIMATELY 2 C.F. MAX IN VOLUME, 1, 2, OR 3-SIDED, WITH A MODERATE AMOUNT OF SURFACE CARVING SUCH AS DENTILS, BEAD AND REEL, EGG AND DART, ORGANIC DECORATION IN RELIEF, ETC.

4 TERRA COTTA UNIT TYPE D
SCALE: NTS



NOTES:
1. TYPE E INCLUDES UNITS APPROXIMATELY 2 C.F. MAX IN VOLUME, 1, 2, OR 3-SIDED, WITH A HIGH AMOUNT OF SURFACE CARVING SUCH AS OPENWORK, CARTOUCHES, COLUMN CAPITALS, CLAM SHELLS, ETC.

5 TERRA COTTA UNIT TYPE E
SCALE: NTS



NOTES:
1. TYPE F INCLUDES UNITS APPROXIMATELY 2-3 C.F. MAX IN VOLUME, 1, 2, OR 3-SIDED, WITH A HIGH AMOUNT OF SURFACE CARVING SUCH AS LIONS HEADS, SPIRALS, AND ORGANIC DECORATION IN RELIEF.

6 TERRA COTTA UNIT TYPE F
SCALE: NTS

For Local Approvals:

KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No: 2926-11

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID
No. Date Description

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE PROVISIONS OF THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.


LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
PABST MANSION
EXTERIOR RESTORATION
2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title
TERRA COTTA TYPES

KH Job# 10446.0001 Drawing Number
Date JUNE 2023
Designed DLW
Drawn DLW
Checked TAG of 38
A602


Apr 05, 2023 - 9:47:46 am ADG-W-10\02300200 KH Pobst Mansion Lighting\E - Design\Drawings\ED001 - DEMO SITE PLAN.dwg



For Local Approvals:

ARCHITECT AND STRUCTURAL ENGINEER:
Klein & Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No: 2926-11

MEP ENGINEER:
adg
700 W. Virginia St. Suite 601
Milwaukee, WI 53204
414-391-2797
avantti design group

	12/19/24	IFC - PHASE I
	6/21/23	ISSUED FOR BID
No.	Date	Description
I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.		

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**


**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
SITE DEMOLITION PLAN


KH_Job# 10446.0001	Drawing Number
Date JUNE 2023	ED001
Designed SJS	
Drawn DLW	
Checked HFB	

of 10

Apr 05, 2023 - 10:10:29 am ADG-W-12_02300200 KH Pobst Mansion Lighting\E - Design\Drawings\E001 - SITE PLAN.dwg



LIGHTING FIXTURE SCHEDULE									
FIXTURE TYPE	DESCRIPTION	FIXTURE DATA					LAMP DATA		REF. NOTES
		MANUFACTURER	CATALOG NO.	MOUNTING	VOLTS	QTY	TYPE		
OA	LED POLE FIXTURE (ACORN)	STERNBERG	PT-D650-SP-VCOB-40-TS-MDL03-A-PEC-5600-BKT	POLE	120	-	LED	1,2,3	
SCHEDULE GENERAL NOTES:									
1. FIXTURE SCHEDULE PROVIDED AS A BASIS OF DESIGN. FIXTURES SELECTED BY CONTRACTOR SHALL BE EQUAL TO OR EXCEED DESIGN PARAMETERS AND SPECIFICATIONS.									
2. COORDINATE MOUNTING OF FIXTURES WITH STRUCTURAL ELEMENTS AND NEW EQUIPMENT SCHEDULED TO BE INSTALLED.									
SCHEDULE REFERENCE NOTES:									
1. PROVIDE WITH 14" POLE STYLE "7700 BIRMINGHAM SERIES BLACK TEXTURED FINISH".									
2. POLE BASE PROVIDED BY STRUCTURAL DESIGNER.									
3. PROVIDE FIXTURE WITH BUTTON PHOTOCELL FOR DUSK TILL DAWN OPERATION.									
4.									



For Local Approvals:

ARCHITECT AND STRUCTURAL ENGINEER:
KleinHoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No. 2926-11

MEP ENGINEER:
adg
700 W. Virginia St. Suite 601
Milwaukee, WI 53204
414-391-2797
avantti design group

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

PABST MANSION
EXTERIOR RESTORATION

2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233

Drawing Title

SITE PLAN

KH_Job# 10446.0001

Date JUNE 2023

Designed SJS

Drawn DLW

Checked HFB

Drawing Number

E001

of 10

ELECTRICAL SPECIFICATIONS:

I. GENERAL

A. INTENT

1. IT IS THE INTENT OF THE CONTRACT DOCUMENTS TO PROVIDE FOR RETROFIT WORK AS INDICATED ON THE DRAWINGS. THE WORK SHALL BE IN ACCORDANCE WITH ALL APPLICABLE CODES, LAWS, ORDINANCES AND REGULATIONS WHICH GOVERN THIS INSTALLATION.

B. APPROVAL OF MATERIALS

1. WHERE THE WORDS "SIMILAR TO," "AS SELECTED," "APPROVED MAKE", OR OTHER NON-SPECIFIC TERMS ARE USED IN REFERENCE TO MATERIALS, QUALITY, METHODS, OR APPORATUS IN LIEU OF OR IN ADDITION TO OTHER SPECIFIC REFERENCES, IT IS TO BE DISTINCTLY UNDERSTOOD THAT THE APPROVAL OF ANY SUCH SUBSTITUTION IS VESTED IN THE OWNER, WHOSE DECISIONS SHALL BE FINAL.

C. REGULATIONS

1. ALL WORK SHALL BE INSTALLED IN STRICT ACCORDANCE WITH ALL APPLICABLE RULES AND REGULATIONS OF LOCAL, STATE AND FEDERAL GOVERNMENTS INCLUDING, BUT NOT LIMITED TO:
 - 1.1. INTERNATIONAL BUILDING CODE, NATIONAL ELECTRICAL CODE, AND NFPA
2. ALL MATERIALS SHALL BEAR THE LABEL OF INSPECTION AND APPROVAL OF THE UNDERWRITER'S LABORATORIES OR OTHER RECOGNIZED TESTING AGENCY, U.S. MAKE AND QUALITY SPECIFIED.
3. ALL MATERIALS SHALL BEAR THE LABEL OF INSPECTION AND APPROVAL OF THE UNDERWRITER'S LABORATORIES OR OTHER RECOGNIZED TESTING AGENCY, U.S. MAKE AND QUALITY SPECIFIED.

D. GUARANTEE

1. GUARANTEE ALL WORK UNDER THE CONTRACTOR AGAINST ANY DEFECT DUE TO FAULTY MATERIALS OR WORKMANSHIP FOR ONE YEAR AFTER COMPLETION, OR LONGER, AS SPECIFIED. CORRECTION OR REPLACEMENT ARE AT CONTRACTOR'S EXPENSE.

E. COORDINATION

1. BEFORE ANY WORK IS INSTALLED AND BEFORE ANY EQUIPMENT IS PURCHASED, CONTRACTOR SHALL CAREFULLY CHECK SPECIFICATIONS AND DRAWINGS FOR EVERY TRADE AND JOB CONDITIONS (INCLUDING REFERENCES TO CONDUIT, WIRE INSTALLED UNDERGROUND, ANY LACK OF COORDINATION BETWEEN HIS WORK AND THE DRAWINGS OR JOB CONDITIONS SHALL BE IMMEDIATELY REPORTED TO THE OWNER IN WRITING. THE OWNER SHALL WORK OUT CONFLICTS AND ADJUSTMENTS IN CONTRACT PRICES. CHANGES IN EQUIPMENT SHALL BE REPORTED TO THE OWNER. IF THE CONTRACTOR FAILS TO CALL SUCH LACK OF COORDINATION BETWEEN SPECIFICATIONS, DRAWINGS, AND JOB CONDITIONS TO THE OWNER'S ATTENTION BEFORE ANY WORK IS DONE OR BEFORE EQUIPMENT IS PURCHASED, IT WILL BE ASSUMED NO CONFLICTS EXIST. IF CONFLICTS ARISE DURING THE CONSTRUCTION PERIOD, THEY SHALL BE IMMEDIATELY REPORTED TO THE OWNER IN WRITING AND THEY WILL BE WORKED OUT BY THE OWNER, BUT NO INCREASE IN CONTRACT PRICE WILL BE ALLOWED. THE OWNER'S DECISIONS SHALL BE FINAL.
2. WHEN ELECTRICAL EQUIPMENT IS OPERATED BY THE ELECTRICAL CONTRACTOR THE ELECTRICAL CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR OPERATION AND SAFETY OF THE EQUIPMENT. WHEN ELECTRICAL EQUIPMENT IS OPERATED BY THE OWNER (OR BY OTHER CONTRACTORS) THE OWNER (OR OTHER CONTRACTORS) SHALL BE SOLELY RESPONSIBLE FOR OPERATION AND SAFETY OF THE EQUIPMENT.
3. THE CONTRACTOR SHALL INSPECT THE JOB SITE TO ENSURE ALL ELECTRICAL DEVICES IN AREAS DESIGNATED TO HAVE ELECTRICAL SUPPLIES TRANSFERRED TO A RELOCATED PANEL ARE INCLUDED IN HIS BID. THE CONTRACTOR MAY REUSE PRESENT WIRING, CONDUIT, JUNCTION BOXES, PANELS ETC. DIFFERENCES IN WIRING BETWEEN THE PRINT AND FIELD SHALL BE PERMISSIBLE BASED ON SITE CONDITIONS PROVIDED ALL WORK IS PERFORMED IN ACCORDANCE WITH THE NEC. THE CONTRACTOR SHALL PROVIDE A TYPED LEGEND AFFIXED TO APPLICABLE LOAD CENTERS/PANELBOARDS INDICATING THE TYPE AND LOCATION OF LOADS SERVED BY EACH CIRCUIT.

II. PRODUCTS

A. RACEWAYS

1. CONDUIT

- A. STEEL RIGID METAL
- B. INTERMEDIATE METAL
- C. RIGID NON METALLIC SCH 40
- D. STEEL LIQUIDTIGHT FLEXIBLE.

2. TUBING

- A. STEEL ELECTRICAL METALLIC.

B. FITTINGS

1. RIGID AND IMC.

- A. ANSI C80.4
- B. LOCKNUTS, STEEL OF MALLEABLE IRON.
- C. BUSHINGS, INSULATING OR INSULATED THROAT TYPE.
- D. COUPLINGS, THREADED OR GLAND COMPRESSION MALLEABLE IRON TYPE. SET SCREW OR INDENTER TYPE NOT ACCEPTABLE.

2. ELECTRICAL METALLIC TUBING

- A. COUPLINGS AND CONNECTORS: STEEL COMPRESSION TYPE. SET SCREW TYPE ALSO ACCEPTABLE.

3. FLEXIBLE.

- A. CONNECTORS, MALLEABLE IRON, THREADLESS SQUEEZE CLAMP TYPE FOR NON-JACKETED CONDUIT.
- B. CONNECTORS, STEEL OR MALLEABLE IRON COMPRESSION TYPE WITH INSULATED THROAT AND "O" RING ASSEMBLY FOR LIQUID-TIGHT CONDUIT.

C. CUTTING, PATCHING AND SEALING

1. CONTRACTOR SHALL DO PATCHING, SEALING AND REBUILDING REQUIRED TO RESTORE CONSTRUCTION TO ITS ORIGINAL CONDITION USING SKILLED CRAFTSMEN AS APPROVED BY THE OWNER. OPENINGS SHALL BE ACCURATELY LOCATED AS SMALL AS POSSIBLE, AND NEATLY AND CLEANLY CUT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CUTTING, PATCHING AND SEALING ALL OPENINGS REQUIRED TO PERFORM HIS WORK SERVED BY EACH CIRCUIT.

D. WIRE AND CABLE

1. BUILDING WIRE, COPPER, 98% CONDUCTIVITY, 600 VOLT INSULATION, THHN/THWN STRANDED. USE THHN IN DRY LOCATIONS ONLY, AND FOR MOTOR CIRCUIT WIRING.
2. BRANCH CIRCUIT WIRING, NO.12 AWG MINIMUM SIZE. WIRING TO BE SIZED AS INDICATED ON THE DRAWINGS OR WHERE NOT INDICATED SIZED TO MEET AMPACITY REQUIREMENTS AS OUTLINED IN THE NEC.
3. WIRING FOR OTHERS SYSTEMS, COMPLY WITH SYSTEM MANUFACTURER'S STANDARDS. NO.14 AWG UNLESS OTHERWISE SPECIFIED.
4. COLOR CODE CONDUCTORS TO DESIGNATE NEUTRAL AND PHASE.
5. WHERE CONDUCTORS OF DIFFERENT SYSTEMS ARE INSTALLED IN SAME RACEWAY, BOX, OR OTHER TYPE ENCLOSURE, COMPLY WITH NEC, USE DIFFERENT COLORS FOR OTHER SYSTEMS. COLOR CODING OF PHASE CONDUCTORS MAY BE ACCOMPLISHED WITH COLORED TAPE APPROVED BY A/E FOR SIZES LARGER THAN NO.8 AWG. IDENTIFY CONTROL WIRE AT EACH END AND IN ALL JUNCTION BOXES WITH DESIGNATED WIRE NUMBER CORRESPONDING TO WIRING DIAGRAMS.

E. BOXES

1. PULL BOXES AND JUNCTION BOXES:

- A. NEC-370 AND UL 50.
- B. FLUSH MOUNTED PULL BOXES, OVERLAPPING COVER WITH FLUSH HEAD SECURITY TYPE RETAINING SCREWS, PRIME-COATED. PROVIDE TWO SCREW REMOVAL/INSERTION TOOLS TO USING OWNER/AGENCY. OVERLAP TWO INCHES ALL SIDES.

H. LIGHTING FIXTURES

1. ALL LIGHTING FIXTURES ARE TO BE PROVIDED COMPLETE WITH ALL NECESSARY ACCESSORIES FOR A PROPER INSTALLATION. CATALOG NUMBERS SHOWN ARE BASIC FIXTURE TYPES. ADDITIONAL FEATURES, ACCESSORIES AND OPTIONS HEREIN SPECIFIED OR SCHEDULED ARE TO BE INCLUDED FOR ALL FIXTURES PROVIDED.
2. PROVIDE REQUIRED LAMPS FOR ALL FIXTURES OF SIZE AND TYPE AS SCHEDULED.
3. MANUFACTURERS:
 - A. LIGHTING FIXTURES, AS SPECIFIED ON THE FIXTURE SCHEDULE. SUBSTITUTIONS TO BE APPROVED BY THE OWNER PRIOR TO BID.

I. OUTLET BOXES.

1. HOT DIPPED GALVANIZED, 1.25 OZ. PER SQ. FT., ANODIZED OR CADMIUM PLATED.
2. INTERIOR BOXES, SHEET STEEL WITH CONDUIT KNOCKOUTS, ATTACHED LUGS FOR LOCATING.

2. RECEPTACLES.

- A. STANDARD DUPLEX, SPECIFICATION GRADE FULL GAUGE SIZE, POLARIZED, PARALLEL BLADE, U-GROUNDING SLAT, SPEC. GRADE, RATED 20 AMP, 125 VOLT, NEMA LINE 5, DESIGNED FOR SPLIT FEED SERVICE. FULL BRASS GROUNDING STRAP.

- (1) ACCEPTABLE MANUFACTURERS:

- (A) COOPER WIRING DEVICES
- (B) HUBBELL
- (C) LEVITON

3. GROUND FAULT CIRCUIT INTERRUPTER:

- A. GENERAL DUTY FEED THRU TYPE CAPABLE OF PROTECTING DOWNSTREAM RECEPTACLES ON SINGLE CIRCUIT, GROUNDING TYPE, UL CLASS A, GROUP 1,20 AMPERE RATING, 125 VOLTS.

B. WALLPLATE COMPATIBLE WITH RECEPTACLE CONFIGURATION.

- C. SEAL ALL CONNECTIONS WITH SEAL COAT COMPOUND AND WRAP TWO LAYERS TAPE.

D. ACCEPTABLE MANUFACTURERS:

- (1) COOPER WIRING DEVICES
- (2) HUBBELL
- (3) LEVITON

4. SURGE SUPPRESSION RECEPTACLES (TVSS).

- A. SPECIFICATION GRADE IVORY FACE WITH LIGHT EQUIPPED WITH MATCHING WALL PLATE ENGRAVED WITH "COMPUTER ONLY" RECEPTACLE TO FIT IN STANDARD WALL BOX.

B. ACCEPTABLE MANUFACTURERS:

- (1) COOPER WIRING DEVICES
- (2) HUBBELL
- (3) LEVITON

K. SCHEDULE

1. CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLATION OF ALL OF HIS WORK IN ACCORDANCE WITH THE SCHEDULE. IF EQUIPMENT DELIVERIES APPEAR TO BE A PROBLEM THE CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY TO DETERMINE IF LIKE EQUIPMENT FROM A DIFFERENT MANUFACTURER MAY BE SUBSTITUTED.

III. INSTALLATION

A. CONDUIT

1. CONDUIT SCHEDULE:

- A. MINIMUM CONDUIT SIZE, (1/2 INCH UNLESS OTHERWISE SPECIFIED, SWITCH, LEGS MAY BE INSTALLED IN 1/2 INCH CONDUIT WHERE IN ACCORDANCE WITH NEC).

- B. MINIMUM FLEXIBLE AND LIQUID TIGHT FLEXIBLE CONDUIT SIZE 1/2 INCH EXCEPT CONNECTIONS TO LIGHTING FIXTURES MAY BE 3/8 INCH IN LENGTHS NOT TO EXCEED 6 FEET

2. INSTALL CONDUIT AS FOLLOWS:

A. USE EMT (THINWALL) CONDUIT FOR:

- (1) BRANCH CIRCUITS IN STUD PARTITIONS AND DROP CEILING AREAS.
- (2) TELEPHONE SYSTEM AND DATA SYSTEMS
- (3) CONCEALED AND EXPOSED LOCATIONS INDOORS

B. USE FLEXIBLE METAL CONDUIT, FOR FINAL CONNECTIONS FOR:

- (1) EQUIPMENT IN DRY LOCATIONS.
- (2) EQUIPMENT IN DRY LOCATIONS ARRANGED FOR FLEXIBLE POSITIONING OR EQUIPPED WITH SLIDING BASES.
- (3) EQUIPMENT IN DRY LOCATIONS WITH VIBRATION ISOLATION MOUNTING.
- (4) NO FLEXIBLE METAL CONDUIT LENGTH RESTRICTION WHEN USING "MANUFACTURED WIRING SYSTEMS".

B. CONDUIT RUNS:

1. SIZE ALL CONDUIT AS INDICATED ON DRAWINGS; WHERE SHOWN, IN ACCORDANCE WITH NATIONAL ELECTRIC CODE. MAKE ALL CONDUIT SYSTEMS MECHANICALLY AND ELECTRICALLY CONTINUOUS FROM SOURCE OF CURRENT TO ALL DEVICES, AND GROUND IN ACCORDANCE WITH NATIONAL ELECTRIC CODE.
2. CONCEAL CONDUIT WHEREVER POSSIBLE, OR EXPOSE AS SHOWN OR NOTED ON THE DRAWINGS AND AS SPECIFIED HEREIN. RUN ALL EXPOSED CONDUIT PARALLEL TO BUILDING WALLS USING RIGHT ANGLE BENDS. EXPOSED DIAGONAL RUNS OF CONDUIT WILL NOT BE PERMITTED.
3. PROVIDE CONDUIT EXPANSION JOINTS AT BUILDING EXPANSION JOINTS FOR CONDUITS RUNS 1-1/2 INCHES AND LARGER. PROVIDE CONDUIT EXPANSION JOINTS OR FLEXIBLE CONDUIT CONNECTION AT BUILDING EXPANSION JOINTS FOR CONDUITS LESS THAN 1-1/2 INCHES.
4. SEAL EACH UNDERGROUND JOINT AND MAKE WATERTIGHT.
5. WHERE BUILDING CONSTRUCTION OR OTHER CONDITIONS MAKE IT IMPOSSIBLE TO USE STANDARD THREADED COUPLINGS, INSTALL WATERTIGHT THREADED UNIONS.
6. WHERE MORE THAN 270 DEGREES TOTAL BENDS ARE NECESSARY IN ANY ONE CONDUIT RUN AND/OR CONDUIT RUNS EXCEED 150 LINEAL FEET, INSTALL A SUITABLE PULL BOX OR JUNCTION BOX.
7. WHERE CONDUITS PASS FROM INTERIOR TO EXTERIOR LOCATIONS PROVIDE A LEAK TIGHT SEAL TO PREVENT LEAKAGE AROUND CONDUIT.
8. CONTRACTOR SHALL DO PATCHING AND REBUILDING REQUIRED TO PATCH OPENINGS AND RESTORE CONSTRUCTION TO ITS ORIGINAL CONDITION UNLESS OTHERWISE INDICATED ON THE DRAWINGS.

C. WIRE AND CABLE

1. ALL WIRING TO BE INSTALLED IN CONDUIT.
2. MAKE CONDUCTORS CONTINUOUS FROM DEVICE TO DEVICE. DO NOT MAKE SPLICES EXCEPT IN OUTLET OR JUNCTION BOXES.
3. DO NOT EXCEED CONDUIT FILL ESTABLISHED BY THE NATIONAL ELECTRICAL CODE FOR NUMBER OF CONDUCTORS INSTALLED IN A RACEWAY.
4. DO NOT PULL ANY CABLE OR WIRE IN A RACEWAY UNTIL THE APPLICABLE PORTION OF THE CONDUIT SYSTEM IS COMPLETE AND INTERNAL RACEWAYS HAS BEEN CLEANED. STRAIN ON CABLES SHALL NOT EXCEED MANUFACTURER'S RECOMMENDATIONS DURING PULLING. USE PULLING LUBRICANT, COMPATIBLE WITH INSULATION AND COVERING, THAT WILL NOT CAUSE DETERIORATION OF INSULATION OR JACKET COVERS OF CABLES OR CONDUCTORS. USE PULLING LUBRICANT RECOMMENDED BY WIRE MANUFACTURER.
5. SUPPORT ALL CONDUCTORS IN VERTICAL RACEWAYS IN ACCORD WITH NATIONAL ELECTRIC CODE.
6. LEAVE AT LEAST SIX INCH (6") LOOPS OR ENDS AT EACH BOX FOR INSTALLATION OF DEVICES. ROLL UP ALL WIRES IN OUTLET BOXES NOT FOR CONNECTION TO DEVICE AT THAT BOX, CONNECT TOGETHER AND TAPE.
7. UPON COMPLETION OF CABLE AND WIRE INSTALLATION, BUT BEFORE TERMINATION TO EQUIPMENT, TEST EACH WIRE FOR GROUNDS AND SHORT CIRCUITS. REPLACE OR CORRECT DEFECTIVE WIRING.

D. BOXES

1. LOCATE ALL BOXES WITH DUE CONSIDERATION TO CLEARANCE FROM VENTILATING DUCTS AND PIPING.
 2. LOCATION OF DEVICE SHOWN ON THE DRAWINGS IS DIAGRAMMATIC ONLY. COORDINATE EXACT LOCATION OF DEVICES EQUIPMENT CONNECTION REQUIREMENTS (AND WORK OF OTHER CONTRACTORS). ARCHITECT MAY ALTER THE LOCATION OF DEVICES SHOWN WITHIN A SIX FEET RADIUS PRIOR TO INSTALLATION.
 3. PROTECT ALL BOXES FROM ENTRY OF FOREIGN MATERIALS.
 4. INDEPENDENTLY SUPPORT ALL BOXES.
 5. PLUG ALL UNUSED OPENINGS. USE THREADED PLUGS FOR CAST BOXES AND SNAP IN METAL PLUGS FOR SHEET METAL BOXES.
 6. PROVIDE PERMANENT BARRIERS IN COMMON BOXES TO LIMIT VOLTAGE BETWEEN ADJACENT SWITCHES TO 300 VOLTS OR LESS.
 7. LOCATION OF DEVICES SHOWN MOUNTED IN CABINTRY SHALL BE VERIFIED WITH THE ARCHITECT PRIOR TO INSTALLATION.
- E. PANELBOARDS
1. EACH PANELBOARD SHALL HAVE A TYPEWRITTEN CIRCUIT SCHEDULE INSTALLED ON THE INSIDE COVER OF EACH PANELBOARD. THIS SCHEDULE SHALL BE COVERED WITH CLEAR PLASTIC AND SHALL INCLUDE THE ITEM SERVED BY EACH BRANCH CIRCUIT.

H. RACEWAY SUPPORT AND HANGERS

1. SECURELY FASTEN RACEWAYS IN PLACE AND SUPPORT FROM CEILING OR WALLS AT SPACINGS NOT EXCEEDING:

MATERIALS	MAX. SPACING OF SUPPORTS
1. 1/2" THROUGH 1" TRADE SIZE CONDUIT	6 FEET
2. 1-1/4" THROUGH 1-1/2" TRADE SIZE CONDUIT	8 FEET
3. 2" TO 4" TRADE SIZE CONDUIT	10 FEET
4. FLEXIBLE METAL CONDUIT	4-1/2' FEET

2. SUPPORT RIGID, IMC OR EMT CONDUITS WITHIN THREE FEET OF EVERY OUTLET BOX, JUNCTION BOX, PULL BOX, CABINET OR TERMINATION. SUPPORT FLEXIBLE CONDUIT WITHIN 12 INCHES OF EVERY OUTLET BOX OR FITTING.

3. SUPPORT VERTICAL RUNS OR CONDUITS AT EACH FLOOR LEVEL AND AT INTERVAL NOT TO EXCEED TEN FEET.

4. SUPPORT CONDUITS BY PIPE STRAPS, WALL BRACKETS, HANGERS, OR CEILING TRAPEZE. THE USE OF PERFORATED IRON OR WIRE FOR SUPPORTING CONDUITS IS PROHIBITED. FASTEN WITH WOOD SCREWS OR SCREW NALLS TO WOOD BY TOGGLE BOLTS ON HOLLOW MASONRY UNITS, BY CONCRETE INSERTS, OR EXPANSION STEEL CONDUITS ON STEEL. DO NOT WELD CONDUITS OR PIPE STRAPS TO STEEL STRUCTURES UNLESS SPECIFICALLY INDICATED.

5. THE LOAD APPLIED TO FASTENERS SHALL NOT EXCEED ONE-THIRD THE PROOF TEST LOAD OF THE FASTENERS OR HANGERS.

6. FOR FASTENERS ATTACHED TO CONCRETE, USE VIBRATION AND SHOCK RESISTANT TYPE.

7. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

8. IN SUSPENDED-CELLING CONSTRUCTION, SPRING STEEL FASTENERS TO CEILING SUPPORTS MAY BE USED FOR THE SUPPORT OF CONDUITS SERVING LIGHTING FIXTURES. NO OTHER CONDUITS MY BE SUPPORTED FROM THE CEILING SUSPENSION SYSTEM.

9. WHERE TWO OR MORE CONDUITS ONE INCH TRADE SIZE OR LARGER RUN PARALLEL, TRAPEZE HANGERS MAY BE USED CONSISTING OF THREADED SOLID RODS, WASHERS, NUTS AND GALVANIZED 7/8" ANGLE OR CHANNEL IRON. INDIVIDUALLY FASTEN CONDUITS TO THE CROSS MEMBER OF EVERY OTHER TRAPEZE HANGER WITH ONE HOLE STRAPS OR CLAMP BACKS WITH PROPER SIZE BOLTS, WASHERS AND NUTS. WHEN ADJUSTABLE TRAPEZE HANGERS ARE USED, USE U- BOLT TYPE CLAMPS AT END OF CONDUIT RUNS, AT EACH ELBOW AND AT EACH THIRD INTERMEDIATED HANGER TO FASTEN EACH CONDUIT.

10. MAKE HANGERS OF DURABLE MATERIALS SUITABLE FOR THE APPLICATION INVOLVED.

11. FABRICATE ALL SCREWS, BOLTS, WASHERS AND MISCELLANEOUS HARDWARE USED FOR CONDUIT SUPPORTS FROM RUST-RESISTING METAL. TRAPEZE HANGERS SHALL HAVE HANGER ASSEMBLIES PROTECTED WITH GALVANIZED FINISH.

For Local Approvals:

ARCHITECT AND STRUCTURAL ENGINEER:

KleinHoffman
Architectural & Structural Engineering

328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No: 2926-11

MEP ENGINEER:

adg

700 W. Virginia St, Suite 601
Milwaukee, WI 53204
414-391-2797

avantti design group

12/19/24 IFC - PHASE I

6/21/23 ISSUED FOR BID

No. Date Description
I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description

**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title

**ELECTRICAL
SPECIFICATIONS**

KH Job# 10446.0001 Drawing Number

Date **JUNE 2023**


Designed **SJS**

Drawn **DLW**

Checked **HLB** of 10

E002

Apr 05, 2023--10:11:01 am ADG--W-10\02300200 KH Pobst Mansion Lighting\E -- Design\Drawings\E100 - BASEMENT PLAN.dwg



For Local Approvals:

ARCHITECT AND STRUCTURAL ENGINEER:
Klein & Hoffman
Architectural & Structural Engineering
328 East Mason Street
Milwaukee, Wisconsin 53202
Phone (414) 261-1345
Wisconsin Architecture/Engineering License No: 2926-11

MEP ENGINEER:
adg
700 W. Virginia St. Suite 601
Milwaukee, WI 53204
414-391-2797
avantti design group

12/19/24 IFC - PHASE I
6/21/23 ISSUED FOR BID

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND TO THE BEST OF MY KNOWLEDGE COMPLY WITH THE STATE OF WISCONSIN COMMERCIAL BUILDING CODE.

LICENSE EXPIRES NOVEMBER 30, 2024

Project Description
**PABST MANSION
EXTERIOR RESTORATION**

**2000 WEST WISCONSIN
AVENUE
MILWAUKEE, WI 53233**

Drawing Title
BASEMENT PLAN

KH Job# 10446.0001 Drawing Number
Date **JUNE 2023**
Designed SJS
Drawn DLW
Checked HFB
E100
of 10