5601 State Rd. 36
Burlington , WI 53105
262-862-1695 / 847-234-4114
prattschimney@gmail.com

BILL TO
Michael Adam
2105 East Layfayet Plc
Milwaukee,Wi
312-806-0208

JOB ADDRESS
2105 East Layfayet Plc
Milwaukee, Wi

WORK ORDER	Appointment
717115	2022-11-22 12:25:00

Deposit	Technician
0.00	Steve Pavlin

DESCRIPTION	PRICE	TAX
UPSTAIRS BEDROOM: Install Valor G4 gas insert (Price includes: unite engine, logs, interior liners, front plate, backing plate, ventilation liners and proper termination cap.)	$ 6,987.00	T
MAINROOM FIREPLACE: Remove clay flue tile as needed. Reline fireplace from the top of the smoke chamber to the top of the chimney with stainless steel liner. Insulate liner with Premier Mix chimney insulation. Parge liner to the smoke chamber, parging smokechamber smooth. Installation of new top tile and seal-tight damper. ***We may need to cut a hole in the side of chimney for proper access.*** Installation of Enervex Chimney Fan. **Electrician will need to be sourced by homeowner to provide electric to the chimney fan.*** Tuckpointing of the firebox as needed is included in the cost below.	$ 12,739.00	T
KITCHEN INSERT OPTION: Installation of a Valor H5 Direct Vent Gas fireplace. (Price includes unit engine, interior panels, collinear cover, liners, faceplate/surround, and logs or rocks) (Custom backing plate and conversion kit will need to be ordered prior to installation)	$ 8,445.00	T
BOOM TRUCK: We will need a boom truck for proper access for the Kitchen and Main Room fireplace relines. ***If done separately this cost will apply per/fireplace.***	$ 3,789.00	T

SUBTOTAL:	$ 31,960.00
DISCOUNT:	($ 0.00)
TAX:	$ 0.00
TOTAL:	$ 31,960.00