

Estimated Cost Of Median Modifications S. Chase Ave; Bucyrus Int'l, Inc.

Description	Proposed Amt
Remove curb & gutter, excavate & grade for road widening, driveway widening & asphalt drop, and furnish & asphalt drop, and furnish & install 4" crushed stone under 8" concrete.	\$6,900
Furnish & maintain barricades.	\$1,850
Final grading, 10" crushed aggregate base and asphalt pave 3" binder course followed by 2" surface course.	\$4,230
Saw Cutting existing asphalt, curb and concrete.	\$1,150
Furnish & install 8" concrete including dowels.	\$11,250
Furnish & install depressed & high side curb & gutter.	\$1,950
Design	\$3,600
Permit	\$200
Tree Removal	\$1,800
Light Pole Move	\$2,500
Total	\$35,430

Source: Graef Anhalt Schloemer