

EXISTING T-MOBILE ANTENNA SLED MOUNT; (TYP. OF 3 PER SECTOR) SEE SHEET A-2A FOR DETAILS
 EXISTING T-MOBILE STEEL PLATFORM W/ EQUIPMENT; SEE SHEET A-1A FOR DETAILS

PROPOSED T-MOBILE CABLE TRAY; SEE SHEET A-4A FOR DETAILS
SECTOR ALPHA

PROPOSED SECTOR ALPHA COVP MOUNTED ON PROPOSED CABLE TRAY USING UNISTRUTS

PROPOSED HYBRID CABLE (FIBER AND DC POWER) ROUTED ALONG EXISTING T-MOBILE CABLE TRAY FROM PROPOSED COVP TO BE MOUNTED ON PROPOSED UNISTRUT H-FRAME ATTACHED TO PROPOSED SSC TO PROPOSED ALPHA SECTOR COVP MOUNTED ON PROPOSED CABLE TRAY W/UNISTRUTS

EXISTING T-MOBILE CABLE TRAY (TYP.)

EXISTING CONCRETE PAVER WALKWAY (TYP.)

PROPOSED HYBRID CABLE (FIBER AND DC POWER) ROUTED ALONG EXISTING T-MOBILE CABLE TRAY FROM PROPOSED COVP TO BE MOUNTED ON PROPOSED UNISTRUT H-FRAME ATTACHED TO PROPOSED SSC TO PROPOSED ALPHA SECTOR COVP MOUNTED ON EXISTING CABLE TRAY W/UNISTRUTS

SECTOR BETA

PROPOSED SECTOR BETA COVP MOUNTED ON EXISTING CABLE TRAY USING UNISTRUTS

EXISTING T-MOBILE ANTENNA SLED MOUNT (TYP. OF 3 PER SECTOR); SEE SHEET A-2A FOR DETAILS

PROPOSED HYBRID CABLE (FIBER AND DC POWER) ROUTED ALONG EXISTING T-MOBILE CABLE TRAY FROM PROPOSED BETA SECTOR COVP TO PROPOSED GAMMA SECTOR COVP MOUNTED ON EXISTING CABLE TRAY W/UNISTRUTS

SECTOR GAMMA

PROPOSED SECTOR GAMMA COVP MOUNTED ON EXISTING CABLE TRAY USING UNISTRUTS


EXISTING T-MOBILE ANTENNA SLED MOUNT; (TYP. OF 3 PER SECTOR) SEE SHEET A-2A FOR DETAILS

EXISTING BUILDING PARAPET WALL, TYP.

PROPOSED HYBRID CABLE LENGTH		
ALPHA SECTOR	1	± 74'
BETA SECTOR	2	± 64'
GAMMA SECTOR	3	± 43'

NOTE:
 1. FOR DETAILED SECTOR EQUIPMENT CONFIGURATION SEE SHEET A-2A

1 ROOF PLAN
 SCALE: 1/8"=1'-0" (1/8"=2'-0" IF 11 X 17 SHEET SIZE)



T-Mobile

T-MOBILE
 8550 WEST BRYN MAWR AVE.
 SUITE 100
 CHICAGO, IL 60631
 MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
 SUITE 1300
 CHICAGO, IL 60631
 MAIN: (216) 593-0400

CONCORDIA, LTD
 A PROFESSIONAL DESIGN FIRM
 LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
 UNIT 101
 CAROL STREAM, IL 60188
 MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice: These Documents/Drawings Are Produced by and Are Therefore The Intellectual Property of Concordia Group Of Companies. Do Not Copy, Reproduce, Reverse-Engineer or Replicate Any Parts of These Documents In any Manner Without Obtaining Written Consent From The Concordia Group.

DRAWN BY: EB CHECKED BY: GMS
 CHECKED BY: RH APPROVED BY: GMS

WISCONSIN PROFESSIONAL ENGINEER


GHAZWAN M. SADAT
 40304
 ARLINGTON HEIGHTS ILLINOIS

Gy Sadat



ML10001A
 ZEIDLER BLDG RT
 841 NORTH BROADWAY
 MILWAUKEE, WI 53201

ROOF PLAN


A-1



1 EXISTING EQUIPMENT LAYOUT
SCALE: 1/2"=1'-0" (1/2"=2'-0" IF 11 X 17 SHEET SIZE)



2 PROPOSED EQUIPMENT LAYOUT
SCALE: 1/2"=1'-0" (1/2"=2'-0" IF 11 X 17 SHEET SIZE)



T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice: These Documents/Drawings Are Produced by and Are Therefore The Intellectual Property of Concordia Group Of Companies. Do Not Copy, Reproduce, Reverse-Engineer or Replicate Any Parts of These Documents In any Manner Without Obtaining Written Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS

WISCONSIN PROFESSIONAL ENGINEER

GHAZWAN M. SADAT
40304

ARLINGTON HEIGHTS ILLINOIS

Gy Sadat

ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

EXISTING & PROPOSED EQUIPMENT LAYOUT

A-1A

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400


SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.
CONCORDIA WIRELESS, INC.
361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS



ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

SITE ELEVATION

A-2

COLLOCATION NOTE:







STRUCTURAL ANALYSIS PERFORMED BY OTHERS. CONTRACTOR TO THOROUGHLY REVIEW THE STRUCTURAL ANALYSIS FOR INFORMATION PERTAINING TO BUILDING UPGRADES, MOUNTING TYPES, ANTENNA HEIGHTS, AND CABLE ROUTING. ANY OTHER DISCREPANCIES BETWEEN THE DRAWINGS AND STRUCTURAL ANALYSIS SHOULD BE BROUGHT TO THE ATTENTION OF THE PROJECT MANAGER PRIOR TO BIDDING AND INSTALLATION.

- NODE B W/ EXISTING MODULES
- PROPOSED SSC W/PROPOSED SYSTEM MODULES AND COVP
- EXISTING T-MOBILE PRIMARY BTS CABINET TO REMAIN
- EXISTING T-MOBILE GPS ANTENNA
- EXISTING HANDRAIL
- EXISTING T-MOBILE STEEL PLATFORM W/EQUIPMENT
- EXISTING MECHANICAL EQUIPMENT
- EXISTING PENTHOUSE
- EXISTING OTHER CARRIER'S ANTENNA MOUNT, TYP.

CL OF T-MOBILE ANTENNAS
ELEV. ± 145'-0" (AGL)

GROUND ELEVATION
ELEV. ± 0'-0" (AGL)

1 SITE ELEVATION
SCALE: N.T.S.



T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS

WISCONSIN

GHAZWAN
M.
SADAT
40304

ARLINGTON HEIGHTS
ILLINOIS

PROFESSIONAL ENGINEER

G. Sadat

ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

EXISTING & PROPOSED
ANTENNA PLANS

A-2A

User: DPATEL32



RFDS Data Configuration Sheet

Date: 8/21/2012

Back to RFDS home

Go Back

Print RFDS

Site Information:

Market:	ML	Radio Vendor:	NSN	Plan Year:	2012
Site Id:	ML10001A	Site Name:	Zeidler Bldg RT	Type/Class:	Building / Roof Top Mount
Address:	841 N Broadway	City:	Milwaukee	State:	WI Zip: 53201
Latitude:	43.04193707	Longitude:	-87.9085521	Created Date:	Apr 18 2012
RF Manager:	Dominador Galicinao	RF Engineer:	Galen Belen	Last Save Date:	Jul 20 2012 10:30AM

Cell Site Configuration

Configuration Type:	Configuration 2B_U2100 on Ground	Final Configuration (Antenna/Line/TMA/RRU):	9/12/3/6	Solution Type:	Rooftop	RFDS Status:	Final
Final Sector Count:							

Sector Information

PCS GSM Design

	A	B	C	D	E	F
Antenna RAD Center:	145	145	145			
Antenna Azimuth:	0	120	240	0	0	0
Mechanical Tilt:	1	1	1	0	0	0
Electrical Tilt:	4	4	4	0	0	0

PCS UMTS Design

	A	B	C	D	E	F
Antenna RAD Center:	145	145	145			
Antenna Azimuth:	0	120	240	0	0	0
Mechanical Tilt:	1	5	4	0	0	0
Electrical Tilt:	5	4	4	0	0	0

AWS UMTS Design

	A	B	C	D	E	F
Antenna RAD Center:	145	145	145			
Antenna Azimuth:	0	120	240	0	0	0
Mechanical Tilt:	1	5	4	0	0	0
Electrical Tilt:	5	4	4	0	0	0

AWS LTE Design

	A	B	C	D	E	F
Antenna RAD Center:	145	145	145			
Antenna Azimuth:	0	120	240	0	0	0
Mechanical Tilt:	1	5	4	0	0	0
Electrical Tilt:	5	4	4	0	0	0

Antenna Configuration (Site Level)

	PCS GSM	PCS UMTS	AWS UMTS	AWS LTE
Antenna ReUse Existing:				
Antenna ReUse Existing Qty:				
Antenna Model:	Andrew - TMBXX-6517-A2M		Andrew - TMBXX-6517-A2M	Andrew - TMBXX-6517-A2M
Antenna Qty:	3	0	3	3
Antenna and (or) Ports Shared:	No	Antenna Shared with AWS UMTS	Antenna Shared with PCS UMTS	No

TMA Configuration (Site Level)

	PCS GSM	PCS UMTS	AWS UMTS	AWS LTE
TMA(Re-use existing TMA/New/Not Needed):			Re-use Existing	
TMA Model:			Andrew Twin AWS - ETW200VS12UB	
TMA Qty:	0	0	3	0

Diplexer/Combiner Configuration

	A	B	C	D	E	F
Diplexer Model (1):						
Diplexer Qty (1):						
Diplexer Model (2):						

Diplexer Qty (2):						
Combinere/Duplexer Model:						
Combinere/Duplexer Qty:						

Antenna Fiber/ Coax Solution (Site Level)

Use HCS (Yes/No)?	Yes
Use NSN Fiber & OVP for Rooftop (Yes/No)?	No
Use Coax Cable (Yes/No)?	Yes

Hybrid Cable Configuration (Site Level)

Hybrid Cable Type:	
Hybrid Cable Length:	
Hybrid Cable Qty:	

Hybrid Cable Config(Sector Level)

	A	B	C	D	E	F
HCS run between Sectors (e.g. Rooftop/Watertank etc.)	Low Capacity HCS-7/8"	Mid Capacity HCS-1 1/4"	Low Capacity HCS-7/8"			
Hybrid Cable Length (ft):	100	75	50	0	0	0

COVP Configuration (Site Level)

COVP Type (1):	Large COVP	COVP Qty (1):	4
COVP Type (2):		COVP Qty (2):	

Coax Configuration

	A	B	C	D	E	F
Re-use existing coax for TDOA (Yes/No)?	Yes	Yes	Yes			
Qty. of excess coax lines to remove?						
New Coax Type:						
New Coax Length/Line:						
New Coax Qty:						
RET Home-Run Cable:						
RET Home-Run Cable Length(ft):						

System Modules (Site Level)

	PCS GSM	PCS UMTS	AWS UMTS	AWS LTE
System Module Type:	ESMB	FSME	FSME	FSMF
System Module Qty:	1	1	1	1
RF Module Type:	FXFB	FXFB	FRIA	FRIG
RF Module Qty:	3	0 (Module Shared with PCS GSM, different PAs)	3	3

Comments/Notes

4/18/2012 - PCS UMTS antenna tilts were matched with AWS UMTS. PCS GSM antenna tilts were kept the same.
 4/20/2012 - Swap existing dual pole antenna with quad pole antenna. Total of 3 quad pole antennas per sector. PCS UMTS antenna tilts were matched with AWS UMTS. PCS GSM antenna tilts were kept the same.
 07/11/12 - Run 1 Low Cap 100ft HCS to Alpha from eqpt. Run 1 Mid Cap 75ft HCS to Beta from eqpt. Run 1 Low Cap 50ft HCS to Gamma from Beta COVP.
 07/20/2012 No update necessary as already Ground Config for AWS (SY)




T-MOBILE
 8550 WEST BRYN MAWR AVE.
 SUITE 100
 CHICAGO, IL 60631
 MAIN: (773) 444-5400



8770 WEST BRYN MAWR AVE.
 SUITE 1300
 CHICAGO, IL 60631
 MAIN: (216) 593-0400

CONCORDIA, LTD
 A PROFESSIONAL DESIGN FIRM
 LICENSE # 3323-011- D.B.A.



361 RANDY ROAD
 UNIT 101
 CAROL STREAM, IL 60188
 MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
 These Documents/Drawings Are Produced by and
 Are Therefore The Intellectual Property of Concordia
 Group Of Companies. Do Not Copy, Reproduce,
 Reverse-Engineer or Replicate Any Parts of These
 Documents in any Manner Without Obtaining Written
 Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS



ML10001A
 ZEIDLER BLDG RT
 841 NORTH BROADWAY
 MILWAUKEE, WI 53201

FINAL RFDS SHEET

A-3

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400


CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB CHECKED BY: GMS
CHECKED BY: RH APPROVED BY: GMS



ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

NSN CONFIGURATION
DIAGRAM & PROPOSED
ANTENNA SCHEDULE

A-3A

PROPOSED ANTENNA AND CABLE SCHEDULE


LOCATION	AZIMUTH	RAD CENTER	TECHNOLOGY	ANTENNA MODEL #	MECHANICAL DOWN TILT	ELECTRICAL DOWN TILT	RRU TYPE	CABLE SIZE	CABLE LENGTH	HCS FACTORY LENGTH	JUMPER LENGTH
ALPHA	A1	0°	145°-0"	LTE-AWS Andrew - TMBXX-6517-A2M	1	5	FRIG	7/8" HYBRID CABLE	74'-0"	75'-0"	9'-0"
	A3	0°	145°-0"	UMTS-AWS/PCS Andrew - TMBXX-6517-A2M	1	5	FRIA(*)/(**) FXXB(**)	7/8" HYBRID CABLE & EXISTING	74'-0" & EXISTING	75'-0" & EXISTING	4'-0"
	A4	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
	A2	0°	145°-0"	GSM-PCS Andrew - TMBXX-6517-A2M	1	4	FXXB(**)	7/8" HYBRID CABLE	74'-0"	75'-0"	4'-0"
BETA	B1	120°	145°-0"	LTE-AWS Andrew - TMBXX-6517-A2M	5	4	FRIG	1 1/4" HYBRID CABLE	64'-0"	75'-0"(**)	6'-0"
	B3	120°	145°-0"	UMTS-AWS/PCS Andrew - TMBXX-6517-A2M	5	4	FRIA(*)/(**) FXXB(**)	1 1/4" HYBRID CABLE & EXISTING	64'-0" & EXISTING	75'-0"(**) & EXISTING	4'-0"
	B4	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
	B2	120°	145°-0"	GSM-PCS Andrew - TMBXX-6517-A2M	1	4	FXXB(**)	1 1/4" HYBRID CABLE	64'-0"	75'-0"(**)	4'-0"
GAMMA	C1	240°	145°-0"	LTE-AWS Andrew - TMBXX-6517-A2M	4	4	FRIG	7/8" HYBRID CABLE	43'-0"(**)	50'-0"	12'-0"
	C3	240°	145°-0"	UMTS-AWS/PCS Andrew - TMBXX-6517-A2M	4	4	FRIA(*)/FXXB(**)	7/8" HYBRID CABLE & EXISTING	43'-0"(**) & EXISTING	50'-0" & EXISTING	4'-0"
	C4	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
	C2	240°	145°-0"	GSM-PCS Andrew - TMBXX-6517-A2M	1	4	FXXB(**)	7/8" HYBRID CABLE	43'-0"(**)	50'-0"	4'-0"

(*) - FRIA INSTALLED INSIDE EXISTING T-MOBILE EQUIPMENTS ROOM AT 6TH FLOOR
(**) - FXXB SHARED BY GSM/PCS AND UMTS/PCS ANTENNAS
(***) - HYBRID CABLE FROM COVP ON SSC CABINET TO BETA SECTOR COVP IS SHARED BY BETA & GAMMA SECTORS
(****) - SECTORS ALPHA AND BETA SHARE THE SAME FRIA


ANTENNA AND COAXIAL CABLE SCHEDULE

- ALL ANTENNAS SHALL BE FURNISHED WITH DOWNTILT BRACKETS. CONTRACTOR SHALL COORDINATE REQUIRED MECHANICAL DOWNTILT FOR EACH ANTENNA WITH RF ENGINEER. ANTENNA DOWNTILT SHALL BE SET AND VERIFIED BY A SMART LEVEL.
- ANTENNA CENTERLINE HEIGHT IS IN REFERENCE TO ELEVATION 0'-0"
- CONTRACTOR SHALL INSTALL COLOR CODE RINGS ON EACH OF THE HYBRID CABLES AND JUMPER CABLES WITH UV RESISTANT TAPE. ALL CABLE SHALL BE MARKED AT TOP AND BOTTOM WITH 2" COLOR TAPE OR STENCIL TAG. COLOR TAPE MAY BE OBTAINED FROM GRAYBAR ELECTRONICS.
- FINAL HYBRID CABLE LENGTH SHALL BE DETERMINED AFTER FIELD SWEEP TEST.
- INSTALL NEW HYBRID THRU THE EXISTING CABLE ENTRY PORTS AND ROUTE ALONG EXISTING T-MOBILE COAXIAL CABLES.
- REMOVE EXISTING T-MOBILE ANTENNA AND RF CABLES AFTER NEW ANTENNA INSTALLATION HAS BEEN TESTED AND APPROVED BY PROJECT MANAGER.


2 PROPOSED ANTENNA AND CABLE SCHEDULE



1 NSN CONFIGURATION DIAGRAM



1 EXISTING ANTENNA DIAGRAM
SCALE: N.T.S.



2 PROPOSED ANTENNA DIAGRAM
SCALE: N.T.S.

LEGEND	
RET CABLING	—————
RF CABLING	—————
FIBER AND POWER JUMPER	- - - - -

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS

WISCONSIN

GHAZWAN
M.
SADAT
40304

ARLINGTON HEIGHTS
ILLINOIS


PROFESSIONAL ENGINEER

Gy Sadat

ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

EXISTING AND PROPOSED
ANTENNA CABLING
DIAGRAMS

A-3B



T-Mobile

T-MOBILE
 8550 WEST BRYN MAWR AVE.
 SUITE 100
 CHICAGO, IL 60631
 MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
 SUITE 1300
 CHICAGO, IL 60631
 MAIN: (216) 593-0400

CONCORDIA, LTD
 A PROFESSIONAL DESIGN FIRM
 LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
 UNIT 101
 CAROL STREAM, IL 60188
 MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
 These Documents/Drawings Are Produced by and
 Are Therefore The Intellectual Property of Concordia
 Group Of Companies. Do Not Copy, Reproduce,
 Reverse-Engineer or Replicate Any Parts of These
 Documents In any Manner Without Obtaining Written
 Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS

WISCONSIN

GHAZWAN
 M.
 SADAT
 40304

ARLINGTON HEIGHTS
 ILLINOIS

PROFESSIONAL ENGINEER


G. Sadat

ML10001A
 ZEIDLER BLDG RT
 841 NORTH BROADWAY
 MILWAUKEE, WI 53201


SYSTEM CONNECTION
 DIAGRAM

A-3C


1 SYSTEM CONNECTION DIAGRAM
 N.T.S.




1 NODE B - EXISTING CONFIGURATION
SCALE: N.T.S.




2 NODE B - PROPOSED CONFIGURATION
SCALE: N.T.S.



3 PROPOSED SYSTEM MODULES & COVP MOUNTING DETAIL
SCALE: N.T.S.



4 TYPICAL CABLE TRAY SECTION DETAIL
SCALE: N.T.S.



5 PROPOSED CABLE TRAY DETAIL
SCALE: N.T.S.

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400


CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011-D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.




DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS



ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

EQUIPMENT MOUNTING
DETAILS

A-4A




COVP (RAYCAP ASU9338TYP01)


SCALE: N.T.S.

Sub-section	Width (mm)	Height (mm)			Depth (mm)		Qty	Volume (L)
		Filter	PA	Total	Filter	PA		
Overall w/o bosses (3-way)	387	324.5	155	479.5	132.9	151.85	1	26

Note:
1. All the dimensions do not include Flange, Screw Boss & Connectors. Stepping fin height was used separately for Volume calculate.





PROPOSED FRIG



PROPOSED RF/SYSTEM MODULES

PROPOSED RF/SYSTEM MODULES

SCALE: N.T.S.



EXISTING TMA (ANDREW ETW200VS12UB)

SCALE: N.T.S.

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.
CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB CHECKED BY: GMS
CHECKED BY: RH APPROVED BY: GMS




Gy Sadat


ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

EQUIPMENT
SPECIFICATIONS


A-4B



SIDE VIEW
SCALE: N.T.S.




ISOMETRIC VIEW
SCALE: N.T.S.




Eye-bolt layout and dimensions

EYE-BOLT LAYOUT AND DIMENSIONS
SCALE: N.T.S.



DETAIL "B" (BOTH SIDE)
SCALE: N.T.S.



FRONT VIEW
SCALE: N.T.S.

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents in any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS




Gy Sadat.


ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

**SITE SUPPORT CABINET
SPECIFICATIONS**

A-4C




1 CABINET PLINTH DETAIL ON EXISTING STEEL PLATFORM
SCALE: N.T.S.



2 CABINET PLINTH DETAIL- TOP VIEW
SCALE: N.T.S.

NOTE:
GC TO V.I.F. INSTALLATION, QUANTITIES & SIZES OF ALL SHOWN MOUNTING HARDWARE; GC TO NOTIFY ENGINEER OF RECORD OF ANY DISCREPANCIES

Parts List			
Item	Part No.	Description	Cnt
1	MT-C6579.01	RECT. TUBE SUPPORT	1
2	MT-C6479.02	2-7/8" OD x 11'-0" (MIN.) MAST	1
3	MT-C6579.03	L2x2x3/16" SANDWICH ANGLE	1
4	MT-C6579.04	L2x2x3/16" BRACE	4
5	MT-C6579.05	L2x2x3/16" BRACE ANGLE	1
6	GB-04125	1/2x1-1/4" GALV. BOLT ASSEMBLY	5
7	MT-6579.06	.375x54" GALV. THREADED ROD	4
8	GN-03	3/8" GALV. NUT	16
9	GW-L03	3/8" GALV. LOCK WASHER	8
10	MT-F1637	1/2x18x48" RUBBER MAT	2
11	GW-F04	1/2" GALV. FLAT WASHER	1
12	GB-04405	1/2x4 GALV. BOLT	1
13	MT-F1037	ANTENNA MOUNT (NOT SHOWN)	2



- NOTES:**
1. SECTIONS MAY VARY IN LENGTH TO ACCOMMODATE LENGTH OF RUN.
 2. NON PENETRATING W/ STRUCTURAL ATTACHMENTS (AMOUNT OF BALLAST PER SECTION DETERMINED BY MFR.).
 3. THIS FRAMING IS REPRODUCED FROM MTS FOR INFORMATION ONLY. CONSULT MTS FOR PROPER INSTALLATION REQUIREMENTS. MTS IS RESPONSIBLE FOR STRUCTURAL INTEGRITY OF THE SYSTEM.

NOTES:
THESE DETAILS WERE REPRODUCED FROM THE DRAWINGS OF THE MANUFACTURER. FOR MORE DETAILS, SEE THE ORIGINAL DRAWINGS.

3 ANTENNA MOUNT ISOMETRIC VIEW
SCALE: N.T.S.

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400

CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB CHECKED BY: GMS
CHECKED BY: RH APPROVED BY: GMS

W I S C O N S I N

GHAZWAN
M.
SADAT
40304

ARLINGTON HEIGHTS
ILLINOIS

PROFESSIONAL ENGINEER

G. Sadat


ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

CABINET PLINTH &
ANTENNA MOUNTING
DETAILS

S-1

GENERAL ELECTRICAL NOTES

- 1.) NATIONAL ELECTRIC CODE, LATEST EDITION.
- 2.) ALL ELECTRICAL MATERIALS, EQUIPMENT AND INSTALLATION PROCEDURES TO CONFORM WITH LOCAL JURISDICTION REQUIREMENTS.
- 3.) CONTRACTOR SHALL PERFORM ALL VERIFICATION TESTS AND EXAMINATION WORK PRIOR TO THE ORDERING OF THE ELECTRICAL EQUIPMENT AND THE ACTUAL CONSTRUCTION. CONTRACTOR SHALL ISSUE A WRITTEN NOTICE OF ALL FINDINGS TO THE ENGINEER LISTING ALL MALFUNCTIONS, FAULTY EQUIPMENT & DISCREPANCIES.
- 4.) ELECTRICAL PLANS, DETAILS, AND DIAGRAMS ARE DIAGRAMMATIC ONLY. FIELD CONDITIONS DICTATE THE AMOUNT AND LOCATION OF EQUIPMENT.
- 5.) ALL MATERIALS SHALL BE MANUFACTURED IN ACCORDANCE WITH APPLICABLE STANDARDS ESTABLISHED BY ANSI, NEMA, NFPA, AND "UL" LISTED.
- 6.) THE ENTIRE ELECTRICAL INSTALLATION SHALL BE GROUNDED AS REQUIRED BY UBC, NEC, T-MOBILE, AND ALL APPLICABLE LOCAL CODES.
- 7.) ALL CIRCUIT BREAKERS, FUSES AND ELECTRICAL EQUIPMENT SHALL HAVE A MINIMUM INTERRUPTING RATING OF 20,000 AIC WHERE APPLICABLE.
- 8.) PATCH, REPAIR AND PAINT ANY AREA THAT HAS BEEN DAMAGED IN THE COURSE OF THE ELECTRICAL WORK.
- 9.) PROVIDE T-MOBILE WITH ONE SET OF COMPLETE ELECTRICAL "AS-BUILT" DRAWINGS AT THE COMPLETION OF THE JOB SHOWING ACTUAL ROUTINGS AND WIRING CONNECTIONS.
- 10.) LABEL ALL ELECTRICAL EQUIPMENT PER T-MOBILE SPECIFICATIONS.
- 11.) ALL SINGLE-PHASE SELF-CONTAINED METER CONNECTION DEVICES MUST INCLUDE HORN TYPE BY-PASS PROVISION SO THAT SERVICE WILL NOT BE INTERRUPTED WHEN A METER IS REMOVED FROM THE SOCKET.
- 12.) ALL ABOVE GROUND CONDUITS AND BUSHING SHALL BE RGS.




1 TYPICAL UTILITY CONDUITS ROUTING DETAIL

VERTICAL UNISTRUT MOUNTING CHART

WALL CONSTRUCTION TYPE	USE
HOLLOW	3/8" Ø TOGGLE BOLT
HOLLOW, AT STUD	3/8" Ø LAG SCREW
CONCRETE BLOCK (HOLLOW)	3/8" Ø HILTI HY-20 WITH SCREEN, MINIMUM EMBEDMENT 2-1/2"
CONCRETE (SOLID)	3/8" Ø HILTI HY-150 WITH SCREEN, MINIMUM EMBEDMENT 2-1/2"

NOTE: USE STANDARD STAINLESS STEEL HARDWARE FOR WALL MOUNT AND CONNECTION OF CHANNELS SPACE UNITS @ 6'-0" ON CENTER

- 1 INNERDUCT
- 2 FIMO OR BUTTERFLY CLAMP AS REQUIRED
- 3 EXISTING WALL ASSEMBLY
- 4 VERTICAL "UNISTRUT" P1000 'T' SERIES LENGTH BASED ON NUMBER OF CONDUIT TO BE MOUNTED




2 WALL MOUNT CABLE SUPPORT
SCALE: N.T.S.

CODES AND STANDARDS

- NEC NATIONAL ELECTRICAL CODE
- ANSI AMERICAN NATIONAL STANDARDS INSTITUTE
- NEMA NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
- NFPA NATIONAL FIRE PROTECTION ASSOCIATION
- UL UNDERWRITERS LABORATORIES, INC.
- IBC INTERNATIONAL BUILDING CODE
- BUILDING OFFICIAL AND CODE ADMINISTRATORS

ABBREVIATIONS

- AIC AMPS INTERRUPTING CAPACITY
- AWG AMERICAN WIRE GAUGE
- BCW BARE COPPER WIRE
- BTS BASE TRANSMISSION SYSTEM
- C CONDUIT
- CAB CABINET
- DISC DISCONNECT SWITCH
- DWG DRAWING
- ELEC ELECTRICAL
- EMT ELECTRICAL METALLIC TUBING
- GEN GENERATOR
- GND GROUND
- GPS GLOBAL POSITIONING SYSTEM
- OH OVERHEAD
- PCS PERSONAL COMMUNICATION SYSTEM
- PPC POWER PROTECTION CABINET
- RGS RIGID GALVANIZED STEEL
- TYP TYPICAL
- UG UNDERGROUND GAS
- UW UNDERGROUND WATER
- SS STORM SEWER



3 ELECTRICAL SITE PLAN
SCALE: 3/8"=1'-0" (3/8"=2'-0" IF 11X17 SHEET SIZE)

LEGEND

- FO FIBER OPTIC CABLE
- E DC DISTRIBUTION CABLE

NOTES:
ALL CONDUIT LENGTHS INCLUDE 15% EXTRA

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400


CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB CHECKED BY: GMS
CHECKED BY: RH APPROVED BY: GMS












Gy Sadat

ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

ELECTRICAL SITE PLAN


E-1

CADWELD CONNECTIONS OR APPROVED EQUAL		BURNDY CONNECTIONS OR APPROVED EQUAL	
 PARALLEL HORIZONTAL CONDUCTORS PARALLEL THROUGH CONNECTION OF HORIZONTAL CABLES TYPE PT	 HORIZONTAL STEEL SURFACE TO FLAT STEEL SURFACE OR HORIZONTAL PIPE TYPE HS	 "C" CONNECTOR HYPRESS TYPE YGHC	
 THROUGH CABLE TO GROUND ROD THROUGH CABLE TO TOP OF GROUND ROD TYPE GT	 VERTICAL STEEL SURFACE CABLE DOWN AT 45° TO VERTICAL STEEL SURFACE INCLUDING PIPE TYPE VS	 BOND JUMPER FIELD FABRICATED GREEN STRANDED INSULATED TYPE 2-YA-2	
 HORIZONTAL SPLICE SPLICE OF HORIZONTAL CABLES	 VERTICAL PIPE CABLE DOWN AT 45° TO RANGE OF VERTICAL PIPES TYPE VS	 COPPER LUGS TWO HOLE - LONG BARREL LENGTH TYPE YA-2	

CADWELD DETAILS







GROUNDING NOTES


- 1.) UNDERGROUND AND OVERHEAD UTILITY LENGTHS TO BE DETERMINED FROM SITE PLAN.
- 2.) SEE ELECTRICAL SPECIFICATIONS SECTION 16000 FOR ALL ELECTRICAL AND GROUNDING INSTALLATION REQUIREMENTS.
- 3.) FOR ORIENTATION OF SITE LAYOUT SEE SITE PLAN, DRAWING.
- 4.) UDA CABINET FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR.
- 5.) GROUND KITS PROVIDED BY OWNER SHALL BE RETROFITTED TO ACCOMMODATE 2 HOLE LUG CONNECTION AND APPROPRIATE LENGTH.
- 6.) CONTRACTOR RESPONSIBLE TO PROVIDE OWNER CERTIFICATION OF RESISTIVITY TESTING.
- 7.) GROUND RODS TO BE INSTALLED AT 10' CENTERS.
- 8.) ALL GROUND LEADS TO BE SLEEVED IN 3/4" Ø SCHEDULE 40 PVC CONDUIT AND SEALED W/ SILICON.
- 9.) GROUND BARS SUPPLIED BY OWNER AND INSTALLED BY CONTRACTOR.
- 10.) ALL BENDS IN GROUNDING SYSTEM MUST BE SMOOTH AND WELL ROUNDED AND MAINTAIN BENDING RADIUS.
- 11.) SEE SITE PLAN FOR COAXIAL ROUTING THIS SHEET IS INTENDED FOR GROUNDING CLARITY ONLY AND IS SCHEMATIC IN DETAIL.
- 12.) GROUND KITS SHALL BE INSTALLED BETWEEN 8"-18" OF ALL CONNECTORS.
- 13.) TOWER FOUNDATION DESIGN BY OWNER, INSTALLED BY CONTRACTOR.
- 14.) ADDITIONAL GROUND KITS TO BE PLACED AT 100' WHEN ANTENNA CENTERLINE IS 200' OR ABOVE.
- 15.) ALL CONDUITS TO BE SEALED W/ SILICONE TO PROVIDE A WATER TIGHT SEAL.



1 PROPOSED GROUNDING DIAGRAM
SCALE: N.T.S.

SYMBOLS LEGEND:

GROUND ROD	
GROUND WIRE (BELOW GRADE)	
GROUND WIRE (ABOVE GRADE) SPARE GROUND WIRE FOR FUTURE CONNECTION (10 FT.)	
GROUND BAR	
EXOTHERMIC WELD CONNECTION	
MECHANICAL CONNECTION	



2 MECHANICAL GROUND CONNECTION
SCALE: N.T.S.

INSTALLATION NOTES:

1. SELECT BOLT LENGTH TO PROVIDE A MINIMUM OF TWO EXPOSED THREADS.
2. BURNISH MOUNTING SURFACE TO REMOVE PAINT IN THE AREA OF LUG CONTACT.
3. APPLY ANTI-OXIDANT COMPOUND TO MATING SURFACE OF LUG AND WIPE CLEAN EXCESS COMPOUND.
4. USE SOLID COPPER WIRE AND MECHANICAL 2-HOLE LUG FOR ALL EXTERIOR GROUNDING.

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400


CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011- D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB CHECKED BY: GMS
CHECKED BY: RH APPROVED BY: GMS



G. Sadat

ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

**PROPOSED SITE
GROUNDING DIAGRAM**

E-2

GENERAL NOTES:

1. OWNER FURNISHED MATERIALS, T-MOBILE "THE COMPANY" WILL PROVIDE AND THE CONTRACTOR WILL INSTALL:

- BTS EQUIPMENT FRAME (PLATFORM) AND ICEBRIDGE SHELTER (GROUND BUILD/CO-LOCATE ONLY)
- AC/TELCO INTERFACE BOX(PPC)
- ICE BRIDGE (CABLE TRAY WITH COVER) (GROUND BUILD/CO-LOCATE ONLY, GC TO FURNISH AND INSTALL FOR ROOFTOP INSTALLATION)
- TOWERS, MONOPOLE
- TOWER LIGHTING
- GENERATORS & LIQUID PROPANE TANK
- ANTENNA STANDARD BRACKETS, FRAMES, AND PIPES FOR MOUNTING.
- ANTENNAS (INSTALLED BY OTHERS)
- TRANSMISSION LINE
- TRANSMISSION LINE JUMPERS
- TRANSMISSION LINE CONNECTORS WITH WEATHERPROOFING KITS
- TRANSMISSION LINE GROUND KITS
- HANGERS
- HOISTING GRIPS
- BTS EQUIPMENT

2. CONTRACTOR TO FURNISH AND INSTALL THE FOLLOWING:

THE CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL OTHER MATERIALS FOR THE COMPLETE INSTALLATION OF THE SITE INCLUDING, BUT NOT LIMITED TO, SUCH MATERIALS AS FENCING, STRUCTURAL STEEL SUPPORTING SUB-FRAME FOR PLATFORM, ROOFING LABOR AND MATERIALS, GROUNDING RINGS, GROUNDING WIRES, COPPER-CLAD OR XIT CHEMICAL GROUND ROD(S), BUSS BARS, TRANSFORMERS AND DISCONNECT SWITCHES WHERE APPLICABLE. TEMPORARY ELECTRICAL POWER, CONDUIT, LANDSCAPING COMPOUND STONE, CRANES, CORE DRILLING, SLEEPERS AND RUBBER MATTING, REBAR, CONCRETE CAISSONS, PADS AND/OR AUGER MOUNTS, MISCELLANEOUS FASTENERS, CABLE TRAYS, NON-STANDARD ANTENNA FRAMES AND ALL OTHER MATERIAL AND LABOR REQUIRED TO COMPLETE THE JOB ACCORDING TO THE DRAWINGS AND SPECIFICATIONS. IT IS THE POSITION OF T-MOBILE TO APPLY FOR PERMITTING AND CONTRACTOR RESPONSIBLE FOR PICKUP AND PAYMENT OF REQUIRED PERMITS.

3. T-MOBILE FURNISHED EQUIPMENT SHALL BE PICKED-UP AT THE T-MOBILE WAREHOUSE, NO LATER THAN 48HR AFTER BEING NOTIFIED INSURED, STORED, UNCRATED, PROTECTED AND INSTALLED BY THE

CONTRACTOR WITH ALL APPURTENANCES REQUIRED TO PLACE THE EQUIPMENT IN OPERATION, READY FOR USE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE EQUIPMENT AFTER PICKING UP.

4. ALL EQUIPMENT FURNISHED AND WORK PERFORMED UNDER THE CONTRACT DOCUMENTS SHALL BE GUARANTEED AGAINST DEFECTS IN MATERIALS OR WORKMANSHIP FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF FINAL ACCEPTANCE, UNLESS NOTED OTHERWISE. ANY FAILURE OF EQUIPMENT OR WORK DUE TO DEFECTS IN MATERIALS OR WORKMANSHIP SHALL BE CORRECTED BY THE CONTRACTOR AT NO COST TO THE OWNER.

5. ALL WORK, MATERIAL, AND EQUIPMENT SHALL COMPLY WITH ALL REQUIREMENTS OF THE LATEST EDITIONS AND INTERIM AMENDMENTS OF THE NATIONAL ELECTRICAL CODE (NEC), NATIONAL ELECTRICAL SAFETY CODE, OSHA, AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL LAWS AND ORDINANCES. ALL ELECTRICAL EQUIPMENT PROVIDED UNDER THIS CONTRACT SHALL BE NEW (EXCEPT WHERE OTHERWISE NOTED) AND SHALL COMPLY WITH THE REQUIREMENTS OF THE UNDERWRITERS' LABORATORIES (U.L.) AND BEAR THE U.L. LABEL.

6. T-MOBILE OR HIS ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT ANY EQUIPMENT OR MATERIALS WHICH, IN HIS OPINION ARE NOT IN COMPLIANCE WITH THE CONTRACT DOCUMENTS, EITHER BEFORE OR AFTER INSTALLATION AND THE EQUIPMENT SHALL BE REPLACED WITH EQUIPMENT CONFORMING TO THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE CONTRACTOR AT NO COST TO THE OWNER OR HIS ARCHITECT/ENGINEER.

7. THE CONTRACTOR SHALL SUPPORT, BRACE AND SECURE EXISTING STRUCTURE AS REQUIRED. CONTRACTOR IS SOLELY RESPONSIBLE FOR THE PROTECTION OF ANY EXISTING STRUCTURES DURING CONSTRUCTION. FIELD VERIFY ALL EXISTING DIMENSIONS WHICH AFFECT THE NEW CONSTRUCTION.

8. THE CONTRACTOR SHALL NOT ALLOW OR CAUSE ANY OF THE WORK TO BE COVERED UP OR ENCLOSED UNTIL IT HAS BEEN INSPECTED BY THE GOVERNING AUTHORITIES. ANY WORK THAT IS ENCLOSED OR COVERED UP BEFORE SUCH INSPECTION AND TEST SHALL BE UNCOVERED AT THE CONTRACTOR'S EXPENSE; AFTER IT HAS BEEN INSPECTED, THE CONTRACTOR SHALL RESTORE THE WORK TO ITS ORIGINAL CONDITION AT HIS OWN EXPENSE.

9. ALL EXISTING UTILITIES, FACILITIES, CONDITIONS, AND THEIR DIMENSIONS SHOWN ON PLANS HAVE BEEN PLOTTED FROM AVAILABLE RECORDS. THE ARCHITECT/ENGINEER AND OWNER (T-MOBILE) ASSUME NO RESPONSIBILITY WHATSOEVER AS TO THE SUFFICIENCY OR ACCURACY OF THE INFORMATION SHOWN ON THE PLANS OR THE MANNER OF THEIR REMOVAL OR ADJUSTMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL SAID UTILITIES AND FACILITIES PRIOR TO START OF CONSTRUCTION. CONTRACTOR SHALL ALSO OBTAIN FROM EACH UTILITY COMPANY DETAILED INFORMATION RELATIVE TO WORKING SCHEDULES AND METHODS OF REMOVING OR ADJUSTING AFFECTED UTILITIES.

GENERAL NOTES (CONTD):

10. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING UTILITIES BOTH HORIZONTALLY AND VERTICALLY PRIOR TO START OF CONSTRUCTION. ANY DISCREPANCIES OR DOUBTS AS TO THE INTERPRETATION OF PLANS SHOULD BE IMMEDIATELY REPORTED TO THE PROJECT MANAGER FOR RESOLUTION AND INSTRUCTION, AND NO FURTHER WORK SHALL BE PERFORMED UNTIL DISCREPANCY IS CHECKED AND CORRECTED BY THE ARCHITECT/ENGINEER. FAILURE TO SECURE SUCH INSTRUCTION MEANS CONTRACTOR WILL HAVE WORKED AT HIS OWN RISK AND EXPENSE.

11. CONTRACTORS SHALL CLEAN ENTIRE SITE AFTER CONSTRUCTION SUCH THAT NO PAPERS, TRASH, DEBRIS, WEEDS, BRUSH, OR ANY OTHER DEPOSITS REMAIN. ALL MATERIALS COLLECTED DURING CLEANING OPERATIONS SHALL BE PROPERLY DISPOSED OF OFF-SITE BY THE CONTRACTOR.

12. ALL SITE WORK SHALL BE CAREFULLY COORDINATED BY THE CONTRACTOR WITH LOCAL GAS, ELECTRIC, TELEPHONE, AND ANY OTHER UTILITY COMPANIES HAVING JURISDICTION OVER THIS LOCATION.

13. DURING CONSTRUCTION, THE CONTRACTOR SHALL AT ALL TIMES MAINTAIN THE UTILITIES OF THE BUILDING/SITE WITHOUT INTERRUPTION. SHOULD IT BE NECESSARY TO INTERRUPT ANY SERVICE OR UTILITY, THE CONTRACTOR SHALL SECURE PERMISSION IN WRITING FROM THE BUILDING/PROPERTY OWNER FOR SUCH INTERRUPTION, AT LEAST 72 HOURS IN ADVANCE. ANY INTERRUPTION SHALL BE MADE WITH A MINIMUM AMOUNT OF INCONVENIENCE TO THE BUILDING/PROPERTY OWNER AND ANY SUCH SHUTDOWN TIME SHALL BE COORDINATED WITH THE BUILDING/PROPERTY OWNER.

14. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION.

15. CONTRACTOR SHALL SUBMIT AT THE END OF THE PROJECT A COMPLETE SET OF AS BUILT DRAWINGS TO T-MOBILE'S PROJECT ENGINEER.

16. GC WILL NOT START THE CONSTRUCTION UNTIL AFTER THEY RECEIVE THE PRE CON PACKAGE AND HAVE A PRE CON WALK WITH THE PROJECT MANAGER.

DIVISION 2 - SITE WORK:

1. THE CONTRACTOR SHALL CALL UTILITIES PRIOR TO THE START OF CONSTRUCTION. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK SHALL BE PROTECTED AT ALL TIMES, AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY THE PROJECT MANAGER. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR PIER DRILLING AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT LIMITED TO:

- FALL PROTECTION
- CONFINED SPACE
- ELECTRICAL SAFETY
- TRENCHING AND EXCAVATION

2. REMOVE FROM SITE/OWNER'S PROPERTY ALL WASTE MATERIALS, UNUSED EXCAVATED MATERIAL INCLUDING MATERIAL CLASSIFIED UNSATISFACTORY, CONTAMINATED OR DANGEROUS TRASH AND DEBRIS, AND DISPOSE OF IN A LEGAL MANNER.

3. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF ENGINEERING.

4. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE BUILDING OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, FERTILIZED, SEEDED, AND COVERED WITH MULCH

5. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, AS REQUIRED DURING CONSTRUCTION.

CONTRACTOR IS RESPONSIBLE FOR LAYOUT AND CONSTRUCTION STAKING. CONTRACTOR SHALL ESTABLISH GRADE AND LINE STAKES PRIOR TO CONSTRUCTION.

CONCORDIA DOES NOT GUARANTEE OR WARRANT THAT THE AFOREMENTIONED EASEMENTS ARE SUFFICIENT FOR CONSTRUCTION TRAFFIC. GC SHALL CONSULT WITH A T-MOBILE REPRESENTATIVE AND LANDLORD WITH EXACT LOGISTICS TO FACILITATE CONTRACTIBILITY OF THE SITE AND DELIVERY OF CRITICAL MATERIALS SUCH AS THE TOWER, STEEL, CONCRETE AND CRANES TO THE PROPOSED LEASE AREA. GC SHALL RESTORE SITE TO ORIGINAL CONDITIONS AND REPLACE ANY AND ALL DISTURBED TREES OR LANDSCAPING.

CONCORDIA IS NOT RESPONSIBLE FOR THE MAINTENANCE AND/OR OPERATIONAL FEASIBILITY.

SCOPE OF WORK FOR THESE PLANS DOES NOT INVOLVE VALUE ENGINEERING AS WELL AS MAINTAINABILITY OPERATIONS OF THE SITE, ACCESS OR UTILITIES.

DIVISION 3 - CONCRETE:

1. MINIMUM ALLOWABLE CONCRETE COMPRESSIVE STRENGTH SHALL BE 4000 PSI AT 28 DAYS WHEN TESTED IN ACCORDANCE WITH THE AMERICAN SOCIETY FOR TESTING AND MATERIALS METHODS STANDARDS ASTM C172, ASTM C31 AND ASTM C39 UNLESS OTHERWISE NOTED.

2. CONCRETE FOR ALL FOUNDATIONS: 540 LBS PER CUBIC YARD OF CONCRETE MINIMUM CEMENT CONTENT FOR 1-INCH MAXIMUM SIZE AGGREGATE, SLUMP RANGE 3 INCHES TO 5 INCHES, TOTAL AIR CONTENT 4 PERCENT TO 7 PERCENT BY VOLUME. AIR ENTRAINING ADMIXTURE REQUIRED TO CONTROL TOTAL AIR CONTENT, WATER REDUCING ADMIXTURE PERMITTED TO OBTAIN SLUMP OVER 3-INCHES.

3. ALL CONCRETE CONSTRUCTION SHALL MEET THE REQUIREMENTS OF THE LATEST EDITION OF THE AMERICAN CONCRETE INSTITUTE (ACI 318) BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE AND (ACI 301) STANDARD SPECIFICATION FOR STRUCTURAL CONCRETE.

4. REBARS SHALL BE ASTM A-615 DEFORMED TYPE WITH MINIMUM YIELD STRENGTH OF 60,000 PSI (40,000 PSI GRADE MAY BE USED FOR TIES & STIRRUPS).

WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-185.

5. DETAILING SHALL BE IN ACCORDANCE WITH MANUAL OF STANDARD PRACTICE OF DETAILING REINFORCED CONCRETE STRUCTURES (ACI STD-315 LATEST EDITION).

6. CHAMFER ALL EXPOSED EDGES OF CONCRETE 3/4" UNLESS OTHERWISE NOTED.

7. REINFORCING STEEL SHALL BE ACCURATELY PLACED AND ADEQUATELY SECURED IN POSITION. LOCATION OF REINFORCEMENT SHALL BE INDICATED ON THE DRAWINGS. THE FOLLOWING MINIMUM COVER (INCHES) FOR REINFORCEMENT SHALL BE PROVIDED, EXCEPT AS NOTED ON DRAWINGS.

MINIMUM COVER (INCHES)
CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH ... 3"
EXPOSED TO EARTH OR WEATHER:
#6 THROUGH #18 ... 2"
#5 BAR AND SMALLER ... 1-1/2"

8. TESTS
CONCRETE MATERIALS AND OPERATIONS SHALL BE TESTED AND INSPECTED BY THE ENGINEER AS THE WORK PROGRESSES. FAILURE TO DETECT ANY DEFECTIVE WORK OR MATERIAL SHALL NOT IN ANY WAY PREVENT LATER REJECTION WHEN SUCH DEFECT IS DISCOVERED NOR SHALL IT OBLIGATE THE ENGINEER FOR FINAL ACCEPTANCE.

- A. FIVE CONCRETE TEST CYLINDERS SHALL BE TAKEN OF THE TOWER PIER FOUNDATION. TWO SHALL BE TESTED @ THREE DAYS, TWO @ TWENTY-EIGHT DAYS, THE FIFTH CYLINDER SHALL BE KEPT SEPARATELY, IF REQUIRED TO BE USED IN THE FUTURE.

- B. ONE ADDITIONAL TEST CYLINDER SHALL BE TAKEN DURING COLD WEATHER AND CURED ON SITE UNDER SAME CONDITIONS AS CONCRETE IT REPRESENTS.

- C. ONE SLUMP TEST SHALL BE TAKEN FOR EACH SET OF TEST CYLINDERS TAKEN.

9. PLACING CONCRETE

- A. THE ENGINEER SHALL BE NOTIFIED NOT LESS THAN 24 HOURS IN ADVANCE OF CONCRETE PLACEMENT, UNLESS INSPECTION IS WAIVED IN EACH CASE, PLACING OF CONCRETE SHALL BE PERFORMED ONLY IN THE PRESENCE OF THE ENGINEER. CONCRETE SHALL NOT BE PLACED UNTIL ALL FORMWORK, EMBEDDED PARTS, STEEL REINFORCEMENT, FOUNDATION SURFACES AND JOINTS INVOLVED IN THE PLACING HAVE BEEN APPROVED, AND UNTIL FACILITIES ACCEPTABLE TO THE T-MOBILE REPRESENTATIVE HAVE BEEN PROVIDED AND MADE READY FOR ACCOMPLISHMENT OF THE WORK AS SPECIFIED. CONCRETE MAY NOT BE ORDERED FOR PLACEMENT UNTIL ALL ITEMS HAVE BEEN APPROVED AND T-MOBILE HAS PERFORMED A FINAL INSPECTION AND GIVEN APPROVAL TO START PLACEMENT IN WRITING.

- B. PLACEMENT OF CONCRETE SHALL BE IN ACCORDANCE WITH ACI 301.

10. PROTECTION

- A. IMMEDIATELY AFTER PLACEMENT, THE CONTRACTOR SHALL PROTECT THE CONCRETE FROM PREMATURE DRYING, EXCESSIVELY HOT OR COLD TEMPERATURES, AND MECHANICAL INJURY. FINISHED WORK SHALL BE PROTECTED.

- B. CONCRETE SHALL BE MAINTAINED WITH MINIMAL MOISTURE LOSS AT RELATIVELY CONSTANT TEMPERATURE FOR A PERIOD NECESSARY FOR HYDRATION OF CEMENT AND HARDENING OF CONCRETE.

- C. ALL CONCRETE SHALL BE WATER CURED BY CONTINUOUS (NOT PERIODIC) FINE MIST SPRAYING OR SPRINKLING ALL EXPOSED SURFACES. WATER SHALL BE CLEAN AND FREE FROM ACID, ALKALI, SALTS, OIL SEDIMENT, AND ORGANIC MATTER. SUCCESSFUL CURING SHALL BE OBTAINED BY USE OF AN AMPLE WATER SUPPLY UNDER PRESSURE IN PIPES, WITH ALL NECESSARY APPLIANCES OF SPRINKLERS, AND SPRAYING DEVICES.

ELECTRICAL NOTES:

1. ELECTRICAL DESIGN SHALL BE PERFORMED BY ELECTRICAL CONTRACTOR. STRUCTURAL DESIGN SHALL BE PERFORMED BY GENERAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL ENSURE THAT ALL WORK COMPLIES WITH ALL APPLICABLE LOCAL AND STATE CODES AND NATIONAL ELECTRICAL CODE.

2. ALL SUGGESTED ELECTRICAL ELEMENTS (SUCH AS BREAKER SIZES, WIRE SIZES, CONDUITS SIZES ARE FOR ZONING PURPOSES ONLY. IT IS THE RESPONSIBILITY TO OF THE ELECTRICAL CONTRACTOR TO CONFIRM COMPLIANCE WITH LOCAL ELECTRICAL CODES AND PASS ALL APPLICABLE AND NECESSARY INSPECTIONS. IN SOME EVENTS, IT MAY BE NECESSARY TO PERFORM AN ELECTRICAL LOAD STUDY TO VERIFY THE CAPACITY OF THE EXISTING SERVICE. THIS IS NOT THE RESPONSIBILITY OF CONCORDIA. IT IS THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.

3. CONTRACTOR SHALL FIELD LOCATE ALL BELOW GRADE GROUND LINES AND UTILITY LINES PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR RELOCATION OF ALL UTILITIES AND GROUND LINES THAT MAY BECOME DISTURBED OR CONFLICTING IN THE COURSE OF CONSTRUCTION.

DIVISION 5 - STRUCTURAL STEEL:

1. DETAIL, FABRICATE AND ERECT STRUCTURAL STEEL IN ACCORDANCE WITH THE LATEST AISC MANUAL OF STEEL CONSTRUCTION (ASD), AWS D1.1, AND THE BASIC BUILDING CODE. STRUCTURAL STEEL SHALL BE AS FOLLOWS:

- ASTM A36, GRADE 36; ROLLED STEEL, RODS, PLATES, U-BOLTS AND ANCHOR BOLTS.
- ASTM A325 BOLTS, BEARING TYPE
- ALL STEEL SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A123.

2. THE CONTRACTOR SHALL PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE REQUIRED DURING CONSTRUCTION UNTIL ALL CONNECTIONS ARE COMPLETE.

3. ANY FIELD CHANGES OR SUBSTITUTIONS SHALL HAVE PRIOR APPROVAL FROM THE ENGINEER, AND T-MOBILE PROJECT MANAGER IN WRITING

4. TIGHTEN HIGH STRENGTH BOLTS TO A SNUG TIGHT CONDITION WHERE ALL PLIES IN A JOINT ARE IN FIRM CONTACT BY EITHER

- A FEW IMPACTS OF A IMPACT WRENCH
- THE FULL EFFORT OF A PERSON USING A SPUD WRENCH.

5. WELDING

- ALL WELDING SHALL BE DONE BY CERTIFIED WELDERS. CERTIFICATION DOCUMENTS SHALL BE MADE AVAILABLE FOR ENGINEER'S AND/OR OWNER'S REVIEW IF REQUESTED.

- WELDING ELECTRODES FOR MANUAL SHIELDED METAL ARC WELDING SHALL CONFORM TO ASTM A-233, E70 SERIES. BARE ELECTRODES AND GRANULAR FLUX USED IN THE SUBMERGED ARC PROCESS SHALL CONFORM TO AISC SPECIFICATIONS.

- FIELD WELDING SHALL BE DONE AS PER AWS D1.1 REQUIREMENTS VISUAL INSPECTION IS ACCEPTABLE.

6. PROTECTION

- UPON COMPLETION OF ERECTION INSPECT ALL GALVANIZED STEEL AND PAINT ANY FIELD CUTS, WELDS, OR GALVANIZED BREAKS WITH ZINC BASED PAINT. COLOR TO MATCH THE GALVANIZING PROCESS.

DIVISION 13 - SPECIAL CONSTRUCTION ANTENNA INSTALLATION

1. WORK INCLUDED:

- ANTENNAS AND COAXIAL CABLES ARE FURNISHED BY T-MOBILE UNDER A SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OF COORDINATION AND SITE ACCESS. ERECTION SUB-CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF PERSONNEL AND PROPERTY.

- INSTALL ANTENNAS AS INDICATED ON DRAWINGS AND T-MOBILE SPECIFICATIONS.

- INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS.

- INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE AND PROVIDE PRINTOUT OF THAT TEST.

- CONTRACTOR SHALL PROVIDE FOUR (4) SETS OF SWEEP TESTS USING ANRITZU-PACKARD 8713B RF SCALAR NETWORK ANALYZER. SUBMIT FREQUENCY DOMAIN REFLECTOMETER(FDR) TESTS RESULTS TO THE PROJECT MANAGER. SWEEP TESTS SHALL BE AS PER ATTACHED RFS "MINIMUM FIELD TESTING RECOMMENDED FOR ANTENNA AND HELIAX COAXIAL CABLE SYSTEMS" DATED 10/5/93. TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING SERVICE AND BE BOUND AND SUBMITTED WITHIN ONE WEEK OF WORK COMPLETION.

- INSTALL COAXIAL CABLES AND TERMINATING BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTORS BETWEEN THE ANTENNA AND EQUIPMENT PER MANUFACTURER'S REQUIREMENTS. TERMINATE ALL COAXIAL CABLE THREE (3) FEET IN EXCESS OF ENTRY PORT LOCATION UNLESS OTHERWISE STATED.

- ANTENNA AND COAXIAL CABLE GROUNDING:

- ALL EXTERIOR #6 GREEN GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE WEATHER SEALED WITH RFS CONNECTOR/SPLICE WEATHERPROOFING KIT #221213 OR EQUAL.

- ALL COAXIAL CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL CABLE (NOT WITHIN BENDS).

CONTRACTOR SHALL FIELD LOCATE ALL BELOW GRADE GROUND LINES AND UTILITY LINES PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR RELOCATION OF ALL UTILITIES AND GROUND LINES THAT MAY BECOME DISTURBED OR CONFLICTING IN THE COURSE OF CONSTRUCTION.

T-Mobile

T-MOBILE
8550 WEST BRYN MAWR AVE.
SUITE 100
CHICAGO, IL 60631
MAIN: (773) 444-5400

SureSite

8770 WEST BRYN MAWR AVE.
SUITE 1300
CHICAGO, IL 60631
MAIN: (216) 593-0400


CONCORDIA, LTD
A PROFESSIONAL DESIGN FIRM
LICENSE # 3323-011-D.B.A.

CONCORDIA WIRELESS, INC.

361 RANDY ROAD
UNIT 101
CAROL STREAM, IL 60188
MAIN: (847) 981-0801

(C) Concordia 2001-2012. Copyright Notice:
These Documents/Drawings Are Produced by and
Are Therefore The Intellectual Property of Concordia
Group Of Companies. Do Not Copy, Reproduce,
Reverse-Engineer or Replicate Any Parts of These
Documents In any Manner Without Obtaining Written
Consent From The Concordia Group.

DRAWN BY: EB	CHECKED BY: GMS
CHECKED BY: RH	APPROVED BY: GMS



ML10001A
ZEIDLER BLDG RT
841 NORTH BROADWAY
MILWAUKEE, WI 53201

GENERAL NOTES
& SPECIFICATIONS

SP-1