

## Summary Scope of Work - 1701 N Lincoln Memorial Blvd

We are preparing to update and replace our current heating and air conditioning system in its entirety. The scope of this project looks to remove current interior water furnaces and ductwork. The new addition included here will slightly impact the exterior presentation of the building. All new additions will be on the western side of the building and opposite of Lincoln Memorial Drive.

The air conditioning will be replaced with conventional outdoor units to be mounted above the current walk-in coolers on the western wall between the building and the main adjacent parking lot. To supply cold air, we plan to install (3) 5ton units with a supplemental 2.5ton minisplit unit for the kitchen space. This minisplit's condenser will also be mounted above the western wall coolers. All four of these units will also require associated linesets through the same wall all covered by linehide.

No exterior modifications or additions are planned for the northern, eastern, or southern facing walls.

The (3) new indoor furnaces will each require two 2in pvc pipes vented through the western face of the roof for exhaust and intake purposes.

No other roof modifications or additions are planned for the northern, eastern, or southern faces.