

CERTIFICATE OF APPROPRIATENESS APPLICATION FORM

Incomplete applications will not be processed for Commission review.

Please print legibly.

	HISTORIC NAME OF PROPERTY OR HISTORIC DISTRICT: (if known) Laura and George Pechkam Miller House				
	DRESS OF PROPERTY: D E. Juneau St., Milwaukee, WI				
NAN	ME AND ADDRESS OF OWNE	R:			
Nam	ne(s): GMC Miller House LLC, MCF	R Miller House			
Addı	ress: 1249 N. Franklin Place, Suite	e 300			
City:	Milwaukee	State: WI	ZIP: 53202		
Ema	il: rossr@wspclement.com, gmcjr4	47@gmail			
Tele	phone number (area code & nu	mber) Daytime: 414-291-8260	Evening:		
Nam	LICANT, AGENT OR CONTRA e(s): Statz Restoration and Engine ess: N57W13580 Reichert Ave		er)		
	N				
,	Menomonee Falls	State: WI	ZIP Code: 53051		
Emai	pete@statzrestoration.com				
Telep	ohone number (area code & nui	mber) Daytime: ²⁶²⁻⁶¹⁷⁻⁶⁸³¹	Evening: 262-617-6831		
ATTA at 41	ACHMENTS: (Because project 4-286-5712 for submittal requir REQUIRED FOR MAJOR P	ements)	please call the HPC Office		
-	Photographs of affected areas & all sides of the building (annotated photos recommended)				
	Sketches and Elevation Dra A digital copy of the photos	wings (1 full size and 1 reduce and drawings is also requeste	ed to 11" x 17" or 8 ½" x 11") d.		
	Sketches and Elevation Draw A digital copy of the photos and Material and Design Specific	wings (1 full size and 1 reduce and drawings is also requeste	ed to 11" x 17" or 8 ½" x 11") d.		
В.	A digital copy of the photos :	wings (1 full size and 1 reduce and drawings is also requeste cations (see next page)	ed to 11" x 17" or 8 ½" x 11") d.		
В.	A digital copy of the photos a Material and Design Specific NEW CONSTRUCTION ALS	wings (1 full size and 1 reduce and drawings is also requeste cations (see next page)	d.		
В.	A digital copy of the photos at Material and Design Specific NEW CONSTRUCTION ALS Floor Plans (1 full size and 1	wings (1 full size and 1 reduce and drawings is also requeste cations (see next page)	" × 17")		

YOUR APPLICATION CANNOT BE PROCESSED UNLESS

BOTH PAGES OF THIS FORM ARE PROPERLY COMPLETED

PLEASE NOTE:

AND SIGNED.

5. **DESCRIPTION OF PROJECT:**

PHONE: (414) 286-5712 or 286-5722

and dimensions. Additional pages may	y be attached via email.	Colgii,
See Attached Document.		
6. SIGNATURE OF APPLICANT:		
SIGNATURE OF APPLICANT:	€2	
Signature	_	
	9/0/00	
Please print or type name	9/7/22	
nis form and all supporting documentation MUST arrive	Date by 4:00 pm (11:50 pm via amail) on the	a alaadiina data
be considered at the next Historic Preservation Comm	ission Meeting. Any information not pro	e deadline date establis
e meeting will not be considered by the Commission do	uring their deliberation. Please call if you	u have any questions ar
aff will assist you.	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	a mare any queenone ar
Mail or Email Form to:		
Historic Preservation Commission City Clerk's Office		
841 N. Broadway, Rm. B1		
Milwaukee, WI 53202		

Tell us what you want to do. Describe all proposed work including materials, design,

hpc@milwaukee.gov

Or click the SUBMIT button to automatically email this form for submission.

www.milwaukee.gov/hpc



April 28, 2022, 2022

The Total Home Company, Inc. 645 N. Milwaukee St. Port Washington, WI 53074

Attn: Corey Didier

Re: Maintenance to Exterior Masonry

1060 E. Juneau St. Milwaukee, WI

Dear Mr. Didier,

Per you request and our site visit, we have developed the following proposal for your review.

SCOPE OF WORK

The exterior stone masonry of the building located at the subject address appears to be in good condition overall. However, there are a few items that should be addressed as part of regular maintenance and/or as part typical aging. The owner would like this work completed.

Accordingly, we have broken this proposal down into two phases. The first phase requires the most pressing repair and that entails rebuilding the two front columns at the base of the south stair. It appears that these two columns have been falling away southward from the wingwalls for some time. This is evident due to some mis-matched mortar and sealant installed into the joints between these columns and the wing walls. It is believed that the foundation for these columns are insufficient and are settling.

To repair this issue, these two columns will be carefully taken apart, set on plywood that is adjacent to these columns and the residual mortar will be cleaned from the stones. The bottom stone on the west column will likely need to be replaced with a similar stone. Because of this, a suitable replacement stone quarry will need to be located prior to the commencement of this work. It is believed that the stone originally used to construct this building came from the Baraboo River area (Abelman quartzite⁴). Because quarries in that area no longer produce stone for architectural features, a similar stone will need to be located. It is believed that a Kasota stone from a quarry in southern Minnesota could be located that would match sufficiently.

With the columns removed, the existing foundation for these columns will be inspected and it is believed they will need to be removed. A new foundation will then be constructed consisting of a 12" thick reinforced concrete footing and a concrete pier that extends upward to slightly above grade that is the size of the original foundation (assumed to be circular and approximately 8" less in diameter than the bottom stone). With the new concrete foundation in place these columns can then be rebuilt.

To rebuild these columns, a historically accurate mortar will be utilized. Based on the age of the building (1887⁴), the mortar used to construct this building originally was a natural hydraulic lime (NHL) mortar. Therefore, an NHL mortar will be tinted to match the original color of this mortar (this color will be found



by removing a piece of mortar from within the column that has not be exposed to atmospheric staining / fading. These columns will be reconstructed to match their original configuration.

The second phase of this project will be to complete basic maintenance to the stone masonry. To begin with, there is a block of mortar that, it appears, someone in recent times placed below the south east column of the front porch. This will be removed and the "cream city" brick behind will be inspected and repaired as necessary. It was assumed that there would need to be approximately 5 brick replacements completed and that they could be replaced without the need to remove any stone.


There is a basement window sill on the west elevation that is badly cracked. This will be completely replaced with the type of stone that was found to be a match for the front porch columns. Further, there are three (3) stones at the base of the building on the west elevation that are delaminating. As these stones are likely the full thickness of the wall, a dutchman type repair will be completed (confirmation of stone depth prior to ordering of new stone elements).

The existing failed stones will be chipped back approximately 4" from the predominate plane of the building and stainless steel pins will be epoxied into the parent stone at 12" on center or a minimum of two pins. Corresponding holes will be drilled into the dutchman stone. These holes will then be cleaned of dust by brushing and blowing out the dust and a gel epoxy placed into the holes. The stone will then be set in place in a full bed of mortar with the stainless steel pins firmly set into the wet epoxy in the corresponding holes of the new stone.


There is also one stone from a second floor window on the east elevation that has broken off. This stone will be reset into place. Specifically, stainless steel pins will be installed, as described earlier, to hold the fractured stone to the parent stone. The surrounding mortar joints will then be tuckpointed and struck to match the surrounding joints, as best possible.

In the preparation of this proposal, we have made the following assumptions.:

- 1.) We have included approximately 3 hours for preconstruction meetings and appointments due to the historic nature of this building.
 - a. Samples of proposed materials to be available for this / these meeting(s). Therefore there will be some cost incurred prior to commencement of this project.
- 2.) Permits, if necessary, costs by others.
- 3.) Work to be completed during 2022 sometime between May 15th and September 15th due to temperature requirements for the NHL mortar. If work is to be completed in 2023 or beyond, we reserve the right to adjust pricing.
- 4.) Date of construction and type of stone on exterior of this building were obtained from:
 Wisconsin Historical Society, Wisconsin Architecture and history Inventory, "Laura and George Peckham Miller House," City of Milwaukee, County of Milwaukee, WI, 27223
- 5.) Repairs to paver walkway by front piers, by others.
- 6.) Any and all landscaping repairs, if necessary, by others.
- 7.) Urns on top of the front columns assumed to be simply set on top and not part of the structure requiring significant procedures to remove &/or replace.
- 8.) Rebuilding of the front two columns is our base bid and contains general conditions along with material approvals. Therefore, item 2 cannot be completed as a stand alone item without item 1 being completed first.







EXTENT

