SUBTERRANEAN UNDERGROUND EXPERTS

ESTIMATE 873 W Windlake Ave

Subterranean

3021 N pierce Milwaukee, Wisconsin 53212 United States

4149370971

Hermenegildo Zacaula Estin	Estimate Number:	111
	Estimate Date:	September 27, 2022
Jdz2020@gmail.com	Expires On:	September 27, 2022
	Grand Total (USD):	\$44,091.00

Items	Quantity	Price	Amount
Basement pipe dig Excavate Cast pipe that had standing water and rusted out a total of 18ft and replace with 4 inch schedule 40. Replace 6 inch clay (4ft) and excavate for a new cleanout per code	1	\$4,748.00	\$4,748.00
Exterior Dig Dig 7ft down and up to 8ft across to access 6 inch clay pipe and replace 6-8ft of it upstream of where it turns to 8 inch pipe. Install a 8inch cleanout with 10 inch frost sleeve. All digging must be done by hand because there is oly 4.5 feet between houses	1	\$10,893.00	\$10,893.00
Exterior Dig Replace all 8 inch sewer lateral from the side of the house to the connection 2 feet from the main. Max dig depth of 14 feet . Includes PROW permit. Dig involves removing 2 pannels of sidewalk, 16 feet of the street and digging under 1 water main, 1 gas main and one electrical system.	1	\$28,450.00	\$28,450.00
		Total:	\$44,091.00
		Grand Total (USD):	\$44,091.00

Notes / Terms

We will replace all under slab plumbing and bring the system up to code. We will also replace all the plumbing the side of the house to the connection at the sewer main. All prices include materials and permits.