

Certificate of Appropriateness

Milwaukee Historic Preservation Commission/200 E. Wells Street/Milwaukee, WI 53202/phone 414-286-5712/fax 414-286-3004

Property

Description of work

3215 W. STATE ST. Concordia Historic District

Description of work Previous COAs have approved re-roofing, rebuilding the parapet walls, installing new windows, and constructing a new connector between Albrecht Hall and the Rincker Library.

As a continuation of the work to restore/rehabilitate the above two buildings, new mechanicals will be installed on the rooftop of the Rincker Library.

The mechanicals consist of air cooled chillers and compressors. The units will be installed at least 10 feet from the north parapet wall and approximately 20 feet from the west parapet wall.

The new mechanicals may be only slightly visible looking southeast from North 33rd Street but are otherwise not visible.

Date issued 1/14/2015 PTS ID 105811 COA

In accordance with the provisions of Section 320-21 (11) and (12) of the Milwaukee Code of Ordinances, the Milwaukee Historic Preservation Commission has issued a certificate of appropriateness for the work listed above. The work was found to be consistent with preservation guidelines. The following conditions apply to this certificate of appropriateness:

Work will be carried out per the materials and plans submitted.

All work must be done in a craftsman-like manner, and must be completed within one year of the date this certificate was issued. Staff must approve any changes or additions to this certificate before work begins. Work that is not completed in accordance with this certificate may be subject to correction orders or citations. If you require technical assistance, please contact Carlen Hatala of the Historic Preservation staff as follows: Phone: (414) 286-3004 E-mail: carlen.hatala@milwaukee.gov








Photo 8 – Library Roof, looking northwest

Mechanicals will be located on the rooftop of Rincker Library and screened from view by the parapet.



Rooftop mechanicals will be installed as shown, set back from the parapet.



Close-up of the mechanicals

Air-Cooled Chiller, Scroll Compressors

Job Information



Tag ACC-1, ACC-2 Model Number CGAM 90 Quantity Product Version 178

Unit type High efficiency

Unit nominal tonnage 90 tons



Certified in accordance with the AHRI Air-Cooled Water-Chilling and Heat Pump Water-Heating Packages Using Vapor Compression Ofcle Certification Program, which is based on AHRI Standard 550/590 (I-P) and AHRI Standard 551/591 (SI). Unit containing freeze protection fluids in the condenser or in the evaporator with a leaving chilled fluid temperature above 32°F [0°C] is certified when rated per the Standard with water. Certified units ma

be found in the AHRI Director at www.ahridirector org.



Physical Information

Length	143,100 in	Water connections	4.000 in	
Width	89,000 in	Refrigerant charge circuit 1	78.0 lb	
Height	92.400 in	Refrigerant charge circuit 2	78.0 lb	
Operating weight	5961.1 lb	Oil charge circuit 1	3.54 gal	
Shipping weight	5859.5 lb	Oil charge circuit 2	3.54 gal	

Information for LEED Projects

ASHRAE 90.1/CSA compliance	ASHRAE all to 2010	IPLV	15.4 EER
Refrigerant charge circuit 1	78.0 lb	Rated capacity (AHRI)	86.20 tons
Refrigerant charge circuit 2	78.0 lb		

Note: This product meets the minimum efficiency requirements of ASHRAE Standard 90.1 and CANSICSA C743 for all versions (which are based on AHRI standard rating conditions) and, therefore, also meets the LEED "Minimum Energy Performance" prerequisite in the Energy and Atmosphere section.

The LEED Green Building Rating System **, developed by the U.S. Green Building Council, provides independent, third-party verification that a building project meets green building and performance measures.



Photo 2a - View South Looking East from 33rd (Parapet Under Construction)



Photomontage showing what mechanicals will look like after installation

Photomontage 2b – View South Looking East from 33^{rd} (With Rooftop Equipment)