

Masonry

New mortar must match the original mortar in terms of color, texture, joint width, and joint finish/profile. Mortar that is too hard is subject to premature failure and could damage the masonry. See the city's books As Good As New or Good for Business, Masonry Chapters, for more information. In most cases this means a lime mortar with natural hydraulic cement rather than Portland cement. No joint of a width less than 3/8" may be cleaned of damaged/decomposed mortar

with power disc grinders. No over-cutting of the joints is permitted. Remove decomposed mortar back into the wall 2.5 times the height of the joint before tuckpointing.

New brick must match as closely as possible the color texture, size and finish of the original brick.

A sample panel of brick and mortar must be reviewed and approved by HPC staff prior to general installation of the material.

Roofs

No dormers, chimneys, moldings or other permanent features will be altered or removed. No box vents, if used, will be visible from the street. If they are installed they must be on a rear slope not visible from the street and they must be painted to blend with the color of the roofing material. A continuous ridge vent can be installed in place of box vents, but the vent must extend across the entire ridge and not stop short. Built-in rain gutters will be retained and sealed where needed. Valleys must be metal W-shape with no interweaving of shingles. Valleys and flashing must be painted or factory-finished to match the roofing color, unless copper. When installing new flashing at a masonry feature, the flashing must be stepped or cut into the mortar joints. The bricks may not be cut to install flashing at an angle.

We strongly recommend that the Wisconsin Historical Society's best practices for re-roofing be used so as to extend the life of your new roof. https://www.wisconsinhistory.org/Records/Article/CS4260


All work must be done in a craftsman-like manner, and must be completed within one year of the date this certificate was issued. Staff must approve any changes or additions to this certificate before work begins. Work that is not completed in accordance with this certificate may be subject to correction orders or citations. If you require technical assistance, please contact Historic Preservation staff as follows: Phone: (414) 286-5712 E-mail: HPC@milwaukee.gov.

If permits are required, you are responsible for obtaining them from the Milwaukee Development Center. If you have questions about permit requirements, please consult the Development Center's web site, <u>www.milwaukee.gov/build</u>, or call (414) 286-8210.

Tom ans

City of Milwaukee Historic Preservation Staff

Copies to: Development Center, Ald. Robert Bauman, Contractor



Recent front view of property



Chimney details showing approiate step flashing. Mortar must be no harder than Type O and preferably made with natural and not Portland cement. A concrete cap may be installed, but no bricks may be removed. Any replacement bricks shall be salvaged cream city brick to match existing.



Typical roof conditions.