

Sebald Millwork LLC
Nate Sebald nate.sebald@gmail.com

April 17, 2018
PH 4-339-1704

Job Address 1851 N. 2nd Street

Quotation as follows...

Windows NOTED as "To Be ReStored" IE: DH Sash Casement Sash and Fixed Sash
Sebald Millwork to...

Remove sash from openings

Remove all hardware and original glass

Have sash chemically stripped

Deliver sash and glass lites to Acker Millwork

Upon Receiving Sash...

Acker Millwork will look sash over and determine which parts need replacing

New sash parts will be over and above At an average cost per part of \$195.00

Install new sash parts, clean-up sand sash, woodlife treat & oil-base prime Interior & Exterior

Glaze sash with the original glass, backbedded and set with diamond glaziers points and putty glazed

DH Sash machined for and supplied with New tilt jamb liners AND

Ploughed and kerfed for and supplied with bulb weatherstrip at checkrails and bottom rails

All New Sash & Sash Parts, Combinations & Storms by Acker Millwork Co...

Manufactured in Clear Solid Northern White Pine [NO finger joints or veneers]

Sash, Combinations & Storms Constructed with mortise and tenon waterproof glued joints

Machine & Finish hand sanded, woodlife treated and oil-base primed

New Sash...

Sticking Profiles, LayOuts and Overalls of Stiles & Rails and Muntins & Bars

To match existing as close as possible using knives from our library

OMISSIONS - All By Others • Hardware • Finishing • Fitting/Installation

Manufacturing time TBD

50% deposit required on all orders

Balance due at pick up Our Plant

Thank You...

- Pete Acker

Continued...

Location 1st Floor Front Elevation - South of Entrance Door
ReStore (2) Pair of InSwing Casement Sash

2 Storms Single putty glazed with 1/8" clear glass
Each true divided 6 lite -2 wide x 3 high-

2 Screens Each true divided with 1-vertical bar Screened with black aluminum wire

Location 1st Floor Front Elevation - Front Entrance

2 Sidelight Storms Single putty glazed with 1/8" clear Tempered glass
1 Transom Storm Single putty glazed with 1/8" clear Tempered glass

Alternate Sidelight Storms and Transom Storm glazed with clear Tempered insulating glass

Location 1st Floor Front Elevation - North of Entrance Door

ReStore (1) Set of DH Cottage Style Sash - Salvaged from 2nd Floor Front Elevation

1 Storm True divided 6 lite -2 wide x 3 high- Single putty glazed with 1/8" clear glass

1 Screen True divided with 1-vertical bar Screened with black aluminum wire

Sebald Millwork LLC
Nate Sebald nate.sebald@gmail.com

April 17, 2018
PH 4-339-1704

Continued...

Location 1st Floor South Left & Right of Fireplace
ReStore (2) Sets of DH Sash

2 DH Acker Combination Storms & Screens
1/8" clear glass
1/2" clear insulating glass

Location 1st Floor Kitchen

4 Sets of 1-3/8" DH Sash with white vinyl tilt jamb liners (2-South wall & 2-North wall)
Each Sash true divided 6 lite -3 wide x 2 high- Single putty glazed with 1/8" clear glass

4 DH Acker Combination Storms & Screens
1/8" clear glass
1/2" clear insulating glass

1 DH Window Unit (West wall)
Includes Combination with 1/8" clear glass
For Combination with 1/2" clear insulating glass

Location 1st Floor North Guest Room
ReStore (1) Set of DH Sash

1 DH Acker Combination Storm & Screen
1/8" clear glass
1/2" clear insulating glass

Continued...

Location 2nd Floor - Top of Stairs (proposed bath)

1 OutSwing Awning Window Unit Size to match existing
Sash true divided 3 lite wide Single putty glazed with 1/8" clear safety glass
Hinged at top with push & hold open bar
NOTE A Hardware allowance is included

1 One-Lite Acker Combination Single glazed with 1/8" clear glass
To be installed @ interior NOTE No mounting hardware figured or included

Location Kitchen - clear story

ReStore (6) FIXED Sash

6 One-Lite Storms
1/8" clear glass
1/2" clear insulating glass

Location Basement North Elevation

1 1-3/8" Sash True divided 2 lite wide
Single putty glazed with 1/4" clear laminate glass

1 One-Lite Acker Combination Single glazed with 1/8" clear Tempered glass

Sebald Millwork LLC
Nate Sebald nate.sebald@gmail.com

April 17, 2018
PH 4-339-1704

Continued...

Location 2nd Floor South Center Bedroom (Boys Bedroom)
ReStore (2) Sets DH Sash

2 DH Acker Combination Storms & Screens
1/8" clear glass
1/2" clear insulating glass

Location 2nd Floor Front Elevation
3 Sets of 1-3/8" DH Sash with white vinyl tilt jamb liners
Top Sash true divided 2 lite wide
Vertical mullion 2-1/4" wide and beaded at center both interior & exterior
Bottom Sash true divided 4 lite -2 wide x 2 high-
Center vertical mullion 2-1/4" wide and beaded at center both interior & exterior
Horizontal muntins 3/4" wide

3 DH Acker Combination Storms & Screens
1/8" clear glass
1/2" clear insulating glass