

KAPUR & ASSOCIATES, INC.
CONSULTING ENGINEERS
7711 N. PORT WASHINGTON ROAD
MILWAUKEE, WISCONSIN 53217

www.kapurengineers.com

Phone: 414.351.6668 Fax: 414.351.4117

PROJECT:

ADMIRALS WHARF

LOCATION:

234 S. WATER ST., MILWAUKEE, WI 53204

CLIENT:

RELEASE:

VJS ONSTRUCTION SERVICES

# DATE DESCRIPTION

NORTH ARROW:

1" = 2

0 20 40

IF NOT ONE INCH ADJUST SCALE
ACCORDINGLY

L:

we listen. we innovate. we turn your vision into reality.


EET:

PLAT OF SURVEY WITH TOPOGRAPHY

PROJECT MANAGER: TP
PROJECT NUMBER: 15.0063.01

DATE: NOVEMBER 19, 2019

HEET NUMBER:



PROPOSED SCHEMATIC DRAWINGS FOR:

ADMIRAL'S WHARF

234 S WATER ST MILWAUKEE, WI



	DATE	REV	ISSUE
ı			CIFICATIONS AS INSTRUMENTS PROPERTY OF VJS

DRAWINGS AND SPECIFICATIONS AS INSTRUMENTS
OF SERVICE ARE THE PROPERTY OF VJS
CONSTRUCTION SERVICES. THE
ARCHITECT/ENGINEER ASSUMES NO
RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE
PLANS FOR ANY PROJECT OTHER THAN
SPECIFICALLY AUTHORIZED BY THEM AND SIGNED
AND SEALED FOR SUCH SPECIFIC LOCATION IN THE
STATE, PROVINCE, OR TERRITORY SHOWN ON THE

PROJECT NUMBER 1170764

DATE 11/19/2019

DRAWN BY


CHECKED BY

SCALE 1" = 20'-0"

BWJ

SITE DEMOLITION PLAN

 $C1.0^{\circ}$ 



CONSTRUCTION SERVICES

W233 N2847 ROUNDY CIRCLE WEST
PEWAUKEE, WI 53072
P. 262.542.9000
F. 262.542.1371
WWW.VJSCS.COM

PROPOSED SCHEMATIC DRAWINGS FOR:

ADMIRAL'S WHARF

234 S WATER ST MILWAUKEE, WI



DATE	REV	ISSUE
		CIFICATIONS AS INSTRUMENTS

OF SERVICE ARE THE PROPERTY OF VJS
CONSTRUCTION SERVICES. THE
ARCHITECT/ENGINEER ASSUMES NO
RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE
PLANS FOR ANY PROJECT OTHER THAN
SPECIFICALLY AUTHORIZED BY THEM AND SIGNED
AND SEALED FOR SUCH SPECIFIC LOCATION IN THE
STATE, PROVINCE, OR TERRITORY SHOWN ON THE
SFAI

PROJECT NUMBER 1170764

DATE 11/19/2019

DRAWN BY


CHECKED BY

SCALE 1" = 20'-0"


SITE PLAN

C1.02


BWJ




1/07/2019 9:01:44 AM



DATE	REV	ISSUE
		CIFICATIONS AS INSTRUMENTS PROPERTY OF VJS



11/07/2019 9:01:44 AM



DATE	REV	ISSUE
		_

### EROSION CONTROL MEASURES

- CONTRACTOR TO INSTALL AND MAINTAIN EROSION CONTROL MEASURES AS INDICATED ON THIS PLAN AND PER THE LATEST WDNR TECHNICAL STANDARDS. TECHNICAL STANDARDS MAY BE VIEWED ONLINE AT:

  http://dnr.wi.gov/runoff/stormwater/techstds.htm
- 2. INLETS AND CATCH BASINS SHALL BE PROTECTED WITH INLET FILTERS THAT ARE PHASED IN WITH CONSTRUCTION TO REDUCE SEDIMENT FROM ENTERING THESE AREAS PER WDNR TECHNICAL STANDARD 1060 AS FOLLOWS:
- A. ALL FABRIC BARRIERS SELECTED FOR INLET/CATCH BASIN PROTECTION DEVICES SHALL BE SELECTED FROM THE LIST OF APPROVED FABRICS CERTIFIED FOR INLET PROTECTION, GEOTEXTILE FABRIC, TYPE FF IN THE CURRENT EDITION OF THE WDOT PRODUCT ACCEPTABILITY LIST, TO OBTAIN THE PAL, PLEASE REFER TO THIS WEBSITE: http://www.dot.wisconsin.gov/business/engrserv/pal.htm
- B. INLET PROTECTION SHALL BE AT A MINIMUM INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT OF ½ INCH OR GREATER DURING A 24-HOUR PERIOD.
- C. PLACEMENT OF SPOIL MATERIAL, DEBRIS, SOILS, ETC. ON TOP OF INLETS/CATCH BASINS, EVEN IF TEMPORARY, IS STRICTLY DISCOURAGED AND PROHIBITED.
- D. SEDIMENT DEPOSITS SHALL BE REMOVED AND THE INLET PROTECTION DEVICE RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED BETWEEN 1/3 TO ½ THE DESIGN DEPTH OF THE DEVICE, OR WHEN THE DEVICE IS NO LONGER FUNCTIONING PER MANUFACTURER'S SPECIFICATIONS. ALL SEDIMENT COLLECTED SHALL BE PROPERLY DISPOSED OF TO PREVENT DISCHARGE INTO AREA WATERWAYS AND WETLANDS.
- E. DUE CARE SHALL BE TAKEN TO ENSURE SEDIMENT DOES NOT FALL INTO THE INLETS/CATCH BASINS AND IMPEDE THE INTENDED FUNCTION OF THE DEVICE. ANY MATERIAL FALLING INTO THE INLET/CATCH BASIN SHALL BE REMOVED AND PROPERLY DISPOSED OF PER NOTE D ABOVE.
- F. INLET FILTERS MAY BE REMOVED AND PROPERLY DISPOSED OF UPON COMPLETION OF CONSTRUCTION, HAULING OR MOVEMENT OF CONSTRUCTION EQUIPMENT THROUGHOUT THE SITE, AND ONCE THE SITE IS ADEQUATELY STABILIZED, UNLESS AS OTHERWISE NOTIFIED BY THE WDNR.
- 3. A TRACKING PAD SHALL BE INSTALLED AS SHOWN ON THE PLAN SHEET PRIOR TO THE START OF CONSTRUCTION TO REDUCE OFF-SITE SEDIMENTATION BY ELIMINATING THE TRACKING OF SEDIMENT FROM THE SITE PER WDNR TECHNICAL STANDARD 1057 AS FOLLOWS:
- A. A WISDOT TYPE R GEOTEXTILE FABRIC SHALL BE USED TO PREVENT MIGRATION OF UNDERLYING SOIL INTO THE STONE.
- B. AGGREGATE USED FOR TRACKING PADS SHALL BE 3 TO 6 INCH CLEAR OR WASHED STONE. ALL MATERIAL TO BE RETAINED BY 3 INCH SIEVE.
- C. THE AGGREGATE SHALL BE PLACED IN A LAYER ON TOP OF THE TYPE R GEOTEXTILE FABRIC AT LEAST 12 INCHES THICK.
- D. THE TRACKING PAD SHALL BE THE FULL WIDTH OF THE EGRESS POINT AND BE AT LEAST 50 FEET LONG.
- E. VEHICLES TRAVELING ACROSS THE TRACKING PAD SHALL MAINTAIN A SLOW CONSTANT SPEED.
- F. ANY SEDIMENT OR ROCK ACCUMULATION ONTO LOCAL ROADWAYS SHALL BE REMOVED BY STREET CLEANING, NOT FLUSHING BEFORE THE END OF EACH WORKING DAY.

G. THE TRACKING PAD SHALL, AT A MINIMUM BE INSPECTED

- WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT OF 1/2 INCH OF RAIN OR MORE DURING A 24-HOUR PERIOD.
- H. THE TRACKING PAD PERFORMANCE SHALL BE MAINTAINED BY SCRAPING OR TOP-DRESSING WITH ADDITIONAL AGGREGATE.
   I. A MINIMUM 12-INCH THICK PAD SHALL BE MAINTAINED.

DATE, TIME OF INSPECTION, AND WEATHER CONDITIONS IN A DAILY LOG BOOK.

SUCH AS A MAILBOX, AVAILABLE TO REGULATORY AGENCIES UPON REQUEST.

THE TIMING AND SEQUENCE OF CONSTRUCTION IS SCHEDULED AS FOLLOWS:

PLACE WITH ALL RELEVANT PARTIES IN ATTENDANCE.

WILL BE APPLIED PER PROJECT SPECIFICATIONS.

INLET FILTER PROTECTION SHALL BE REMOVED.

GENERAL CONTRACTOR TO THE CITY AND WDNR.

EROSION CONTROL OPERATION SEQUENCE + SCHEDULE

AFTER BIDS ARE RECEIVED AND A MASS GRADING CONTRACTOR IS SELECTED, A PRE-CONSTRUCTION MEETING SHALL TAKE

HE GENERAL CONTRACTOR IS RESPONSIBLE FOR INSTALLING AND MAINTAINING ALL SILT FENCES. SEEDING. EROSION MATTING

AND OTHER EROSION CONTROL MEASURES. GENERAL CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PRIOR

TO COMMENCING GRADING, GRUBBING, OR OTHER LAND DISTURBING ACTIVITIES. EROSION CONTROL MEASURES MUST BE

ACTIVE CONTRACTOR SHALL CONDUCT DAILY INSPECTIONS AND DOCUMENT CONDITIONS AND REPAIRS MADE, ALONG WITH

ALL REGULATORY PERMITS, PROJECT PLANS, AND INSPECTION LOGS SHALL BE KEPT ON SITE IN AN ACCESSIBLE LOCATION,

. OBTAIN PLAN APPROVAL FROM THE CITY OF MILWAUKEE, AND ALL APPLICABLE PERMITS, INCLUDING EROSION CONTROL

3. A GRAVEL TRACKING PAD UNDERLAIN WITH WISDOT TYPE R GEOTEXTILE FABRIC, SHALL BE INSTALLED AS SHOWN ON THE

4. SILT FENCE AND INLET FILTER PROTECTION SHALL BE INSTALLED AS SHOWN ON THE PLANS, AND INSPECTED PRIOR TO

5. FOLLOWING INSTALLATION OF THE EROSION CONTROL MEASURES, EXCAVATE THE BIORETENTION BASIN TO FUNCTION AS A

CONTRACTOR SHALL CONSTRUCT BASIN INLETS AND OUTLET STRUCTURE FOR USE DURING CONSTRUCTION. CONTRACTOR SHALL IMMEDIATELY STABILIZE THE BASIN BANKS, INLETS, AND OUTLET STRUCTURE. BIORETENTION/SEDIMENT BASIN SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES ½ INCH OF RAIN OR MORE DURING A 24-HOUR PERIOD. SEDIMENT SHALL BE REMOVED TO MAINTAIN THE 3 FOOT DEPTH OF

THE TREATMENT SURFACE AREA AS MEASURED FROM THE INVERT OF THE PRINCIPAL OUTLET. IF THE OUTLET BECOMES CLOGGED IT SHALL BE CLEANED TO RESTORE FLOW CAPACITY. SEDIMENT TO BE REMOVED AFTER CONSTRUCTION & SITE

7. CONSTRUCTION OF THE BUILDING, STARTING WITH THE FOUNDATION, WILL BEGIN IMMEDIATELY AFTER THE SITE DEMOLITION

8. TOPSOIL STRIPPING AND ROUGH GRADING WILL FOLLOW. TOPSOIL STOCKPILES WILL BE LOCATED AS SHOWN ON THE PLANS.

10. AFTER ROUGH GRADING IS COMPLETE IN AREAS OUTSIDE OF PROPOSED ROADWAYS, PARKING LOTS, BUILDINGS, AND ALL OTHER HARD SURFACE AREAS, THE TOPSOIL WILL BE REAPPLIED AND THE LANDSCAPE CONTRACTOR WILL COMPLETE

11. FINAL SITE STABILIZATION IS ANTICIPATED FOLLOWING THE COMPLETION OF GRADING ACTIVITIES. IF SITE STABILIZATION CANNOT BE COMPLETED BY OCTOBER 1, THEN THE USE OF ANIONIC POLYACRYLAMIDE CONFORMING TO WDNR TECHNICAL

12. AFTER ALL TOPSOIL HAS BEEN REAPPLIED AND STABILIZATION IS UNDERWAY, ROADWAY, AND SIDEWALK BASE MATERIAL

13. THE GENERAL CONTRACTOR WILL REQUEST A FINAL INSPECTION BY THE CITY. UPON APPROVAL, ALL SILT FENCES AND

14. IF REQUIRED, FINAL "AS-BUILT" SURVEYS ARE TO BE CONDUCTED BY THE OWNER AND FINAL DOCUMENTS FORWARDED

STANDARD 1059, OR TEMPORARY GRADING PRACTICES PER WDNR TECHNICAL STANDARD 1067 MAY BE IMPLEMENTED.

16. WE DO NOT ANTICIPATE THE NEED FOR WATERING WITH THIS CONSTRUCTION SCHEDULE, HOWEVER, IF ADEQUATE RAIN IS NOT EXPERIENCED WITHIN ONE WEEK AFTER INITIAL SEED GERMINATION AT ANY POINT DURING THE CONSTRUCTION

IF CONSTRUCTION SCHEDULES SHOULD CHANGE SIGNIFICANTLY, THIS PLAN NARRATIVE WILL BE UPDATED AND RESUBMITTED BY THE

5. BARE SOIL LEFT UNDISTURBED FOR 14 CALENDAR DAYS MUST BE TEMPORARILY STABILIZED PER WDNR TECHNICAL

SEEDING/SODDING/FERTILIZING/MULCHING AND INSTALL EROSION MATTING AS PER APPROVED PLANS AND SPECIFICATIONS.

STOCKPILES WILL BE USED FOR FINAL LANDSCAPING. REMAINING STOCKPILES WILL BE REMOVED FROM THE SITE.

TO TEMPORARILY DIRECT STORMWATER RUNOFF TO SEDIMENT BASIN DURING SITE CONSTRUCTION OPERATIONS.

6. SITE DEMOLITION OF PAVEMENT, ETC. WILL OCCUR AFTER ALL EROSION CONTROL MEASURES ARE IN PLACE.

9. UTILITY INSTALLATION WILL OCCUR NEXT AND CONTINUE UNTIL ALL THE UTILITIES ARE INSTALLED.

HOWEVER BY OCTOBER 1, THE SITE SHALL BE STABILIZED PER NOTE 12 ABOVE.

PROCESS, WATER SHALL BE TRUCKED IN AND APPLIED ONCE PER WEEK.

SEDIMENT BASIN DURING CONSTRUCTION. CONSTRUCT DIVERSION SWALES AT THE PERIMETER OF LAND DISTURBANCE AREAS

INSPECTED WEEKLY AND WITHIN 24 HOURS OF EVERY PRECIPITATION EVENT OF 1/2 INCH OR GREATER. IN ADDITION. THE

CONTRACTORS ARE TO MAINTAIN THE CONSTRUCTION SITE IN A NEAT AND TIDY MANNER FOR THE DURATION OF THE

2. CONSTRUCTION IS SCHEDULED TO BEGIN IN SPRING 2020, DEPENDING ON WEATHER & GROUND CONDITIONS.

COMMENCING OF ANY LAND DISTURBING ACTIVITIES PER PROJECT PLANS AND DETAILS.

- 4. THE CONSTRUCTION SITE PERIMETER AND TOPSOIL STOCKPILE AREA SHALL BE PROTECTED WITH SILT FENCE AS SHOWN ON THE PLAN SHEET PRIOR TO THE START OF CONSTRUCTION TO INTERCEPT AND REDUCE THE FLOW OF SEDIMENT-LADEN SHEET FLOW RUNOFF FROM THE CONSTRUCTION SITE PER WDNR TECHNICAL STANDARD 1056 AS FOLLOWS:
- A. SILT FENCE ENDS SHALL BE EXTENDED UPSLOPE TO PREVENT WATER FROM FLOWING AROUND THE ENDS OF THE FENCE AS SHOWN ON THE PLAN SHEET.
- B. INSTALLED SILT FENCE SHALL BE A MINIMUM 14
  INCHES HIGH AND SHALL NOT EXCEED 28 INCHES
  IN HEIGHT MEASURED FROM THE INSTALLED
- C. SILT FENCE SHALL BE SUPPORTED BY EITHER STEEL OR WOOD SUPPORT POSTS.

GROUND ELEVATION.

- D. THE MAXIMUM SPACING OF POSTS FOR NONWOVEN SILT FENCE SHALL BE 3 FEET OR
- NONWOVEN SILT FENCE SHALL BE 3 FEET OR FOR WOVEN FABRIC 8 FEET.

E. SILT FENCE SHALL HAVE A SUPPORT CORD AT

- F. WHERE JOINTS ARE NEEDED, EACH END OF THE FABRIC SHALL BE SECURELY FASTENED TO A POST. THE POSTS SHALL BE WRAPPED AROUND EACH OTHER TO PRODUCE A STABLE AND SECURE JOINT OR SHALL BE OVERLAPPED THE DISTANCE BETWEEN TWO POSTS.
- G. A MINIMUM OF 20 INCHES OF THE POSTS SHALL EXTEND INTO THE GROUND AFTER INSTALLATION.
- H. SILT FENCE SHALL BE ANCHORED BY SPREADING AT LEAST 8 INCHES OF THE FABRIC IN A 4 INCH WIDE BY 6 INCH DEEP TRENCH, OR 6 INCH DEEP V—TRENCH ON THE UPSLOPE SIDE OF THE FENCE. THE TRENCH SHALL BE BACKFILLED AND COMPACTED. TRENCHES SHALL NOT BE EXCAVATED ANY WIDER OR DEEPER THAN NECESSARY FOR PROPER INSTALLATION.
- I. ON THE TERMINAL ENDS OF THE SILT FENCE THE FABRIC SHALL BE WRAPPED AROUND THE POST SUCH THAT THE STAPLES ARE NOT VISIBLE.
- J. GEOTEXTILE FABRIC SPECIFICATIONS SHALL MEET VALUES ESTABLISHED IN TECHNICAL STANDARD
- K. SILT FENCE SHALL BE REMOVED ONCE THE SITE IS ADEQUATELY STABILIZED.
- L. WHEN PLACING SILT FENCE NEAR TREES, CARE SHALL BE TAKEN TO MINIMIZE DAMAGE TO THE ROOT SYSTEM BY AVOIDING COMPACTION AND ROOT CUTTING WITHIN 1.5 FEET MULTIPLIED BY THE INCH DIAMETER OF THE TREE.
- M. THE CONTRACTOR MAY FURTHER STRENGTHEN THE SILT FENCE BY USING HAY BALES ON THE DOWN SLOPE SIDE AS NEEDED.
- N. SILT FENCE SHALL AT A MINIMUM BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES ½ INCH OF RAIN OR MORE DURING A 24 HOUR PERIOD.
- O. DAMAGED OR DECOMPOSED SILT FENCE, UNDERCUTTING, OR FLOW CHANNELS AROUND THE END OF BARRIERS SHALL BE REPAIRED OR CORRECTED
- P. SEDIMENT SHALL BE PROPERLY DISPOSED OF ONCE THE DEPOSITS REACH ½ THE HEIGHT OF THE FENCE TO PREVENT DISCHARGE INTO AREA WATERWAYS AND WETLANDS.

- OIL
  LT
  WHERE THE ESTABLISHMENT OF VEGETATION IS DESIRED. TEMPORARY SEEDING APPLIES
  TO THE
  TO DISTURBED AREAS THAT WILL NOT BE BROUGHT TO FINAL GRADE OR ON WHICH
  LAND-DISTURBING ACTIVITIES WILL NOT BE PERFORMED FOR A PERIOD GREATER THAN 14
  UNOFF
  WINICAL
  WILCH SHALL BE UTILIZED THROUGHOUT THE DURATION OF CONSTRUCTION TO
  ESTABLISH TEMPORARY VEGETATION TO HELP REDUCE EROSION PER WDNR TECHNICAL
  STANDARDS 1059 AND 1058 RESPECTIVELY AS FOLLOWS:
  - A. TEMPORARY SEEDING REQUIRES A SEEDBED OF LOOSE SOIL TO A MINIMUM DEPTH
  - B. FERTILIZER APPLICATION IS NOT GENERALLY REQUIRED FOR TEMPORARY SEEDING.
    HOWEVER, ANY APPLICATION OF FERTILIZER OR LIME SHALL BE BASED ON SOIL
  - C. THE SOIL SHALL HAVE A PH RANGE OF 5.5 TO 8.0.
  - D. ALL SEED SHALL CONFORM TO THE REQUIREMENTS OF THE WISCONSIN STATE STATUTES AND OF THE ADMINISTRATIVE CODE CHAPTER ATCP 20.01 REGARDING NOXIOUS WEED SEED CONTENT AND LABELING.
  - E. SEED SHALL NOT BE USED LATER THAN ONE YEAR AFTER THE TEST DATE ON THE
  - F. IN THE SUMMER-SPRING, CONTRACTOR SHALL USE OATS APPLIED AT 131
    LBS/ACRE FOR TEMPORARY SEEDING PURPOSES. IN THE FALL THE CONTRACTOR
    SHALL USE ANNUAL RYEGRASS APPLIED AT 80 LBS/ACRE OR WINTER WHEAT
    APPLIED AT 131 LBS/ACRE. THE CONTRACTOR SHALL USE STRAW MULCH APPLIED
    AT 1.5 TONS/ACRE. DORMANT SEED SHALL BE USED WHEN SOIL TEMPERATURE IS
    CONSISTENTLY BELOW 53 DEGREES FAHRENHEIT (TYPICALLY NOV. 1 UNTIL SNOW
    COVER ANNUALLY). NEVER PLACE SEED ON TOP OF SNOW. IF COVER IS NEEDED
    AFTER SNOW FALL, CONTRACTOR MAY CHOOSE TO USE A DRY, NONTOXIC TYPE B
    SOIL STABILIZER PER MANUFACTURER'S SPECIFICATIONS AS REQUIRED BY THE
  - G. SEEDING SHALL NOT TAKE PLACE WHEN THE SOIL IS TOO WET.
  - H. CONTRACTOR MAY CONSIDER WATERING TO HELP ESTABLISH THE SEED. WATER APPLICATION RATES SHALL BE CONTROLLED TO HELP PREVENT RUNOFF AND FROSION.
  - I. DURING CONSTRUCTION, AREAS THAT HAVE BEEN SEEDED AND MULCHED SHALL AT A MINIMUM BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES ½ INCH OF RAIN OR MORE DURING A 24 HOUR PERIOD. INSPECT WEEKLY DURING THE GROWING SEASON UNTIL VEGETATION IS DENSELY ESTABLISHED OR THE SOD IS LAID. REPAIR AND RESEED AREAS THAT HAVE EROSION DAMAGE AS NECESSARY.
  - J. CONTRACTOR IS TO LIMIT VEHICLE TRAFFIC AND OTHER FORMS OF COMPACTION IN AREAS THAT ARE SEEDED AS MUCH AS POSSIBLE. RE—SEED DRIVEN OVER AREAS
  - K. MULCH SHOULD BE PLACED WITHIN 24 HOURS OF SEEDING.
  - L. MULCHING OPERATIONS SHALL NOT TAKE PLACE DURING PERIODS OF EXCESSIVELY HIGH WINDS THAT WOULD PRECLUDE THE PROPER PLACEMENT OF MULCH.
  - M. MULCH THAT IS DISPLACED SHALL BE REAPPLIED AND PROPERLY ANCHORED.
    MAINTENANCE SHALL BE COMPLETED AS SOON AS POSSIBLE WITH CONSIDERATION
    TO SITE CONDITIONS.
  - N. WHEN CHANNEL EROSION MAT IS USED WITHIN CONSTRUCTION SITE DIVERSION AREAS, TECHNICAL STANDARDS 1053 AND 1066 SHALL BE FOLLOWED.
  - O. WHEN NON-CHANNEL EROSION MAT IS USED TECHNICAL STANDARD 1052 SHALL BE FOLLOWED.
  - P. DEPENDING ON DURATION OF CONSTRUCTION, THE CONTRACTOR MAY NEED TO RE—SEED AND RE—STABILIZE THE TOPSOIL STOCKPILE AS NECESSARY TO DISCOURAGE SEDIMENT AND EROSION.
  - 6. A COPY OF EROSION CONTROL INSPECTION REPORTS AND THE APPROVED EROSION CONTROL PLANS SHALL BE KEPT ON SITE.
  - 7. CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL PRACTICES BY THE END OF EACH WORKDAY
  - 8. LOCAL ROADS SHALL BE CLEAN BY THE END OF EACH WORKDAY. CONTRACTOR SHALL HAVE LOCAL ROADS SWEPT WHERE SEDIMENT ACCUMULATES.

### DEWATERING PLAN


TO FACILITATE CONSTRUCTION AT THE PROJECT SITE, DEWATERING MAY TAKE PLACE BY THE SELECTED CONTRACTOR. CONTRACTOR TO FOLLOW THESE INSTRUCTIONS WHILE PERFORMING DEWATERING ACTIVITIES

NOTE: THESE INSTRUCTIONS DO NOT APPLY TO WATER BEING DISCHARGED DIRECTLY TO GROUNDWATER OR KARST FEATURES OR WELL DEWATERING SYSTEMS. CONTRACTOR SHALL COORDINATE ACCORDINGLY FOR

- OTHER DEWATERING ACTIVITIES AS DEEMED NECESSARY WITH THE WDNR.

  1. THE CONTRACTOR SHALL ENSURE THAT THE DEWATERING PRACTICES CARRIED OUT MEET OR EXCEED
- WNDR TECHNICAL STANDARD NUMBER 1061.

  2. A PAN OR OTHER CONTAINMENT DEVICE SHALL BE PLACED UNDERNEATH THE PUMP TO CAPTURE ANY SPILLS. OILS, GASOLINE, ETC. SHALL NOT BE STORED WITHIN WETLANDS, NEAR THE STORMWATER POND, OR OTHER ON—SITE WATER AREAS.
- 3. A TYPE 2 GEOTEXTILE BAG THAT IS NO SMALLER THAN 100 SQUARE FEET; HAS A MAXIMUM APPARENT OPENING SIZE OF 0.212 mm; HAS A GRAB TENSILE STRENGTH OF 300 LBS; MULLEN BURST OF 580 PSI; PERMEABILITY OF 0.2 CM/SEC; FABRIC WEIGHT OF 12 OZ SHALL BE USED. THE GEOTEXTILE BAG AREA AND DOWNGRADE FLOW AREA SHALL CONSIST OF VEGETATED AND UNDISTURBED SOILS.
- 4. POLYMER APPROVED BY THE WDNR MEETING WDNR TECHNICAL STANDARD 1051 MAY BE USED IN COMBINATION WITH THE DEWATERING BAG IF THE DEWATERING BAG IS NOT DOING AN ADEQUATE JOB ALONE OF FILTERING SEDIMENTS. THE CONTRACTOR SHALL SUPPLY TOXICITY TESTING DATA TO THE WDNR BEFORE USE ON—SITE FOR WDNR APPROVAL. POLYMER SHALL NOT BE DIRECTLY APPLIED TO SURFACE WATER. CONTRACTOR SHALL OBTAIN THE POLYMER MATERIAL SAFETY DATA SHEETS (MSDS) FOR THE SELECTED POLYMER, MANUFACTURER'S INFORMATION AND WDNR USE RESTRICTIONS (SEE TECHNICAL STANDARD 1051) AND KEEP ALL THIS INFORMATION ON—SITE. CONTRACTOR SHALL ADHERE TO MANUFACTURER AND WDNR'S APPLICATION RATES FOR THE POLYMER. THE APPLICATION RATE SHALL NOT EXCEED THE WDNR USE RESTRICTION, EVEN IF THIS IS THE RECOMMENDED RATE BY THE MANUFACTURER. THE CONTRACTOR SHALL TAKE STEPS TO ENSURE THAT THE POLYMER IS NOT SPILLED. THE MANUFACTURER'S RECOMMENDED CLEANUP PROCEDURES SHALL BE FOLLOWED IN THE EVENT OF A SPILL.
- 5. A TARP MAY BE UTILIZED UNDERNEATH THE TYPE 2 GEOTEXTILE BAG AND JUST DOWN SLOPE OF THE BAG TO DISCOURAGE EROSION AND SCOUR.
- A FLOATING SUCTION HOSE OR OTHER FLOTATION METHOD SHALL BE UTILIZED WHEN PUMPING FROM AN AREA WITH STANDING WATER TO AVOID SUCKING SEDIMENT FROM GRADE.
- 7. IF TURBID WATER IS LEAVING THE GEOTEXTILE BAG, THE CONTRACTOR SHALL SHUT OFF THE PUMP TO ALLOW SEDIMENTS TO SETTLE INTO THE BAG. CONTRACTOR SHALL FOLLOW THE MANUFACTURER'S SPECIFICATIONS FOR DETERMINING THE SEDIMENT CAPACITY OF THE GEOTEXTILE BAG USING GOOD COMMON SENSE. SEDIMENT LEVELS CONTAINED IN THE BAG SHALL BE MONITORED TO MEASURE THE LOSS OF STORAGE CAPACITY OVER TIME. THE CONTRACTOR SHALL PROPERLY DISPOSE OF THE GEOTEXTILE BAG IN A WASTE RECEPTACLE ONCE IT IS NO LONGER USED.
- 8. DURING DEWATERING ACTIVITIES THE CONTRACTOR SHALL MONITOR DEWATERING PRACTICES AND KEEP A LOG OF THE FOLLOWING:
- A. DISCHARGE DURATION AND SPECIFIED PUMPING RATE.
- B. OBSERVED WATER TABLE AT TIME OF DEWATERING.
- C. MAINTENANCE ACTIVITIES
- D. NAME AND QUANTITY OF POLYMER USED. PRODUCT TYPE.E. APPLICATION RATE OF POLYMER IN POUNDS/ACRE FEET OF WATER.
- E. APPLICATION RATE OF POLYMER IN POUNDS/ACRE FEET OF WATER.
- F. DATE AND TIME APPLIED.
- G. WEATHER CONDITIONS DURING APPLICATION.H. METHOD OF APPLICATION.
- THIS LOG NEEDS TO BE KEPT ON SITE FOR WDNR REGULATORY REVIEW. COPIES OF THIS DOCUMENTATION SHOULD BE KEPT IN THE CONTRACTOR'S MONITORING LOG AND MADE AVAILABLE UPON REQUEST.
- REVIEW THE FOLLOWING FOR MORE INFORMATION:
- WDNR TECHNICAL STANDARD 1061 FOR DEWATERING http://dnr.wi.gov/runoff/pdf/stormwater/techstds/erosion/Dewatering\_1061.pdf
- WDNR TECHNICAL STANDARD 1051 FOR POLYMER <a href="http://dnr.wi.gov/runoff/pdf/stormwater/techstds/erosion/Dewatering\_1061.pdf">http://dnr.wi.gov/runoff/pdf/stormwater/techstds/erosion/Dewatering\_1061.pdf</a>
- INSPECT ALL EROSION CONTROL MEASURES PRIOR TO COMMENCING GRADING, GRUBBING OR OTHER LAND DISTURBING ACTIVITIES. EROSION CONTROL MEASURES MUST BE INSPECTED WEEKLY AND WITHIN 24 HOURS OF EVERY PRECIPITATION EVENT OF 0.50 INCH OR GREATER. IN ADDITION THE CONTRACTOR SHALL CONDUCT DAILY INSPECTIONS AND DOCUMENT CONDITIONS AND REPAIRS MADE, ALONG WITH DATE, TIME OF INSPECTION AND WEATHER CONDITIONS IN A DAILY LOG BOOK. THE DAILY LOG BOOK, WEEKLY / 0.50 INCH PRECIPITATION REPORTS, APPROVED PLANS WPDES PERMIT & CHAPTER 30 PERMIT SHALL BE KEPT IN AN ACCESSIBLE LOCATION, LIKE A MAILBOX, WITHIN THE STAGING AREA.
- AT ABSOLUTELY NO TIME MAY CONSTRUCTION EQUIPMENT, DEBRIS, FILL, ETC. BE PLACED WITHIN WETLANDS, WATERWAYS OR FLOODPLAINS UNLESS IDENTIFIED IN THE PLANS & APPROVED BY DNR/



DIVERSION RIDGE REQUIRED
WHERE GRADE EXCEEDS 2%

EXISTING PAVED
ROADWAY

SECTION A—A

FILTER FABRIC TYPE R

USE SANDBAGS, STRAW BALES
OF OTHER APPROVED METHODS
TO CHECK DAMAS AS REQUIRED.

FLOW

F

THE AGGREGATE SIZE FOR CONSTRUCTION OF THE PAD SHALL BE 3- TO 6-INCH STONE. PLACE THE GRAVEL TO THE SPECIFIC GRADE & DIMENSIONS SHOWN ON THE PLANS & GRADE TO CREATE A SMOOTH SURFACE.

THE THICKNESS OF THE PAD SHALL NOT BE LESS THAN 12 INCHES. USE GEOTEXTILE FABRICS, IF NECESSARY, TO IMPROVE STABILITY OF THE FOUNDATION IN LOCATIONS SUBJECT TO SEEPAGE OR HIGH WATER TABLE.

THE WIDTH OF THE PAD SHALL NOT BE LESS THAN THE FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS & IN ANY CASE SHALL NOT BE LESS THAN 15 FEET WIDE.

THE LENGTH OF THE PAD SHALL BE AS REQUIRED, BUT NOT LESS THAN 50 FEET.


LOCATE CONSTRUCTION ENTRANCES & EXITS TO LIMIT SEDIMENT LEAVING THE SITE & TO PROVIDE FOR MAXIMUM UTILITY BY ALL CONSTRUCTION VEHICLES. AVOID ENTRANCES WHICH HAVE STEEP GRADES & ENTRANCES AT CURVES IN PUBLIC ROADS.

THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE & REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS—OF—WAY SHALL BE REMOVED BY THE END OF THE WORK DAY.

PROVIDE DRAINAGE FOR A 2 YEAR - 24 HOUR EVENT TO CARRY WATER TO A SEDIMENT TRAP OR OTHER SUITABLE OUTLET.

WHEN NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, DESIGNATE AN AREA WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.



INLET PROTECTION. TYPE A

MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE SUBSTITUTED.

WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

FINISHED SIZE SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL. SIDE FLAPS, WHERE REQUIRED SHALL BE A MIN. OF TWO INCHES LONG. FOLD THE FABRIC OVER AND REINFORCE WITH MULTIPLE STITCHES.

FOR INLET PROTECTION, TYPE C (WITH CURB BOX), FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2"X4". THE REBAR, STEEL PIPE, OR WOOD SHALL BE INSTALLED IN THE FLAP AND NOT BLOCK THE TOP HALF OF THE CURB BOX OPENING.

TYPE B & C
TRIM EXCESS FABRIC A MINIMUM OF 10" AROUND GRATE FOR MAINTENANCE OR REMOVAL. THE CONTRACTOR SHALL DEMONSTRATE A
METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM
ENTERING THE INLET.

INLET PROTECTION. TYPE D.
INSTALLED IN ANY INLET TYPE, WITH OR

WITHOUT A CURB BOX)

UTILIZE INLET PROTECTION TYPE D IN INLETS DEEPER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE. THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3".

WHERE NECESSARY THE CONTRACTOR MAY CINCH THE BAG, USING PLASTIC ZIP TIES, TO FIT INLETS LESS THAN 30" DEPTH. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.

4 INLET PROTECTION DETAIL
N.T.S.

INLET PROTECTION. TYPE C. WITH CURB BOX

GRATE WITH WIRE

INSTALLATION NOTES



PROPOSED SCHEMATIC DRAWINGS FOR:

ADMIRAL'S WHARF

234 S WATER ST MILWAUKEE, WI



DATE	REV	ISSUE
-		

DRAWINGS AND SPECIFICATIONS AS INSTRUMENTS
OF SERVICE ARE THE PROPERTY OF VJS
CONSTRUCTION SERVICES. THE
ARCHITECT/ENGINEER ASSUMES NO
RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE
PLANS FOR ANY PROJECT OTHER THAN
SPECIFICALLY AUTHORIZED BY THEM AND SIGNED
AND SEALED FOR SUCH SPECIFIC LOCATION IN THE
STATE, PROVINCE, OR TERRITORY SHOWN ON THE

PROJECT NUMBER 117076.

DATE 11/19/2019

DRAWN BY BWJ


SITE DETAILS

CHECKED BY

C201

11/07/2019 9:01:44 AM

1" = 20'-0"



CONSTRUCTION SERVICE
W233 N2847 ROUNDY CIRCLE WEST
PEWAUKEE, WI 53072
P. 262.542.9000
E. 262.542.1371

PROPOSED SCHEMATIC DRAWINGS FOR:

ADMIRAL'S WHARF

234 S WATER ST MILWAUKEE, WI



DATE	REV	ISSUE

OF SERVICE ARE THE PROPERTY OF VJS
CONSTRUCTION SERVICES. THE
ARCHITECT/ENGINEER ASSUMES NO
RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE
PLANS FOR ANY PROJECT OTHER THAN
SPECIFICALLY AUTHORIZED BY THEM AND SIGNED
AND SEALED FOR SUCH SPECIFIC LOCATION IN THE
STATE, PROVINCE, OR TERRITORY SHOWN ON THE

PROJECT NUMBER 1170764

DATE 11/19/2019


DRAWN BY BWJ


CHECKED BY TP

SCALE 1" = 20'-0"

SITE DETAILS

C2.02






#### STORM OUTFALL STRUCTURE NOTES:

- 1. PRECAST CONCRETE ADJUSTING RINGS TO BE REINFORCED WITH ONE HOOP OF STEEL CENTERED WITHIN THE RING. WHERE NECESSARY, RINGS SHALL BE GROOVED TO RECEIVE STEP. 2. CONCRETE AND STEEL REINFORCEMENT SHALL CONFORM TO DESIGNATION C-478 REQUIREMENTS OF ASTM SPECIFICATIONS.
- S. JOINTS SHALL BE WATERTIGHT AND SHALL BE MADE USING RUBBER GASKETS OR BUTYL RUBBER MASTIC MATERIAL. 4. 3" MIN. BEDDING MATERIAL REQUIRED UNDER MANHOLE BASE AND BACKFILLED STRUCTURE WITH GRANULAR BACKFILL MATERIAL.
- 5. SEE STANDARD SPECIFICATIONS, FILE NO. 12 FOR PRECAST MANHOLE AND FILE NO. 13 FOR MANHOLE INVERTS, INCLUDING INVERTS OF LATERAL SEWERS THAT CONNECT DIRECTLY TO MANHOLES. 6. OUTFALL STRUCTURE SHALL HAVE TWO ACCESS POINTS WITH MANHOLE FRAME & COVER AND ACCESS LADDERS, ONE ON EACH SIDE OF THE WEIR WALL.


UNDERGROUND DETENTION FACILITY OUTLET STRUCTURE



STORM OUTFALL STRUCTURE NOTES: 1. PRECAST CONCRETE ADJUSTING RINGS TO BE REINFORCED WITH ONE HOOP OF STEEL CENTERED WITHIN THE RING. WHERE NECESSARY, RINGS SHALL BE GROOVED TO RECEIVE

- $^2$ . CONCRETE AND STEEL REINFORCEMENT SHALL CONFORM TO DESIGNATION C-478 REQUIREMENTS OF ASTM SPECIFICATIONS. 3. JOINTS SHALL BE WATERTIGHT AND SHALL BE MADE USING RUBBER GASKETS OR BUTYL RUBBER MASTIC MATERIAL.
- 4. 3" MIN. BEDDING MATERIAL REQUIRED UNDER MANHOLE BASE AND BACKFILLED STRUCTURE WITH GRANULAR BACKFILL MATERIAL. 5. SEE STANDARD SPECIFICATIONS, FILE NO. 12 FOR PRECAST MANHOLE AND FILE NO. 13 FOR MANHOLE INVERTS, INCLUDING INVERTS OF LATERAL SEWERS THAT CONNECT DIRECTLY TO
- 6. TEMPORARY 3" ORIFICE IN OUTLET STRUCTURE USED DURING THE OPERATION OF THE TEMPORARY SEDIMENT BASIN SHALL BE BULKHEADED AND CLOSED ON INTERIOR AND EXTERIOR OF STRUCTURE AND SHALL BE MADE WATERTIGHT WHEN BIORETENTION BASIN IS BROUGHT ONLINE. 8" INFLOW PIPE SHALL BE CORED INTO THE STRUCTURE WHEN THE BIORETENTION BASIN IS BROUGHT ONLINE.







PROPOSED SCHEMATIC DRAWINGS FOR:

ADMIRAL'S WHARF

234 S WATER ST MILWAUKEE, WI




DATE	REV	ISSUE
OF SERVICE CONSTRUC	ARE THE	CIFICATIONS AS INSTRUMENT PROPERTY OF VJS VICES. THE ER ASSUMES NO

PLANS FOR ANY PROJECT OTHER THAN SPECIFICALLY AUTHORIZED BY THEM AND SIGNED AND SEALED FOR SUCH SPECIFIC LOCATION IN THE STATE, PROVINCE, OR TERRITORY SHOWN ON THE

1170764 PROJECT NUMBER 11/19/2019 DATE BWJ DRAWN BY

CHECKED BY 1'' = 20'-0'' SCALE

SITE DETAILS



#### CONSTRUCTION NOTES

NOTE 1: THE BIO-RETENTION BASINS WILL FUNCTION AS TEMPORARY SEDIMENT BASINS DURING LAND DISTURBING CONSTRUCTION ACTIVITIES. THE SEDIMENT BASINS SHALL BE CONSTRUCTED WITHIN THE FOOTPRINT OF FUTURE BIO-RETENTION BASINS AND EXCAVATED TO THE APPROXIMATE DIMENSIONS OF THE FUTURE BIO-RETENTION BASINS. SEDIMENT BASINS SHALL BE CONSTRUCTED IN ACCORDANCE TO WISCONSIN DNR TECHNICAL STANDARD 1064 UNLESS SHOWN OTHERWISE IN PLANS OR SPECIFICATIONS. IF SEDIMENT BASIN NEEDS TO BE DEWATERED IT SHALL BE DONE IN ACCORDANCE TO WISCONSIN DNR TECHNICAL STANDARD 1061.

NOTE 2: FOLLOWING SITE STABILIZATION, SEDIMENT BASIN SHALL BE DEWATERED AND ACCUMULATED SEDIMENT SHALL BE REMOVED AND PROPERLY DISPOSED. FOLLOWING SEDIMENT REMOVAL THE BASINS WILL NO LONGER ACT AS TEMPORARY SEDIMENT BASINS AND THEREFORE NO SEDIMENT LADEN WATER FROM CONSTRUCTION ACTIVITIES SHALL BE ALLOWED TO DISCHARGE INTO THESE BASINS.

NOTE 3: CONSTRUCTION OF THE BIO-RETENTION BASINS SHALL BEGIN ONLY AFTER ACCUMULATED SEDIMENT WITHIN THE BASIN HAS BEEN DISPOSED AND THE SITE HAS BEEN FULLY DEVELOPED AND STABILIZED FROM EROSION SUCH THAT NO SEDIMENT/SEDIMENT LADEN RUNOFF CAN MIGRATE INTO THE BASIN.

NOTE 4: ONCE CONSTRUCTION OF THE BIO-RETENTION BASINS BEGIN, ALL HEAVY EQUIPMENT AND CONSTRUCTION TRAFFIC IS PROHIBITED WITHIN THE FOOTPRINT OF THE BIO-RETENTION BASINS, INSTALL CONSTRUCTION FENCING TO PREVENT TRAFFIC AS NEEDED. PLACEMENT OF THE STONE AND ENGINEERED SOIL LAYERS SHALL BE COMPLETED WITH A BACKHOE FROM THE SIDE SLOPES OF THE BASIN. EVERY EFFORT SHALL BE MADE TO AVOID THE COMPACTION OF THE ENGINEERED SOIL WITHIN THE BASINS DURING AND AFTER CONSTRUCTION.

NOTE 5: BASIN CONSTRUCTION SHALL BE SUSPENDED DURING PERIODS OF RAINFALL OR SNOWMELT. CONSTRUCTION SHALL REMAIN SUSPENDED IF PONDED WATER IS PRESENT OR IF RESIDUAL SOIL MOISTURE CONTRIBUTES SIGNIFICANTLY TO THE POTENTIAL FOR SOIL SMEARING, CLUMPING, OR OTHER FORMS OF COMPACTION.

NOTE 6: ENGINEERED SOIL CONSIST OF: 70% PRE-WASHED, COARSE DOLOMITIC SAND AND 30% COMPOST (SHALL MEET DNR SPECIFICATION 100; AVAILABLE AT S & R COMPOST, WAUKESHA, WI OR PURPLE COW ORGANICS, MIDDLETON, WI). WHEN ARRIVING ON SITE IT SHALL BE PLACED IMMEDIATELY OR IF STORED MUST BE PROTECTED FROM BECOMING INTERMINGLED WITH OTHER BACKFILL AND/OR SITE SOILS.

NOTE 7: CONSTRUCT PER WISCONSIN DNR TECHNICAL STANDARD 1004 BIORETENTION FOR INFILTRATION UNLESS INDICATED IN SPECIFICATIONS AND DETAILS.

ASPHALT/CONCRETE

PAVEMENT

NOTE 8: REFER TO LANDSCAPING SHEETS, L101 AND L102, FOR ADDITIONAL INFORMATION ON PLANTINGS. NOTE 9: DIMENSIONS, ELEVATIONS, AND INVERTS VARY, SEE SITE PLAN, SITE GRADING PLAN, AND SITE UTILITY

PLAN




PROPOSED SCHEMATIC DRAWINGS FOR:

## ADMIRAL'S **WHARF**

234 S WATER ST MILWAUKEE, WI

-ROADWAY BASE





ARCHITECT/ENGINEER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE PLANS FOR ANY PROJECT OTHER THAN

SPECIFICALLY AUTHORIZED BY THEM AND SIGNED AND SEALED FOR SUCH SPECIFIC LOCATION IN THE STATE, PROVINCE, OR TERRITORY SHOWN ON THE

1170764 PROJECT NUMBER 11/19/2019 DATE BWJ DRAWN BY

CHECKED BY

1" = 20'-0"

SCALE

SITE DETAILS

30" RISER AT 5'-0" 30" RISER A2 15" STUB B1 CLEARANCE ŔĔQUſŖĔĎ BETWEEN /BACKFILL /PIPES/ 48" BULKHEAD - 30" RISER B2 \_ GRANULAR BEDDING CMP UNDERGROUND DETENTION BACKFILL DETAIL 30" RISER AT 5'-0" -REINFORCING TABLE

STUB INFORMATION SYSTEM **PIECE** STUB INVERT INVERT 12" STUB A1 1.50 -0.50 15" STUB B1 -0.50 -0.50

RISER	INFORMA	ATION
PIECE	RIM ELEV.	SYSTEM INVERT
30" RISER A2	5.30	-0.50
30" RISER B2	4.85	-0.50

DIAMETER CMP UNDERGROUND DETENTION SYSTEM

2'-6"

11-0"

12" STUB A1

48" CMP

PIPE STORAGE VOLUME = 2,945 CU. FT.

1) ALL RISER AND STUB DIMENSIONS ARE TO CENTERLINE.

CHAPTER 8 OF THE NCSPA CSP DESIGN MANUAL.

2) ALL FITTINGS AND REINFORCEMENT SHALL COMPLY TO ASTM A998.

3) ALL RISERS AND STUBS ARE  $2\frac{2}{3}$ "  $\times \frac{1}{2}$ " CORRUGATION AND 16 GAGE UNLESS

WILL MATCH THE CMP COATING. BULKHEAD PLATES SHALL BE FULLY

WELDED ONTO THE CMP WITH STEEL REINFORCEMENT AS REQUIRED.

BULKHEAD DESIGNS SHALL SATISFY THE REQUIREMENTS SHOWN IN

5) BULKHEADS SHALL BE 12-GAGE OR HEAVIER STEEL AND THE COATING

MAINLINE PIPE GAGE=14

TRAFFIC LOADING: H25

OTHERWISE NOTED.

4) RISERS TO BE FIELD TRIMMED TO GRADE.

WALL TYPE: SOLID


CORRUGATION=5x1

PIPE INVERT: -0.50

DIAMETER = 48"

48" CMP

48" CMP



NOTES:

1. DESIGN IN ACCORDANCE WITH AASHTO, 17th EDITION AND ACI 350.


2. DESIGN LOAD HS25. 3. CONCRETE STRENGTH = 4,000 psi

4. REINFORCING STEEL = ASTM A615, GRADE 60.

5. PROVIDE ADDITIONAL REINFORCING AROUND OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.

6. TRIM OPENING WITH DIAGONAL #4 BARS, EXTEND BARS A MINIMUM OF 12" BEYOND OPENING, BEND BARS AS REQUIRED TO MAINTAIN BAR COVER.

RISER AND RISER REINFORCEMENT




#### Plant Schedule Scientific Name Common Name Quantity Spacing Install Size Deciduous Trees Amelanchier x grandiflora 'Autumn Brillance' PP5,717 Autumn Brillance Serviceberry Per Plan 8' multi-stem B&B CSM Per Plan 2.5" caliper B&B Acer truncatum x Acer platanoides 'JFS-KW202' Crimson Sunset Maple Kentucky Coffee Tree - MALE SPECIES Gymnocladus dioicus - MALE SPECIES Per Plan 2.5" caliper B&B Malus 'Jewelcole' PP3,267 Red Jewel Crabapple Per Plan 1.5" caliper B&B Gleditsia tricanthos 'Skycole' PP1,619 2.5" caliper B&B Per Plan Skyline Honeylocust 2.5" caliper B&B SSM Acer miyabei 'Morton' State Street Miyabei Maple 2.5" caliper B&B SWO Quercus bicolor Swamp White Oak Per Plan Deciduous Shrubs Annabelle Hydrangea Per Plan Hydrange arborescens 'Annabelle' 16 #2 cont. Anthony Waterer Spirea 6 Per Plan #2 cont. AWS Spirea x bumalda 'Anthony Waterer' BF Per Plan #2 cont. Forsythia viridissima 'Bronxensis' Bronx Forsythia CKV Per Plan 3' B&B Vibumum carlesii 'Compactum' Compact Koreanspice Vibumum 103 DBH Per Plan #2 cont. Diervilla lonicera Dwarf Bush Honeysuckle 50 #2 cont. Rosa rugosa 'Dwarf Pavement' Dwarf Pavement Rose Per Plan Spirea x japonica 'Goldmound' Gold Mound Spirea Per Plan #2 cont. 20 3' B&B Cotoneaster lucidus Per Plan Hedge Cotoneaster Aronia melanocarpa 'Morton' 20 Per Plan #2 cont. roquois Beauty Balck Chokeberry LHS Itea virginica 'Little Henry' PP10,988 8 Per Plan #2 cont. Little Henry Dwarf Sweetspire SWN Per Plan 3' B&B Physocarpus opulifolius 'Seward' Summer Wine Ninebark 4' B&B Hamamelis vernalis √ernal Witchhazel 4 Per Plan Evergreen Shrubs 10 Per Plan #3 cont. Juniperus sabina 'Buffalo' Buffalo Juniper Per Plan 5' B&B Juniperus virgiana 'Hillii' Hill Dundee Juniper 4 21 5' B&B Juniperus chinensis 'Iowa' lowa Juniper Per Plan 23 Juniperus chinensis 'Pfitzeriana Kallay' Per Plan #3 cont. Kallays Compact Juniper Perennials 50 Parthenocissus tricuspidata 'Veitchii' Boston Ivy Per Plan 1 gal 48 Dwarf Hameln Fountain Grass Per Plan 1 gal Pennisetum alopecuroies GSG 52 Per Plan Miscanthus sinensis 'Graziella' Graziella Maiden Grass 1 gal 13 Hosta 'Halcyon' Halcyon Hosta Per Plan 1 gal 97 HMS Panicum virgatum 'Heavy Metal' Heavy Metal Switch Grass Per Plan 1 gal 22 Heuchera x 'Palace Purple' Per Plan Palace Purple Coralbell 1 gal 23 Leucanthemum x superbum 'Snowcap' Snowcap Shasta Daisy Per Plan 1 gal PMD Hemerocallis 'Pardon Me' 57 Pardon Me Daylily Per Plan 1 gal SHN Nepeta faassenii 'Six Hills Giant' 12 Per Plan Six Hills Nepeta 1 gal VJS Vera Jameson Sedum 16 Per Plan 1 gal Sedum x 'Vera Jameson' NOTE: Installation contractor is responsible for verifying plant count from plan. Plan quantities take precedence over list.



- 1. ALL PLANT MATERIAL SHALL BE OBTAINED FROM A NURSERY LOCATED IN ZONE 5, CONFORM TO APPLICABLE REQUIREMENTS OF THE CURRENT EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK, AND BOTANICAL NAMES SHALL BE ACCORDING TO THE CURRENT EDITION OF "STANDARDIZED PLANT NAMES PREPARED BY THE AMERICAN JOINT COMMITTEE ON HORTICULTURE NOMENCLATURE.
- 2. CONTRACTOR TO PROVIDE TO THE LANDSCAPE ARCHITECT SAMPLES OF ALL BARK AND MINERAL/STONE MULCHES, DECORATIVE GRAVELS, MAINTENANCE STRIP STONE, OR OTHER GROUND COVER MATERIALS FOR APPROVAL PRIOR TO INSTALLATION.
- 3. BARK MULCH TO BE FRESHLY ACQUIRED HARDWOOD SHREDDED BARK MULCH. NOT DOUBLE MILLED, EXCESSIVE DIRT AND DUST LIKE MATERIAL OR OLD MATERIAL IS NOT ACCEPTABLE.
- 4. LANDSCAPE EDGING TO BE ALUMINUM EDGING. REFER TO SPECIFICATION 32 93 00 PLANTS FOR ADDITIONAL INFORMATION.
- 5. ALL PLANTING AREAS TO RECEIVE A 3-INCH THICK LAYER OF HARDWOOD SHREDDED BARK MULCH WITH PREEMERGENT HERBICIDE AND EDGING. EDGING TO BE INSTALLED BETWEEN DIFFERENT TYPES OF MULCHES, BETWEEN MULCHES AND TURF, AND/OR WHERE SPECIFICALLY NOTED ON THE PLAN. REFER TO SPECIFICATION 32 93 00 PLANTS FOR ADDITIONAL INFORMATION.
- 6. INSTALL SHOVEL CUT EDGE AROUND ALL INDIVIDUAL TREES AND SHRUBS IN LAWN AREAS AND ALONG PAVEMENT WHERE PLANTING AREAS ABUT TO PREVENT HARDWOOD SHREDDED BARK MULCH FROM SPILLING OUT OF
- 7. CONTRACTOR RESPONSIBLE FOR MAINTENANCE OF PLANT MATERIAL FOR 90 DAYS FROM INSTALLATION, INCLUDING WATERING, WEEDING, ETC. CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF SEEDED AREAS FOR 60 DAYS FROM INSTALLATION, INCLUDING WATERING, WEEDING, ETC. CONTRACTOR TO PROVIDE AND REVIEW MAINTENANCE INSTRUCTIONS WITH THE OWNER PRIOR TO THE COMPLETION OF THESE MAINTENANCE PERIODS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- 8. CLEANLY PRUNE AND REMOVE DAMAGED BRANCHES, DEAD WOOD, AND ROOTS IMMEDIATELY PRIOR TO PLANTING. DO NOT CUT LEADERS OR LEAVE "V" CROTCHES OR DOUBLE LEADERS UNLESS A MULTI-STEM TREE IS
- 9. REMOVE BURLAP, WIRE BASKET, ROPE, TWINE, AND ALL SYNTHETIC MATERIAL FROM THE ROOTS, TRUNK, OR CROWN OF PLANT.
- 10. REMOVE EXCESS SOIL ABOVE ROOT COLLAR.
- 11. PLANT TREES AND SHRUBS SO THAT THE ROOT COLLAR IS 2" ABOVE FINISHED GRADE OR SEVERAL INCHES ABOVE GRADE IF PLANT IS INSTALLED IN POOR SOILS.
- 12. PLANT TREES AND SHRUBS WITH SAME ORIENTATION AS WHEN HARVESTED FROM THE NURSERY OR TO SHOWCASE THE MOST AESTHETIC VIEW.
- 13. PLANT ALL TREES WITH THREE SLOW RELEASE FERTILIZER PACKETS, SPACED EQUIDISTANT AROUND THE EDGE OF THE ROOT BALL.
- 14. PLANT ALL SHRUBS WITH ONE SLOW RELEASE FERTILIZER PACKET, PLACED BELOW THE ROOTING SYSTEM.
- 15. WATER AND TAMP BACKFILL AND ROOTS OF ALL NEWLY SET PLANT MATERIAL SO THE SOIL AND ROOTS ARE THOROUGHLY SOAKED AND AIR POCKETS ARE REMOVED.
- 16. FOR INDIVIDUAL TREES & SHRUBS PLANTED IN TURF AREAS, PROVIDE CONTINUOUS 3" SOIL SAUCER TO CONTAIN WATER & MULCH (TREES ON SLOPES SHALL BE SAUCERED ON THE DOWNHILL SIDE)
- 17. INSTALL 3" THICK SHREDDED HARDWOOD BARK MULCH RING 3'-0" DIA. FOR DECIDUOUS TREES AND ALL INDIVIDUAL SHRUBS IN LAWN AREAS, 5'-0" DIA. FOR EVERGREEN TREES. KEEP MULCH 2" AWAY FROM TRUNKS.
- 18. STAKING ONLY STAKE EVERGREEN TREES 5'-0" OR GREATER IN HEIGHT OR TREES THAT ARE UNABLE TO REMAIN UPRIGHT AFTER PLANTING. TREES WILL BECOME STRONGER FASTER WHEN THE TOP 2/3 OF THE TREE IS FREE TO SWAY. DO NOT ATTACH WIRE DIRECTLY TO TREES OR THROUGH HOSES - UTILIZE GROMMETED, SYNTHETIC STRAPS AT LEAST 2" WIDE AROUND THE TREE, ATTACH STRAPPING TO STAKE WITH WIRE. STAKE ONLY WHEN NECESSARY. STAKES SHOULD BE DRIVEN DEEPLY INTO THE GROUND TO PREVENT DISLODGING. CHECK AT LEAST EVERY THREE MONTHS FOR BINDING OR OTHER PROBLEMS. STAKES AND TIES SHOULD BE REMOVED SIX MONTHS TO ONE YEAR AFTER PLANTING.
- 19. REFER TO SPECIFICATIONS 32 93 00 PLANTS AND 32 92 00 TURF AND GRASSES FOR ADDITIONAL INFORMATION.





PREPARE SOIL IN THE ENTIRE BED USING PROCEDURES OUTLINED IN THE SPECIFICATIONS BALLED AND BURLAPPED PLANT CONTAINER PLANT REMOVE PLANT FROM POT.
SET ROOT COLLAR SLIGHTLY SET ROOT COLLAR 2" — ABOVE FINISHED GRADE ABOVE FINISHED GRADE AMM OR PAVING - BEFORE PLANTING, ADD 3" TO 4" OF AMENDMENTS TO BED AND TILL INSTALL MULCH 3" THICK. KEEP 2" AWAY FROM TRUNK. INTO TOP 2" OF PREPARED SOIL RETURN EXISTING SOIL --LOOSEN AND PULL OUT ROOTS TO ROUGHEN SOIL SURFACE TO AMENDED PER SPECS PREVENT PLANT FROM BECOMING BIND EXISTING SOIL WITH NEW ROOT BOUND SOIL AND AMENDMENTS BALL SEATED FIRMLY ON -- BALL SEATED FIRMLY ON SCARIFIED UNDISTURBED SUBGRADE SCARIFIED UNDISTURBED SUBGRADE INSTALL ONE SLOW RELEASE -FERTILIZER PACKETS PER - INSTALL ONE SLOW RELEASE FERTILIZER PACKETS PER SHRUB, SHRUB, BENEATH THE ROOT BALL. BENEATH THE ROOT BALL. **DECIDUOUS & EVERGREEN SHRUB PLANTING** 

SET ROOT COLLAR -

THICK, INCREASE TO

3" THICK OUTSIDE LEAFY CANOPY OF

PERENNIAL

SLIGHTLY ABOVE

FINISHED GRADE

SOIL AMENDED

PER SPECS

RETURN EXISTING -



PROPOSED SCHEMATIC DRAWINGS FOR:

**ADMIRAL'S WHARF** 

234 S WATER ST MILWAUKEE, WI



DATE	REV	ISSUE
	_	
	+	
DRAWINGS	AND SPE	CIFICATIONS AS INSTRUMENT

ARCHITECT/ENGINEER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE PLANS FOR ANY PROJECT OTHER THAN SPECIFICALLY AUTHORIZED BY THEM AND SIGNED AND SEALED FOR SUCH SPECIFIC LOCATION IN THE STATE, PROVINCE, OR TERRITORY SHOWN ON THE

PROJECT NUMBER DATE DRAWN BY

SCALE

SITE LANDSCAPE DETAILS

# MILWAUKEE RIVER (2) GROUND-MOUNT RECESSED LIGHTING FIXTURES. LIGHTING FIXTURES SURFACE MOUNTED TO NEW DOCK -COOPER INDUSTRIES BOCA 696 LED. PROPOSED SCHEMATIC WALL TO PROVIDE LIGHTING ON THE LOWER LEVEL DRAWINGS FOR: REFER TO ARCHITECTURAL PLANS OF THE RIVERWALK. REFER TO ARCHITECTURAL FOR ADDITIONAL INFORMATION. PLANS FOR ADDITIONAL INFORMATION. ADMIRAL'S WHARF 234 S WATER ST MILWAUKEE, WI LIGHT FIXTURES RECESSED IN (2) GROUND-MOUNT CONCRETE PLANTER WALL. RECESSED LIGHTING FIXTURES. (3) LIGHT FIXTURES PER RAMP (TYP.) $\longrightarrow$ COOPER INDUSTRIES BOCA LIGHT FIXTURE PER LANDING (TYP.)-696 LED. REFER TO kapur ARCHITECTURAL PLANS FOR (7) LIGHT FIXTURES ON EXTENDED ADDITIONAL INFORMATION. LANDING CENTERED ON BUILDING. (21) LIGHT FIXTURES TOTAL. LUMENS VITRA HORIZONTAL LED BRICK DATE REV ISSUE 50' RIVER WALK OVERLAY <u>50' RIVER WALK OVERLAY</u> LIGHT. REFER TO ARCHITECTURAL PLANS FOR ADDITIONAL INFORMATION. PROPOSED BUILDING DRAWINGS AND SPECIFICATIONS AS INSTRUMENTS OF SERVICE ARE THE PROPERTY OF VJS CONSTRUCTION SERVICES. THE ARCHITECT/ENGINEER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR THE USE OF THESE PLANS FOR ANY PROJECT OTHER THAN SPECIFICALLY AUTHORIZED BY THEM AND SIGNED 1170764 11/19/2019 DRAWN BY CHECKED BY 1'' = 10'-0''Scale: 1" = 10' RIVERWALK LIGHTING PLAN Dial or (800)242-8511 www.DiggersHotline.com

C3.01