



APPROVED

By Tim Askin - Milwaukee HPC at 1:47 pm, Jun 23, 2021






7 | EXISTING EAST ELEVATION
SCALE: 1/16" = 1'-0"


6 | EXISTING WEST ELEVATION


SCALE: 1/16" = 1'-0"

5 | EXISTING SOUTH ELEVATION

SCALE: 1/16" = 1'-0"







KINN MKE GUESTHOUSE

MILWAUKEE, WI 53202

PROPOSED NORTH ELEVATION

SCALE: 1/16" = 1'-0"

3 | PROPOSED EAST ELEVATION SCALE: 1/16" = 1'-0"

2 PROPOSED WEST ELEVATION

SCALE: 1/16" = 1'-0"

1 PROPOSED SOUTH ELEVATION

SCALE: 1/16" = 1'-0"

13

NATIONAL PARK SERVICE: CONDITIONAL APPROVAL MASONRY NOTES (12/06/19):

- 1. Cleaning of exterior masonry must be accomplished using the gentlest means possible without damaging the surface of the masonry. This work must be accomplished in accordance with the guidance provided in Preservation Brief 1, Assessing Cleaning and Water-Repellent Treatments for Historic Masonry Buildings. Specifications and test cleaning samples should be reviewed and approved by the State Historic Preservation Office before proceeding with this work. Good quality overall and close-up color photographs of the masonry both before and after cleaning must be submitted with the Request for Certification of Completed Work.
- 2. Repointing mortar must match the color, texture, strength, joint width and joint profile of the existing historic masonry. Specifications and repointing samples should be reviewed and approved by the State Historic Preservation Office before proceeding with this work. Good quality overall and close-up color photographs of the masonry both before and after repointing must be submitted with the Request for Certification of Completed Work.

GENERAL NOTES:

- 1. ALL EXISTING NON-HISTORIC SINGLE HUNG WINDOWS TO BE REMOVED & REPLACED WITH NEW ALL-WOOD FRAME PAINTED SINGLE HUNG WINDOWS COMPATIBLE WITH HISTORIC BUILDING. GLAZING TO BE 72% OR GREATER VISIBLE LIGHT TRANSMITTANCE AND 12% OR LESS REFLECTIVITY.
- 2. ALL EXTERIOR MASONRY TO BE RETAINED AND REPAIRED AS NEEDED. IF ANY REPOINTING WORK IS NECESSARY, REPOINTING MORTAR WILL MATCH THE COLOR, COMPOSITION, TEXTURE, STRENGTH, JOINT WIDTH, AND JOINT PROFILE OF THE EXISTING HISTORIC MASONRY. SPECIFICATIONS AND REPOINTING SAMPLES WILL BE REVIEWED AND APPROVED BY SHPO BEFORE PROCEEDING WITH ANY WORK.
- 3. THE CURRENTLY PAINTED EXTERIOR BRICK TO BE REPAINTED. EXISTING BRICK TO BE CAREFULLY SCRAPED TO REMOVE THE CURRENT PAINT.

KEYNOTES:

- 01) REMOVE EXISTING EGRESS STAIR
- REMOVE EXISTING BRICK WALL FOR NEW WINDOW OPENING. INFILL EXISTING OPENING BELOW WINDOW WITH BRICK TO MATCH HISTORIC MASONRY CONFIGURATIONS.
- REMOVE EXISTING NON-HISTORIC ENTRY ARCHWAY, PATCH AND REPAIR CONCRETE AT GRADE
- O4a EXISTING STOREFRONT & ENTRY DOORS TO BE REPLACED WITH NEW ALUMINUM SYSTEM, NON ANODIZED, & PAINTED WOOD DOORS. SEE A3.1 & A3.2.
- 04b EXISTING ALUMINUM STOREFRONT SYSTEM & GLAZING TO BE RETAINED.
- existing stone & Cast-Iron Columns to be retained and protected during construction, Cast-Iron Columns to be repainted
- 06 NEW CANOPY w/ PAINTED NON-ANODIZED METAL FASCIA, SOFFIT TO BE PAINTED T&G WOOD, SEE A3.2

- NEW PAINTED NON-ANODIZED METAL SIGNAGE LETTERING, SEE A3.2
- NEW METAL CLAD ROOF PATIO PARTITION WALL.
- (08b) REPURPOSED MECHANICAL FALL PROTECTION GUARDRAIL, REPAIR AND REPAINT, OR PROVIDE REPLACEMENT (MOST COST EFFECTIVE SOLUTION).
- NEW ALUMINUM WINDOW / DOOR SYSTEM, SEE WINDOW/DOOR SCHEDULE
 - NEW BRICK CLADDING, RUNNING BOND PATTERN, SIZE TO MATCH EXISTING

GLEN-GERY EASTLINE THIN BRICK - STONE GREY (K12-3009) - OR EQ

- NEW FLUSH METAL EXTERIOR WALL CLADDING BRIDGERSTEEL SHIPLAP WALL, FLUSH REVEAL, MATTE BLACK - OR EQ.
- REPAIR MASONRY AT EXISTING STONE WATER TABLE. DUTCHMEN OR PATCHING SAMPLES WILL BE REVIEWED AND APPROVED BY SHPO BEFORE PROCEEDING WITH THE WORK.
- NEW EXTERIOR LIGHTING PER LIGHTING PLAN

ISSUE DATE 80% DD 11.18.19 100% DD 01.20.20 100% CD 03.26.21 A-2 VARIANCE 06.04.21

JUNE 04, 2021

BUILDING ELEVATIONS A3.0

Vettef.


161 south first street, suite 110
milwaukee, wisconsin 53204
414 223 3388 phone
www.vetterdenk.com

APPROVED


By Tim Askin - Milwaukee HPC at 1:47 pm, Jun 23, 2021


STOREFRONT NOTES:

- REPAIR MASONRY AT EXISTING STONE WATER TABLE.
 DUTCHMEN OR PATCHING SAMPLES WILL BE REVIEWED
 AND APPROVED BY SHPO BEFORE PROCEEDING WITH
 WORK.
- 2. STOREFRONT SYSTEM THAT IS TO BE REMOVED IS TO BE REPLACED WITH HISTORICALLY-COMPATIBLE STOREFRONT. NEW STOREFRONT SYSTEM IS TO BE NON-ANODIZED ALUMINUM. GLAZING TO BE 72% OR GREATER VISIBLE LIGHT TRANSMITTANCE AND 12% OR LESS REFLECTIVITY.
- 3. EXISTING STONE & CAST-IRON COLUMNS TO BE RETAINED AND PROTECTED DURING CONSTRUCTION, CAST-IRON COLUMNS TO BE REPAINTED
- NEW CANOPY w/ PAINTED NON-ANODIZED METAL FASCIA, SOFFIT TO BE SOLID STAINED T&G WOOD, STUCCO AS ALTERNATE



4 BUILDING PHOTO - 1906





KINN MKE
KINN MKE
GUESTHOUSE

600 N BROADWAY
MILWAUKEE, WI 53202

 ISSUE
 DATE

 80% DD
 11.18.19

 100% DD
 01.20.20

 100% CD
 03.26.21

 A-2 VARIANCE
 06.04.21

3 | STOREFRONT SECTION

SCALE: 1/4" = 1'-0" (AT SOUTH RETAIL)

2 PROPOSED WEST STOREFRONT

SCALE: 1/4" = 1'-0"


1 | PROPOSED SOUTH STOREFRONT


SCALE: 1/4" = 1'-0"


JUNE 04, 2021

STOREFRONT ELEVATIONS

A3.1







ELEVATION - PROPOSED ENTRY

SCALE: 3/8" = 1'-0"

FURTHER REVIEWED

KINN MKE

GUESTHOUSE

600 N BROADWAY

MILWAUKEE, WI 53202

ISSUE DATE

80% DD 11.18.19

100% DD 01.20.20

100% CD 03.26.21

ALL EXTERIOR

DETAILS TO BE

JUNE 04, 2021

CANOPY ELEVATIONS

A-2 VARIANCE

06.04.21


milwaukee, wisconsin 53204

414 223 3388 phone www.vetterdenk.com

CANOPY ELEVATIONS SECTION DETAILS


A3.2

© COPYRIGHT VETTER DENK ARCHITECTS, INC.





(FOR REFERENCE ONLY, REFER TO 2D DRAWINGS FOR ACTUAL INFORMATION)




SECTION

SCALE: 3/8" = 1'-0"



APPROVED By Tim Askin - Milwaukee HPC at 1:47 pm, Jun 23, 2021



FRESH AIR 7'x7'x6'



ISSUE DATE 80% DD 11.18.19 EXISTING MONO PITCHED ROOF REMOVED 01.20.20 100% DD 03.26.21 100% CD A-2 VARIANCE 06.04.21 JUNE 04, 2021

NORTH ELEVATION

— NEW FLUSH METAL PANELS

EXISTING NEIGHBORING BUILDING

ADDITION ELEVATIONS





DESIGN REVISIONS


- 1. BUILDING HEIGHT REDUCED FROM 77'-6" TO 74'-7"
- 2. BRICK COLOR TONE LIGHTENED
- 3. WINDOWS REDUCED IN HEIGHT TO ALLOW FOR BRICK HEADER








METAL SIDING
BRIDGERSTEEL SHIPLAP WALL, FLUSH
REVEAL, MATTE BLACK - OR EQ.





1 | EAST ELEVATION

SCALE: 1/4" = 1'-0"



MILWAUKEE, WI 53202

 ISSUE
 DATE

 80% DD
 11.18.19

 100% DD
 01.20.20

 100% CD
 03.26.21

 A-2 VARIANCE
 06.04.21

JUNE 04, 2021

ADDITION ELEVATIONS A3 4